



# **MONITORING, OPERATION, AND MAINTENANCE PLAN**

**GENERAL MOTORS POWERTRAIN GROUP  
GMPT BAY CITY PLANT AND CROTTY STREET CHANNEL SITE  
BAY CITY, MICHIGAN**

**JANUARY 2002  
REF. NO. 12610 (11)**

**Prepared by:  
Conestoga-Rovers  
& Associates**

651 Colby Drive  
Waterloo, Ontario  
Canada N2V 1C2

Office: (519) 884-0510  
Fax: (519) 884-0525

web: <http://www.CRAworld.com>

TABLE OF CONTENTS

	<u>Page</u>
1.0 INTRODUCTION.....	1
1.1 PURPOSE AND ORGANIZATION OF PLAN .....	1
2.0 DESCRIPTION.....	2
2.1 REMEDIAL ACTIONS.....	2
2.2 REMEDIAL ACTION PLAN COMPONENTS AND MODIFICATIONS.....	3
2.2.1 SHEET PILE WALL.....	3
2.2.2 MULTI-LAYER CAP .....	3
2.2.3 GROUNDWATER EXTRACTION SYSTEMS .....	4
2.2.4 STORMWATER CONTROL.....	4
3.0 OPERATION AND MAINTENANCE ACTIVITIES.....	5
3.1 EXPOSURE BARRIERS INSPECTION .....	5
3.2 MULTI-LAYER CAP INSPECTION .....	6
3.3 CONTAINMENT SYSTEMS INSPECTION.....	7
3.4 GROUNDWATER EXTRACTION SYSTEMS INSPECTIONS.....	8
3.5 O&M TASKS FOR GROUNDWATER EXTRACTION SYSTEMS.....	9
3.5.1 O&M LOG.....	9
3.5.2 EXTRACTION WELL WATER LEVELS .....	9
3.5.3 EXTRACTION WELL INSPECTION .....	10
3.5.4 EXTRACTION WELL PUMP MAINTENANCE .....	10
3.5.5 GROUNDWATER LEVEL TRANSMITTER MAINTENANCE AND INSPECTION.....	10
3.5.6 FLOWMETER MAINTENANCE AND INSPECTION .....	11
3.5.7 CONTROL PANEL MAINTENANCE AND INSPECTION .....	11
3.5.8 AIR SUPPLY MANIFOLD.....	11
3.5.9 LAGOON AREA AIR COMPRESSOR INSPECTION AND MAINTENANCE .....	11
3.5.10 HEATER INSPECTION .....	12
3.5.11 EAST LAGOON SUMP PUMP INSPECTION AND MAINTENANCE ..	12
3.6 STORMWATER COLLECTION SYSTEM INSPECTIONS.....	12
3.6.1 STORMWATER TREATMENT SYSTEM.....	13
3.6.2 ARCHIMEDES SCREW PUMPS .....	13
3.6.3 CROTTY STREET 66-INCH SEWER.....	14
3.7 STAFF GAUGES AND MONITORING WELLS INSPECTION .....	14
3.8 REPORTING.....	14
4.0 GROUNDWATER AND STORMWATER MONITORING PROGRAM .....	15
4.1 OVERVIEW .....	15
4.2 MONITORING WELL SAMPLING.....	15
4.2.1 OVERVIEW .....	15

TABLE OF CONTENTS

	<u>Page</u>
4.2.2	HYDRAULIC MONITORING ..... 15
4.2.3	GROUNDWATER QUALITY MONITORING ..... 16
4.2.3.1	LOCATION ..... 16
4.2.3.2	SCHEDULE ..... 17
4.2.3.3	ANALYTICAL PARAMETERS ..... 17
4.2.4	GROUNDWATER SAMPLING PROCEDURES..... 17
4.2.5	DATA EVALUATION AND REPORTING ..... 19
4.3	STORMWATER MONITORING..... 19
5.0	REPORTING ..... 20
5.1	OPERATION AND MAINTENANCE ACTIVITIES ..... 20
5.2	GROUNDWATER SAMPLING..... 20
5.3	STATIC WATER LEVEL MONITORING ..... 20
5.4	STORMWATER MONITORING ..... 20
5.5	CONTINGENCY PLANS ..... 21
5.6	SITE MODIFICATIONS..... 21
5.7	ARCHIMEDES SCREW PUMP SYSTEM SHUTDOWN ..... 21
6.0	INSTITUTIONAL CONTROLS..... 22
6.1	PURPOSE OF INSTITUTIONAL CONTROLS..... 22
6.2	IMPLEMENTATION OF INSTITUTIONAL CONTROLS ..... 22
7.0	SITE HEALTH AND SAFETY PLAN..... 24
8.0	QUALITY ASSURANCE..... 25
9.0	RESPONSIBILITY..... 26

LIST OF FIGURES  
(Following Text)

FIGURE 1.1	SITE LOCATION
FIGURE 1.2	SITE PLAN
FIGURE 3.1	LIMITS OF DEED RESTRICTIONS
FIGURE 3.2	EXTRACTION WELL LOCATIONS
FIGURE 3.3	PUMP MAINTENANCE
FIGURE 4.1	MONITORING WELL LOCATIONS AND GROUNDWATER CONTOURS - AUGUST 13, 2001

LIST OF TABLES  
(Following Text)

TABLE 3.1	SUMMARY OF STORMWATER SYSTEM MAINTENANCE ACTIVITIES
TABLE 4.1	MONITORING WELL COMPLETION DETAILS AND GROUNDWATER ELEVATIONS
TABLE 4.2	SUMMARY OF LONG-TERM GROUNDWATER AND STORMWATER MONITORING ACTIVITIES
TABLE 5.1	REPORTING REQUIREMENTS
TABLE 8.1	ANALYTICAL PARAMETERS

LIST OF APPENDICES

APPENDIX A	OPERATION, MAINTENANCE, AND MONITORING FORMS
APPENDIX B	MONITORING AND EXTRACTION WELL LOGS
APPENDIX C	MANUFACTURER PRODUCT INFORMATION
APPENDIX D	HEALTH AND SAFETY PLAN
APPENDIX E	HISTORICAL GROUNDWATER DATA
APPENDIX F	AS-RECORDED DRAWINGS

## **1.0 INTRODUCTION**

A generalized Monitoring, Operation, and Maintenance (O&M Plan) Plan was submitted to Michigan Department of Environmental Quality (MDEQ) as part of the Remedial Action Plan (RAP), for the General Motors Powertrain Group, Bay City Plant (GMPT Plant Site), Bay City, Michigan. The Site location is presented on Figure 1.1.

The Site-specific Monitoring, Operation and Maintenance (O&M Plan) Plan presented herein is a continuation of the previous document detailing inspection and maintenance programs for specific aspects of the RAP, and is being submitted subsequent to the completion of the Remedial Action (RA) for the GMPT Plant Site and the Crotty Street Channel Site (Sites).

### **1.1 PURPOSE AND ORGANIZATION OF PLAN**

The purpose of the O&M Plan is to provide a synopsis of the remedy and certification of the design and construction including the monitoring, operation, and maintenance requirements for the RA implemented at the Sites. The O&M Plan is organized as follows:

- Section 1.0 presents a general introduction to the Site and the purpose and organization of the O&M Plan;
- Section 2.0 presents a description of the remedial actions for the Sites, including an explanation of any modifications to the plans and why these were necessary;
- Section 3.0 presents the Site operation and maintenance activities;
- Section 4.0 presents the groundwater monitoring program;
- Section 5.0 presents the reporting requirements;
- Section 6.0 presents the institutional controls;
- Section 7.0 presents the Site Health and Safety Plan for long-term operation, maintenance, and monitoring activities; and
- Section 8.0 presents the Site Quality Assurance Project Plan, including sampling and analysis procedures, for the long-term Site monitoring requirements.

## **2.0 DESCRIPTION**

A RAP for the GMPT Plant Site, Bay City, Michigan was submitted and approved by the MDEQ. A RAP was also submitted for the Crotty Street Channel Site. The Crotty Street RAP was also approved by the MDEQ. The Crotty Street RAP modified several components of the GMPT Plant Site RAP. An amendment to the Plant Site RAP was submitted to the MDEQ and approved. Other components of the RAP have been modified during construction based on field conditions. These modifications, which are outlined in Section 2.2 are the only modifications to the original approved RAP. All other Remedial Actions have been implemented as approved by the MDEQ.

## **2.1 REMEDIAL ACTIONS**

The implemented remedial actions at the Sites are as follows:

- multi-layer cap;
- sheet pile wall;
- three groundwater extraction systems: Lagoon Area (LA), Machine Storage Area (MSA), and Crotty Street Channel Containment Area (CSC);
- existing stormwater collection systems modification;
- soil excavation;
- sediment removal or stabilization;
- lagoon liner replacement;
- paving;
- institutional controls;
- fencing;
- groundwater monitoring; and
- operation and maintenance.

The remedial actions will be maintained as described in this report. In addition, groundwater monitoring will be conducted as described in this report. The monitoring, operation, and maintenance activities described herein will be conducted for as long as chemicals pose a risk to public health, safety, welfare, and the environment. Monitoring, operation, and maintenance activities will be reassessed at least every 5 years.

## **2.2 REMEDIAL ACTION PLAN COMPONENTS AND MODIFICATIONS**

The following sections described the remedial action components and modifications to the original GMPT Plant Site RAP due to the Crotty Street RAP and field conditions.

### **2.2.1 SHEET PILE WALL**

The proposed location of the sheet pile wall in the GMPT on-Site RAP has been modified as follows. Beginning at the northern end of the Machine Storage Area (MSA), the wall was keyed into the MSA deep soil mixing (DSM) wall prior to leaving the shoreline in a westward direction. The sheet pile wall extends in a westerly direction across the mouth of the Crotty Street Channel, continuing west to within close proximity to the Crotty Street Property line continuing south down the west side of the Crotty Street Property, and then turns east and connects to the DSM wall on GM Property (As Recorded Drawing S-02AR).

The sheet pile wall across the mouth of the channel is of dual wall construction for structural stability. The backfill between the walls is clean imported clay. The remainder of the sheet pile wall down the west and south sides of the Crotty Street Property is a single wall. The design life of the sheet pile wall is 40 years.

The sheet pile wall was modified to include the Crotty Street Channel Containment Area. Across the mouth of the channel the piling has been extended to a depth of 55 feet with a top-of-wall elevation of 588 feet above mean sea level (AMSL).

### **2.2.2 MULTI-LAYER CAP**

A multi-layer cap has been placed over the area contained by the sheet pile wall, and the MSA DSM wall. The cap will reduce stormwater infiltration and prevent direct contact to underlying soil. The cap is graded to direct stormwater runoff to two stormwater collection inlets on the western side of the MSA on the GMPT Plant property. The cap primarily covers the MSA and the Crotty Street Channel Property (As-Recorded Drawing C-08AR).

Two fuel tanks have been removed from the eastern portion of the MSA and the modified cap in this area has been graded and replaced with the typical multi-layer cap.

### **2.2.3 GROUNDWATER EXTRACTION SYSTEMS**

In addition to the lagoon area (LA) and machine storage area (MSA) groundwater extraction systems required in the GMPT Plant Site RAP, a groundwater extraction system consisting of three sumps was constructed in the Crotty Street Channel containment area and discharges into the GMPT on-Site MSA groundwater extraction system. The LA groundwater extraction system consists of five extraction wells that discharge to the lagoons. The MSA groundwater extraction system consists of seven extraction wells that discharge to storm manhole ST-41, which then directs extracted water to the GMPT on-Site stormwater treatment plant (As-Recorded Drawing C-05AR). All waters (surface water and extracted groundwater) from the Crotty Street Channel are directed to the GMPT stormwater treatment plant via the GMPT on-Site MSA groundwater extraction system.

All extraction pumps in the MSA and LA are equipped with scale free units produced by Nexteq to reduce scaling due to high iron concentrations.

### **2.2.4 STORMWATER CONTROL**

Stormwater from the MSA and Crotty Street Channel is directed to the swale along the western edge of the GMPT MSA by sheet flow and swales. This required an extension to the grading proposed in the GMPT on-Site RAP to include all surfaces over the Crotty Street Channel. The multi-layer cap over the MSA and the Crotty Street Channel is graded so that surface water flows are directed to two stormwater collection inlets in the MSA (As-Recorded Drawing C-08AR). Surface water that infiltrates through the soil layer of the cap will drain via the geonet layer, and collect in the two stormwater inlets. Collected stormwater is routed to the GMPT on-Site stormwater treatment plant where it will be treated and used as non-contact cooling water or discharged to the river under NPDES permit MI0001121.

### **3.0 OPERATION AND MAINTENANCE ACTIVITIES**

The monitoring, operation, and maintenance activities at the Site are related to the exposure barriers (e.g., paving, or clay barriers), multi-layer cap, containment systems (e.g., deep soil mixing walls or sheetpiling), groundwater extraction systems, fences institutional controls, and monitoring wells and staff gauges.

#### **3.1 EXPOSURE BARRIERS INSPECTION**

Exposure barriers in conjunction with land use restrictions [which have been placed on impacted, subsurface soils and sediments located in the MSA, LA, Inlet Slip (IS), Support Facilities Area (SFA), and Crotty Street Channel Containment Area (CSC)], are designed to prevent human exposure to these materials. As part of Site inspection activities, each of the above-mentioned areas will be field-inspected for any signs of trespassing or disturbance that may have exposed subsurface soils or sediments. Disturbances to be observed during field inspections include impairment to new or existing pavement, grading, trenching, or excavating activities, or erosion of soils in restricted areas. In the IS, the field inspection will look for dredging or any other activities that may have impacted subsurface sediments. A maintenance activity checklist will document each Site field inspection. The checklist is presented in Appendix A along with all other Operation, Maintenance, and Monitoring forms. The checklist may be updated periodically as appropriate. Follow-up actions will be performed as visual inspections deem necessary.

Surface soil and pavement capping will be visually assessed during each Site inspection performed during the post-closure period to determine if any areas have been disturbed. The inspector will walk each area to check for signs of trespassing or disturbances such as unusual settlement, holes, tire tracks, or signs of digging. In areas where remedial actions included excavation and backfill, the backfilled area will be inspected to ensure fill is not eroded. Pavement in the SFA will be inspected for signs of cracking and integrity of caulked joints.

Pavement, backfill, and surface soil capping will be maintained as visual inspections deem necessary. If eroded or exposed areas are found, additional fill material will be placed to ensure continued protection from subsurface soils. In areas where the pavement has deteriorated, the area will be repaired in a timely manner during the construction season.

In addition, the UA will be inspected semi-annually to confirm the restrictions are being followed.

The City of Bay City's O&M obligations, as associated with the RAP for the UA are the following:

1. do not dig or disturb the soil in areas identified as areas not to be disturbed on Figure 3.1 without appropriate notifications, approvals by MDEQ, and Due Care;
2. do not drink or otherwise contact the groundwater;
3. notify GM of any intrusive work activities (disturbing of soil or digging) in the areas not to be disturbed in the UA at least 20 days prior to planned commencement, and shall endeavor to timely notify GM of any such activities in other portions of the UA;
4. maintain permanent markers on the fence;
5. allow GM access to perform inspections, groundwater monitoring and fence repairs;
6. do not disturb fences on the west and south sides of the parcel; and
7. comply with the Declaration of Restrictive Covenant as it applies to the UA.

### **3.2 MULTI-LAYER CAP INSPECTION**

Land use restrictions placed on the multi-layer cap system located in the MSA and the CSC are designed to restrict any activities that might impair the integrity of the multi-layer cap. The multi-layer cap constructed in this area is designed to prevent direct contact exposure to subsurface soils, provide containment of subsurface soils, and minimize surface water infiltration. Inspection and maintenance of the multi-layer cap will maintain the integrity of the multi-layer cap system, which consists of the following layers (bottom to top):

- grading layer;
- 6-inch sand bedding;
- 40-mil HDPE liner;
- Geonet layer for subsurface drainage;
- 12-inch sand layer; and
- 6-inch vegetated, topsoil cover.

To assure the integrity of the cap, the condition of the multi-layer cap will be visually assessed during each Site inspection performed during the post-closure period to determine, if any, the extent of settlement, evidence of erosion or other disturbances, presence of stressed vegetation, and existence of a uniform vegetative growth. All permanent erosion control features will be monitored to ensure that they are serving the intended purpose.

Cap maintenance will be conducted as visual inspections deem necessary throughout the post-construction period and may include regrading, filling in animal burrows, and repairing settled or eroded areas. This work may include but is not limited to placement and compaction of fill in areas which have settled and are causing water to pond on the cap; repair and replacement of sections of HDPE liner which may have been impaired due to settlement or breaches in the material; and restoration of topsoil and vegetative cover including fertilizing disturbed areas and seeding the cap. Erosion and sediment control features will be maintained as needed during the post-construction period. Maintenance includes the removal of excess siltation and debris that may build up in the stormwater runoff channel or inlets.

### **3.3 CONTAINMENT SYSTEMS INSPECTION**

Land use restrictions were placed on the areas where the containment structures are located (MSA, LA, CSC, and IS). These are designed to restrict any activities that may impair the integrity of the containment systems located in these areas. These containment systems include the Deep Soil Mixing Walls, Sheet Piling installed along the Saginaw River and west side of the Crotty Street Channel, and the Inlet Slip Isolation Wall.

Two separate Deep Soil Mixing Walls surround both the perimeter of the MSA and the perimeter of the LA to physically isolate soil and groundwater in these areas from the remainder of the GMPT Site and also from the adjacent Saginaw River. Both Deep Soil Mixing Walls extend into, and were completed within, the laterally persistent Clay Till that underlies the entire GMPT Site.

Tight-joint sheet piling was installed along the banks of the Saginaw River around the perimeter of the CSC and the LA and across the IS. The sheet piling is a minimum 27 feet long, extending from at least 2 feet into the intermediate confining unit to a top-of-wall elevation of 588 feet AMSL, except across the Crotty Street Channel mouth where the piling is 55 feet long with a top of wall elevation of 588 feet.

The condition of the sheet piling will be visually assessed during each Site inspection performed to look for signs of deterioration, rusting, deformation, excessive movement or visible leakage. All unusual sightings will be noted on the inspection log. Maintenance will be conducted as inspections deem necessary to maintain the integrity of the containment systems.

### **3.4 GROUNDWATER EXTRACTION SYSTEMS INSPECTIONS**

Groundwater extraction systems installed within the areas contained by the Deep Soil Mixing (DSM) Walls in the MSA, in the LA, and within the area contained by the DSM wall and the sheetpile wall in the CSC are designed to reduce groundwater levels within each containment area and to maintain an inward hydraulic gradient. Both groundwater extraction systems are automated and operate when groundwater rises above a pre-set level and continues to operate until groundwater is below the pre-set level. The pump in each well is activated when the water level within the well reaches a certain elevation. All pumps have been set as deep as possible within each extraction well. These levels will be monitored remotely by water level indicators placed in monitoring well MW-1S in the MSA, LMW-2S in the LA; and MW-300S in the CSC. Each air operated extraction pump located in the MSA, LA and CSC systems will independently automatically start if the water level in the well rises above the pre-set level. As part of Site inspection activities, the groundwater extraction systems will require periodic inspections to ensure proper operation of pumps and controls. All O&M activities related to the groundwater extraction systems should be recorded in the O&M log. A copy of the log is presented in Appendix A.

The extraction systems consist of 15 shallow groundwater extraction wells (EW1 - EW15), five in the LA system (EW1 – EW5), seven in the MSA system (EW6 – EW12), and three in the CSC system (EW13 - EW15) as presented on Figure 3.2. Stratigraphic logs and well completion details for the extraction wells are presented in Appendix B. As-recorded, drawing C-08AR presents the locations of the extraction wells. The shallow extraction wells are screened at depths of 5 to 19 feet below ground surface in the shallow sand/fill. From the extraction wells, pump discharge lines are connected to a header pipe. Extracted groundwater from all systems discharges to the stormwater system for subsequent treatment at the GMPT on-Site stormwater treatment plant using sand filters then granular activated carbon filters. The end-of-pipe treatment system, is regularly inspected as part of an existing ongoing O&M program.

The groundwater extraction systems will be inspected in accordance to the frequency as outlined in Appendix A to ensure the system is operating properly. During each

groundwater monitoring event, water levels will be recorded from the shallow monitoring wells in the MSA, LA, and CSC. Water levels will also be measured at all extraction wells to ensure that groundwater levels are being maintained below the pre-set water level. Additionally, the daily volume of groundwater collected from CSC, MSA, and LA extraction systems will be recorded. If there is an excessive and consistent increase in the amount of groundwater collected which cannot be attributed to maintenance or seasonal fluctuation, then a plan will be submitted to determine the cause.

System maintenance will be performed as specified in the respective manufacturer's systems manual and/or as visual inspections deem necessary. Maintenance activities may include such activities as cleaning and repairing or replacing parts in the pumping, piping, and air supply systems.

### **3.5 O&M TASKS FOR GROUNDWATER EXTRACTION SYSTEMS**

The following sections are a detailed description of data collection and documentation, and extraction well components which will require inspection and maintenance.

#### **3.5.1 O&M LOG**

The O&M log is to be completed each Site visit documenting data collection, maintenance, and visual observations. Copies of the O&M log are to be maintained on Site by technical staff as well as an office copy forwarded to Project Management for review and analysis of collected data.

#### **3.5.2 EXTRACTION WELL WATER LEVELS**

Water levels from the 15 extraction wells are to be recorded, as required to evaluate system operation, using a QED PRO MODEL 6000 static water level or equivalent to an accuracy of  $\pm 0.01$  feet. Manufacturer product information is enclosed in Appendix C1. Pump elevation is to be adjusted accordingly to ensure an optimum operation. All collected data and adjustments are to be recorded in the O&M log.

### **3.5.3 EXTRACTION WELL INSPECTION**

Extraction well vaults will be checked for deterioration of the structure, lids, system piping and any and all system components. Observation will be noted in the O&M log and any repairs will be made in a timely basis.

### **3.5.4 EXTRACTION WELL PUMP MAINTENANCE**

The pumps in extraction wells are air driven pneumatic pumps, specifically QED model SOLO. Compressed air from the GMPT Plant is utilized for the pneumatic pumps in the MSA and CSC, and a compressor in the Raw Water Pump Station (RWPS) is utilized for the pumps in the LA. In conjunction with this, a Drypoint compressed air membrane dryer is used in the LA to ensure proper moisture content of the compressed air. Nexteq Scale free units, have been installed at each extraction well to ensure no scale buildup due to iron and hard water. Manufacturer production information for the QED SOLO, Drypoint Type Dryer, and Nexteq scale free unit are enclosed in Appendix C2, C3, and C4, respectively, as well as other extraction system components.

Pump maintenance will be completed as necessary. Observations will be noted in the O&M log including presence of iron accumulation, product, silt and any deterioration of the pump, hoses, fittings, and other appurtenances. Pump maintenance is to be conducted by service personnel in a safe and orderly manner, as outlined on Figure 3.3, wearing proper PPE and using appropriate tools. Waste, rinse water, spent solution and new solution is to be stored in appropriate containers with proper labeling. Storage and work areas are to be properly identified and secured, as necessary, to protect non O&M personnel. Disposal of pump maintenance by-products will be coordinated by O&M personnel.

Manufacturer product information for appurtenances of the extraction well system is included in Appendix C5 (Union ball check valves), C6 (transformer, disconnect and circuit breakers) and C7 (tubing).

### **3.5.5 GROUNDWATER LEVEL TRANSMITTER MAINTENANCE AND INSPECTION**

The groundwater level transmitter is a Druck PTX 1830 submersible depth/level transmitter, coupled with a Druck STE 110 sensor termination enclosure. Product information is enclosed in Appendix C8. Visual inspection will be conducted by

removing protective cover and checking for any physical impairments and for the indicator color of the desiccant module. Blue indicates normal operation, pink indicates a saturated condition and required maintenance. Desiccant modules will be replaced, as necessary.

### **3.5.6 FLOWMETER MAINTENANCE AND INSPECTION**

The Krohne Altflux Model IFM 4080K magnetic flow meter was chosen to record flow volumes from the extraction wells, coupled with the Krohne IFC 090K signal convertor. Manufacturer product information is enclosed in Appendix C9. Inspection of the flowmeters and appurtenances is to be conducted by visually checking for level connections and property display and outputs. Meter calibration will be checked and reported at 6 month intervals. The system will be shut down and the meter zeroed.

### **3.5.7 CONTROL PANEL MAINTENANCE AND INSPECTION**

Visual inspection of the control panel will be conducted by opening the well vault cover and checking for physical impairments. An integral part of the Control Panel is the Sensaphone 2000 by Phonetics; Manufacturers product information for the enclosed in Appendix C10. Data logged by the Sensaphone 2000 (including depth to groundwater and extraction well flow volumes) will be faxed on a weekly basis. Maintenance for the Sensaphone 2000 includes replacement of batteries and repair of faulty connections as necessary.

### **3.5.8 AIR SUPPLY MANIFOLD**

Inspection of the air supply manifold will be visual for leaks and proper operation. Maintenance will require filter change outs as required.

### **3.5.9 LAGOON AREA AIR COMPRESSOR INSPECTION AND MAINTENANCE**

Quincy Compressor Model QT-5 was installed in the LA for the extraction well system. Manufacturer product information is attached in Appendix C11. Visual inspection of the air compressors will include checking for leaks, oil level, and operation pressure and dryer operation. Maintenance will be routine oil and air filter changes as recommended

by the manufacturer. Inspection and maintenance of the LA air compressors is currently completed by GMPT Plant staff.

### **3.5.10 HEATER INSPECTION**

Visual inspection will be conducted during operating season for proper heater functioning. Manufacturer product information is enclosed in Appendix C12.

### **3.5.11 EAST LAGOON SUMP PUMP INSPECTION AND MAINTENANCE**

Inspection will be a visual inspection for operation and flow. Maintenance will involve cleaning pump and level switches when reduction of flow is detected.

## **3.6 STORMWATER COLLECTION SYSTEM INSPECTIONS**

The storm sewer and recirculation system were identified as pathways for groundwater to exit the SFA and as the main contributors to dewatering of this area. Storm sewer lines and collected groundwater feed into the stormwater sewer pump lift station located south and west of the West Lagoon, from where collected water is lifted to the lagoons for storage and subsequent treatment at the GMPT on-Site Stormwater Treatment Plant. The end-of-pipe stormwater treatment system is regularly inspected as part of an ongoing O&M program by GM Plant personnel.

As part of the remedial action, changes in the MSA altered preexisting grades and changed stormwater runoff patterns. A new drainage channel and two stormwater inlets were installed adjacent to the Deep Soil Mixing Wall between the MSA and CSC. The multi-layer cap over the MSA and Crotty Street Channel is graded so that stormwater flows are directed by sheet flow and swales to the newly installed stormwater collection inlets. From the new stormwater collection inlets, stormwater will flow by gravity to the existing storm manhole ST-41 (located in the northwest corner of the SFA).

The condition of these stormwater collection inlets and storm manhole ST-41 will be inspected during Site inspection activities. Evidence of debris or excessive siltation or any damaged or crushed piping will be recorded. Maintenance will be performed as needed. Any collection system piping that has been crushed or damaged will be

replaced. Debris and excessive siltation will be removed from the culverts and drainage channels.

### **3.6.1 STORMWATER TREATMENT SYSTEM**

Stormwater treatment system maintenance is being performed on a routine basis. This includes maintenance of all mechanical and electrical components of the system, all meters associated with the operation of the system, and the multi media sand filters and GAC contactors.

Maintenance of mechanical and electrical components of the system is summarized in Table 3.1. All meters associated with operation of the system are calibrated and inspected in accordance with manufacturer's specifications.

Each month the sand level within one filter is inspected. Sand is added to the filter as needed.

The multi-media sand filters are backwashed due to any of the following:

- Differential pressure cross filter reaches the maximum allowable;
- Effluent turbidity reaches the maximum allowable; or
- A set time since last backwash has been reached.

Sand filters are typically air scoured and backwashed with water.

GAC contactors are backwashed when the differential pressure across a contactor bed reaches the maximum allowable. The GAC contactors are manually air scoured and backwashed with water.

### **3.6.2 ARCHIMEDES SCREW PUMPS**

Groundwater in and around the SFA flows toward the stormwater sewer pump lift station located south and west of the LA. Although the stormwater collection and sewer pump lift system was not originally intended as a groundwater remediation system, groundwater elevation data obtained at various times of the year support, on a consistent basis, the effectiveness of the existing stormwater collection and pumping system in providing year-round elimination of any groundwater migration potential. The stormwater sewer pump lift station located south and west of the LA will be inspected during Site inspections.

GM will provide verbal notification to the MDEQ within 2 business days followed by written notification within 7 days if the Archimedes screw pump system is shut down for any reason. The notification will specify, as appropriate, how the problem will be addressed and an implementation schedule.

### **3.6.3 CROTTY STREET 66-INCH SEWER**

A 66-inch sewer pipe which previously discharged into the Crotty Street Channel has been blocked upstream from the channel, leaving a section of isolated sewer pipe. This sewer pipe will be inspected monthly to ensure no build up of water occurs. The results of the inspection are recorded on the maintenance activity checklist found in Appendix A. If a water buildup does occur, the water will be pumped to the on-Site stormwater treatment plant or containerized and treated off Site.

### **3.7 STAFF GAUGES AND MONITORING WELLS INSPECTION**

During each monitoring event, monitoring wells will be inspected for signs of damage or wear and tear such as rusted or broken locks or bent well casings. Signs of an inadequate seal, such as a cracked or mounded concrete pad, a missing well cap, or a loose cover will also be noted. Additionally, total depths will be collected to check for signs of silting or erosion of the well screen. Any unusual conditions will be noted in the field notebook. An effort will be made to repair or replace any damaged item. If there is evidence of tampering or damage which could impair sample integrity, the well will not be sampled. Staff gauges and monitoring wells must be inspected and replaced if any damage occurs which makes them unusable.

### **3.8 REPORTING**

A report summarizing Site inspection and maintenance activities shall be prepared by REALM and submitted to the MDEQ semi-annually for the first 2 years and annually for another 28 years. After this period of time, the plan will be re-evaluated but monitoring and O&M activities will continue until contaminants on Site no longer exceed applicable criteria. The semi-annual/annual reports will be provided, in accordance with the Consent Judgment.

The report shall document the results of the Site inspection and any necessary maintenance/repair activities. Appendix A provides a summary of O&M tasks.

## **4.0 GROUNDWATER AND STORMWATER MONITORING PROGRAM**

### **4.1 OVERVIEW**

Groundwater and stormwater monitoring will be undertaken at the Site in order to ensure that materials are not migrating off-Site. Groundwater and stormwater monitoring will be conducted to monitor the effectiveness of the implemented remedial actions in the MSA, LA, PB, Outer PB, SFA, and CSC.

### **4.2 MONITORING WELL SAMPLING**

#### **4.2.1 OVERVIEW**

The purpose of the groundwater monitoring program is to monitor groundwater quality, and to evaluate the performance of remedial actions.

The groundwater monitoring program will be re-evaluated every 5 years and will consist of the following components:

- i) hydraulic monitoring (all monitoring wells and staff gauges); and
- ii) groundwater quality monitoring (33 selected monitoring wells).

The monitoring program will continue for the same duration as O&M activities continue for the Site. The following subsections identify the scope of work anticipated for each monitoring component.

#### **4.2.2 HYDRAULIC MONITORING**

Groundwater and staff gauge elevations will be determined on a monthly basis for 2 years (March, 1999 to March, 2001) and during groundwater sampling activities thereafter, for 59 monitoring wells and five staff gauges. The purpose of the hydraulic monitoring program is to evaluate the performance of groundwater containment remedial actions. This includes the groundwater extraction systems and the stormwater collection system. Figure 4.1 shows long-term monitoring well locations, staff gauge locations and shallow groundwater contours measured October 31, 2000. Monitoring well logs for these wells are presented in Appendix B.

For every hydraulic monitoring event, the following procedures will occur and be recorded for each of the above mentioned wells and staff gauges:

1. Monitoring wells will and staff gauges be inspected for signs of damage or wear and tear. If there is evidence of tampering or damage that could impair the ability to accurately measure the static water level, the water level within the well will not be measured, and all corrective measures will be taken to repair the damaged well.
2. Static water level measurements will be taken using an electronic water level indicator to a precision of 0.01 feet. The depth to water will be referenced from the top of the riser pipe. Each measurement will be converted into a mean sea level elevation.
3. The number of Archimedes screw pumps operating at the time of the event will be noted.

All static water level measurements for an event will be taken within a 24-hour period.

Groundwater elevations and staff gauge elevations will be plotted to define the horizontal and vertical flow patterns. Shallow groundwater contours are presented on Figure 4.1.

The monitoring well completion details and groundwater elevations are presented in Table 4.1. Table 4.2 presents the frequency of hydraulic monitoring.

### **4.2.3 GROUNDWATER QUALITY MONITORING**

The groundwater quality monitoring program includes 33 monitoring wells and is summarized in Table 4.2.

#### **4.2.3.1 LOCATION**

Monitoring well sampling will consist of both shallow aquifer groundwater and deep sand aquifer groundwater. The proposed wells for groundwater sampling are presented in Table 4.2. Monitoring well logs for these wells are presented in Appendix B. Historical groundwater analytical data is presented in Appendix E.

#### **4.2.3.2**     **SCHEDULE**

The groundwater monitoring program will continue for 27 years. The first event took place prior to commencing construction activities (March 1999). The second event was completed upon completion of remedial action activities (September 2000). Subsequent events will take place every 6 months for the next year (until September 2001), then annually for the remaining 25 years. The program will be re-evaluated at least every 5 years. The parameter list, number of monitoring wells and their locations, frequency of sampling, and program necessity will be evaluated.

Monitoring reports will be prepared and submitted to the State within 60 days after receipt of analytical data from the sampling event.

#### **4.2.3.3**     **ANALYTICAL PARAMETERS**

All groundwater samples collected will be analyzed for polychlorinated biphenyls (PCBs). In addition, wells in the LA will be analyzed for volatile organic compounds (VOCs) and wells in the UA will be analyzed for metals. The analytical parameters for each well are detailed in Table 4.2.

#### **4.2.4**        **GROUNDWATER SAMPLING PROCEDURES**

Groundwater samples will be collected immediately following development or purging. All sampling equipment will be cleaned, prior to use.

All monitoring wells will be sampled according to the following protocols:

1.     New disposable latex gloves will be used when sampling each well.
2.     The sampler will measure and record the depth to water in each well to the nearest 0.01 foot using an electric tape. The electric tape will be cleaned prior to use in each well.
3.     Standing water will be purged with a low flow pump designed for a flow rate between 0.1 L/min and 0.5 L/min, with a maximum drawdown of 0.3 feet. Temperature, pH, conductivity, turbidity, and DO will be recorded every ten minutes of purging until each water quality parameter has stabilized for three consecutive readings, and the water is deemed to be silt free. All waste groundwater not used for sampling will be treated in the GMPT on-Site stormwater treatment facility. Calibration of field instruments will be

undertaken prior to each sampling event or at the beginning of the day. In the event that a well is purged dry at a rate of 0.1 L/min, groundwater will be permitted to recover to a level sufficient for sample collection.

4. After purging, water samples will be collected using either a peristaltic pump or bladder pump with polyethylene tubing, except where samples will be analyzed for VOCs. Where VOCs will be analyzed, bladder pumps and dedicated teflon coated tubing will be used. Groundwater samples will be taken in appropriately preserved, laboratory supplied containers, using the appropriate pump with a flow rate between 0.1 L/min and 0.5 L/min.
5. Each pump will be cleaned prior to each use. The cleaning procedure consists of washing with distilled water and Alconox detergent, rinsing with distilled/deionized water, and air drying.
6. Containers for sample collection and preservation requirements will be determined as required by the analytical parameters. All sample bottles will be provided by the laboratory and will be prepared using standard laboratory validated washing procedures. The sample bottles will be delivered to the Site in sealed containers. The containers will be labeled with the sample ID, date, time, analysis requested, preservative added, and sampler's initials.
7. A blind field duplicate sample will be collected at a minimum frequency of 1 in 10 groundwater samples.
8. Samples for matrix spike/matrix spike duplicate analysis will be collected at a minimum frequency of 1 per 20 samples.
9. A rinsate blank sample will be collected at a minimum frequency of 1 in 10 groundwater samples. The rinsate sample will consist of deionized water pumped through and then sampled out of, a cleaned pump. This will provide a quality assurance check on the field decontamination procedures employed on the pumps.
10. All disposable gloves, and other solid waste materials will be placed in an appropriate landfill. All decontamination fluids will be treated in the GMPT on-Site stormwater treatment plant.
11. All samples will be placed in a cooler that maintains a temperature of approximately 4°C. Chain-of-custody forms will be completed in the field and will accompany the sample shipment to the analytical laboratory.

#### **4.2.5      DATA EVALUATION AND REPORTING**

Groundwater elevations and contours will be plotted to define the horizontal and vertical flow patterns in the vicinity of the LA, MSA, and CSC. These results will be reported following each sampling event.

The analytical results for groundwater quality monitoring, once received from the laboratory, will undergo a thorough inspection and data validation will be undertaken to determine if the data is acceptable for use in the monitoring program. If the data is deemed acceptable for use, the data will be entered into a computer database and submitted to the MDEQ following each sampling event.

The monitoring requirements will be re-evaluated at least every 5 years to ensure that appropriate monitoring activities are being conducted.

#### **4.3              STORMWATER MONITORING**

Stormwater sample collection will be conducted to monitor the effectiveness of the treatment system to eliminate contaminants found in stormwater collected.

The stormwater quality monitoring program allows the evaluation of loading on the SWTP and includes the collection of samples from the MSA, LA, and CSC extraction systems, Catch Basin 2 located in CSC Area and Influent from the Lagoons to the SWTP, and is summarized in Table 4.2.

Samples from the stormwater/non-contact cooling water treatment plant will also be collected and reported in accordance with the Plant's NPDES permit. Samples of wastewater discharging to the City POTW will be collected and reported in accordance with the Plant's Industrial Users Permit.

## **5.0 REPORTING**

All reporting requirements have been outlined in Table 5.1.

### **5.1 OPERATION AND MAINTENANCE ACTIVITIES**

A report summarizing Site inspection and maintenance activities shall be prepared by REALM and submitted to the MDEQ semi-annually for the first 2 years and annually for another 28 years. After this period of time, the plan will be re-evaluated but monitoring and O&M activities will continue until contaminants on-Site no longer exceed applicable criteria. The semi-annual/annual reports will be provided within 60 days of completion of inspections.

### **5.2 GROUNDWATER SAMPLING**

Monitoring reports will be prepared and submitted to the State as part of the report identified in Section 5.1. The report will include static water level measurements and a corresponding groundwater flow map, analytical results in tabular form, and a discussion of results. The sampling event will be compared to historical results.

### **5.3 STATIC WATER LEVEL MONITORING**

Monitoring reports will be prepared and submitted to the State as part of the report identified in Section 5.1. The report will include static water level measurements, a corresponding groundwater flow map, and a discussion of the results. The event will be compared to historical results.

### **5.4 STORMWATER MONITORING**

Monitoring reports will be prepared and submitted to the State as part of the semi-annual report identified in Section 5.1. The report will include water level measurements, flow rates, analytical results, and a discussion of the results.

## **5.5 CONTINGENCY PLANS**

In the event that either monitoring results indicate contaminant migration has occurred or if other significant changes occur, GM will verbally notify the MDEQ within 3 business days and submit a written proposal on how they plan to address the issue within 10 business days.

## **5.6 SITE MODIFICATIONS**

Any intrusive site work which may adversely impact the intended remedy must be reported to and approved by the MDEQ prior to commencement.

## **5.7 ARCHIMEDES SCREW PUMP SYSTEM SHUTDOWN**

GM will provide verbal notification to the MDEQ within 2 business days followed by written notification within 7 days if the Archimedes screw pump system is shut down for any reason. The notification will specify, as appropriate, how the problem will be addressed and an implementation schedule.

## **6.0 INSTITUTIONAL CONTROLS**

This section presents the institutional controls which have been implemented as part of the remedy.

### **6.1 PURPOSE OF INSTITUTIONAL CONTROLS**

Institutional controls have been implemented to ensure the integrity of the remedy.

### **6.2 IMPLEMENTATION OF INSTITUTIONAL CONTROLS**

A land use agreement with MDEQ and a restrictive covenant is being recorded with the Bay County Register of Deeds. The institutional controls include:

- i) restrict the use of soil and groundwater at the Site;
- ii) prohibit general public access to and development of the Site;
- iii) ensure the integrity of the cap is not compromised;
- iv) ensure the property is used for industrial purposes only; and
- v) be binding upon any and all persons who acquire title or any legal interest in property within the Site.

These restrictions shall remain in full force and effect until the MDEQ determines that the restrictions are no longer necessary to protect human health and the environment. Any person who owns or controls property subject to such deed restrictions may request of the MDEQ a determination that such restrictions are no longer required to protect human health and the environment.

These restrictions also include a land use agreement and declaration of restrictive covenant pursuant to Part 201, Section 324.20120b(3) and (4), and a Notice of Approved Environmental Remediation for the Parking Area and the PA (excluding location BH702) portions of the Site. These documents will ensure that long-term monitoring, O&M programs, land use or resource use restrictions, and financial assurances, if applicable, will be met on an ongoing basis to assure the effectiveness and integrity of the remedial measures to be implemented.

These restrictions also include a land use agreement and declaration of restrictive covenant for the UA to ensure Site-specific Recreational Use. GM will continue to be

responsible for groundwater monitoring O&M activities in the UA even though the City of Bay City is the current owner. The City is responsible for exercising due care with respect to the UA in general and particularly with respect to maintaining the integrity of those areas outlined in the restrictive covenant for the UA area.

## **7.0 SITE HEALTH AND SAFETY PLAN**

The Health and Safety procedures for the long-term operation, maintenance, and monitoring activities at the Site are incorporated within the Site Health and Safety Plan (HASP) included as Appendix D to this Long-Term O&M Plan.

## **8.0 QUALITY ASSURANCE**

A certified analytical laboratory will be retained to perform the analyses for the groundwater monitoring program. Samples will be analyzed as specified under Part 201 of Act 451.

Quality Control/Quality Assurance samples will be collected as part of the sampling program. These samples will consist of duplicates, equipment rinsate blanks, matrix spike and matrix spike duplicates, and trip blanks. One duplicate sample will be collected for every ten investigative samples. One equipment blank and duplicate will be collected for every ten investigative samples with a minimum of one per day. One matrix spike and one matrix spike duplicate will be collected for every 20 investigative samples. One trip blank will be collected with each shipment of VOCs.


All sample parameters analyzed including analytical method numbers, and target detection limits are presented in Table 8.1.

## **9.0 RESPONSIBILITY**

Mr. Joseph Medved of General Motors (GM) Worldwide Facilities Group (WFG) has overall responsibility for implementing RAP O&M activities.

Ms. Jennifer Bigelow will be responsible for O&M activities associated with operations (i.e., treatment plants, Archimedes screws, etc.) Mr. Medved will be responsible for O&M activities associated with historical activities (i.e., maintaining caps, extraction systems, sheet pile, wall, etc.). Any changes in personnel will be identified to the MDEQ within 30 days.

It is the responsibility of the City of Bay City to conduct certain O&M activities in the UA. If the City of Bay City fails to conduct these activities, GM will perform these activities following appropriate discussions and consultation with the MDEQ and City of Bay City; such performance by GM does not relieve the City of Bay City of its responsibilities.



SOURCE: U.S.G.S. QUADRANGLE MAPS;  
 BAY CITY AND ESSEXVILLE, MICHIGAN  
 1967 (PHOTO REVISED 1973)

figure 1.1

**SITE LOCATION**  
**GM-POWERTRAIN GROUP - BAY CITY PLANT**  
*Bay City, Michigan*






figure 1.2

**SITE PLAN**  
**GM-POWERTRAIN GROUP - BAY CITY PLANT**  
*Bay City, Michigan*








figure 3.2  
**EXTRACTION WELL LOCATIONS**  
**GM-POWERTRAIN GROUP - BAY CITY PLANT**  
*Bay City, Michigan*






figure 3.3

**PUMP MAINTENANCE**  
**GM-POWERTRAIN GROUP - BAY CITY PLANT**  
*Bay City, Michigan*






figure 4.1  
 WELL LOCATIONS FOR LONGTERM GROUNDWATER MONITORING AND  
 SHALLOW GROUNDWATER CONTOURS, OCTOBER 31, 2000  
 GM-POWERTRAIN GROUP - BAY CITY PLANT  
 Bay City, Michigan

**TABLE 3.1**  
**SUMMARY OF STORMWATER SYSTEM MAINTENANCE ACTIVITIES**  
**GM POWERTRAIN GROUP, BAY CITY PLANT, BAY CITY, MICHIGAN**

<i>Frequency</i>					
<i>Daily</i>	<i>Weekly</i>	<i>Every 2 Weeks</i>	<i>Monthly</i>	<i>Semi-Annually</i>	<i>Annually</i>
<b><u>MECHANICAL</u></b>					
Inspect cooling tower pumps, valves & piping systems	Check oil level in pumps, and fill as necessary	Inspect & clean lagoon screens	Backwash GAC	--	--
Inspect and maintain pH pumps & piping systems	Inspect & clean storm water pumps		Inspect Sand Filters		
Inspect & maintain pumps & piping	Inspect Trybon lubrication systems, and fill as necessary		Inspect heating systems in water storage tanks		
Inspect groundwater extraction system, drain water from oil cooler & add oil twice daily	Clean screen on lagoon turbidity pump				
	Inspect air makeup units and change as necessary				
	Inspect filters on blowers and change as necessary				
<b><u>ELECTRICAL</u></b>					
--	--	--	Check undervoltage control for cooling supply pumps Operate Emergency Generator - Stand alone test Run air compressor for 1 hr	Check sacrificial anodes in Sand Filters Check anode in slurry tank	Run both portable diesel generators
<b><u>OPERATIONS</u></b>					
Log flows etc.	Clean turbidimeter in Archimedes Building	--	Clean Storm Plant Clarifier Tanks	--	--
Clean Process & Storm Plant turbidimeters			Power Wash Storm Press		

**TABLE 4.1**  
**MONITORING WELL COMPLETION DETAILS AND GROUNDWATER ELEVATIONS**  
**GM POWERTRAIN DIVISION, BAY CITY, MICHIGAN**

Well Location	Top of Riser Elevation (ft AMSL)	Modified Top of Riser Elevation (ft AMSL)	Depth to Water (feet) 10/31/00	Depth of Well (feet)	Screen Length (feet)	Screen Type	Riser Type	Diameter of Screen (inches)	Groundwater Elevation (feet AMSL)								
									03/08/99	03/19/99	04/20/99	05/20/99	06/22/99	07/20/99	09/07/99	09/27/99	
<b><u>Inlet Slip (IS)</u></b>																	
Gage 4	580	579.52	1.44	--	--	--	--	--	584.79	584.54	584.68	583.67	Dry	581.40	n/a	n/a	
Gage 5	582.72	569.47	8.00	--	--	--	--	--	580.12	580.26	580.02	580.17	580.04	579.72	Dry	Dry	
<b><u>Lagoon Area (LA)</u></b>																	
LMW2S	590.16	589.48	11.28	19.25	10	SS	PVC	2	581.04	581.06	579.43	578.62	580.38	579.54	578.54	578.02	
LMW6S	590.41	589.86	11.66	19.04	10	SS	PVC	2	581.52	581.46	577.85	576.01	579.05	576.95	577.49	577.14	
LMW7S	592.04	591.47	13.88	18.52	10	SS	PVC	2	579.15	579.42	579.59	579.87	579.30	579.00	578.19	577.90	
LMW8S	590.69	590.12	12.05	18.59	10	SS	PVC	2	581.61	581.69	579.17	577.29	580.33	578.83	577.95	577.54	
LMW11S	591.49	590.61	9.97	19.54	10	SS	SS	2	580.92	580.69	580.90	579.74	577.27	580.20	582.42	582.29	
LMW12S	590.43	589.59	11.24	18.99	10	SS	PVC	2	581.28	581.63	579.70	579.33	583.55	581.49	578.85	578.46	
MW201D1	588.21	587.65	9.97	29.63	10	SS	SS	2	579.30	579.46	579.25	579.26	578.13	579.57	578.47	578.76	
MW201D2	587.86	587.26	9.60	36.36	10	SS	SS	2	579.30	579.46	579.23	579.17	577.86	579.56	578.09	578.75	
MW201D3	588.29	587.76	10.05	46.70	10	SS	SS	2	579.26	579.29	579.18	579.24	577.83	579.51	578.31	578.69	
MW201D4	588.33	587.78	10.32	56.75	10	SS	SS	2	579.31	578.92	578.73	578.71	577.46	580.15	578.35	578.35	
LMW5S	590.51	589.73	11.73	19.43	10	SS	PVC	2	579.71	579.68	579.66	579.66	579.30	579.29	578.93	578.35	
<b><u>Machine Storage Area (MSA)</u></b>																	
LMW13S	590.02	589.4	10.77	19.22	10	SS	PVC	2	582.56	583.17	582.65	581.42	579.23	579.68	580.02	580.55	
LMW17S	589.77	589.31	10.38	19.83	10	SS	PVC	2	581.58	581.57	580.25	579.77	579.65	579.43	579.19	578.98	
LMW18S	591.24	592.33	13.81	22.52	10	SS	PVC	2	579.44	579.44	579.78	579.39	579.45	579.57	577.89	577.51	
LMW19S	589.22	588.61	9.23	19.32	10	SS	PVC	2	580.66	580.90	580.94	580.51	580.52	580.42	580.01	579.53	
MW1S	591.94	591.08	12.51	12.95	2	SS	SS	2	584.12	584.35	579.49	579.29	578.64	--	578.58	578.51	
MW100S	590.03	591.97	12.64	14.44	10	SS	SS	2	582.71	582.53	579.96	579.30	579.07	579.33	--	578.57	
MW101S	594.17	593.34	14.43	19.22	10	SS	SS	2	586.44	586.50	580.44	579.19	578.71	578.83	579.18	579.04	
MW102D1	594.13	594.86	16.99	30.99	10	SS	SS	2	582.32	582.38	579.34	579.27	576.82	579.69	578.29	577.64	
MW102D2	594.08	594.93	17.08	36.21	10	SS	SS	2	581.93	582.03	579.39	579.34	576.78	579.68	578.15	577.50	
MW102D3	594.14	594.91	17.11	46.74	10	SS	SS	2	581.84	581.92	579.35	579.25	576.80	579.66	578.20	577.55	
MW102D4	594.06	594.9	17.17	56.85	10	SS	SS	2	581.45	581.54	579.21	579.13	576.70	579.56	578.05	577.40	
MW300S	587.71	587.12	8.85	15.06	10	SS	SS	2	579.51	579.37	579.86	579.51	579.95	579.69	579.33	578.90	
LMW14SR (Replaced LMW14S Jan/00)	589.65	589.01	10.88	13.00	7	SS	SS	2	582.11	582.10	581.12	580.40	578.55	579.97	578.88	578.30	
<b><u>Perimeter Banks (PB)</u></b>																	
LMW1S	590.05	589.36	10.56	18.96	10	SS	PVC	2	579.94	581.03	579.27	579.26	579.36	579.71	579.48	581.14	
LMW3D	590.02	589.46	11.80	32.84	5	SS	SS	2	580.72	580.87	579.27	579.17	577.70	579.66	579.78	578.77	
LMW15D	589.06	588.34	10.71	32.8	10	SS	PVC	2	579.71	579.86	579.23	579.21	577.88	579.68	579.81	578.93	
MW200D	588.12	587.35	10.28	63.15	10	SS	SS	2	578.93	578.87	578.60	578.69	577.84	579.12	579.08	578.14	
MW200S	588.45	587.69	9.67	16.0	10	SS	SS	2	n/a	n/a	n/a	579.67	579.29	579.41	579.76	578.65	
MW301D1	590.15	589.54	(5)	27.50	10	SS	SS	2	579.29	579.40	579.32	579.22	575.75	579.73	579.67	578.99	
MW301D2	589.77	589.16	(5)	37.24	10	SS	SS	2	579.23	579.35	579.28	579.19	576.11	579.69	579.62	578.93	
MW301D3	589.83	589.22	(5)	44.04	10	SS	SS	2	579.23	579.38	579.25	579.18	576.13	579.65	579.59	578.90	
MW301D4	589.92	589.33	(5)	55.95	10	SS	SS	2	579.18	579.37	579.26	579.17	576.08	579.62	579.52	578.85	
MW302D1	589.38	588.76	10.99	29.18	10	SS	SS	2	579.28	579.53	579.38	579.48	575.78	579.72	580.61	578.96	
MW302D2	589.4	588.78	11.03	35.70	10	SS	SS	2	579.27	579.40	579.29	579.20	576.28	579.70	580.98	578.95	
MW302D3	589.56	588.96	11.24	45.97	10	SS	SS	2	579.26	579.41	579.24	579.29	576.28	579.66	580.64	578.90	
MW302D4	589.36	588.7	11.19	55.94	10	SS	SS	2	579.17	579.21	579.12	579.02	576.16	579.46	580.05	578.71	
Gage 2	Buried	569.4	8.00	--	--	--	--	--	Buried	Buried	Buried	Buried	Buried	Buried	Buried	Buried	

TABLE 4.1

MONITORING WELL COMPLETION DETAILS AND GROUNDWATER ELEVATIONS  
GM POWERTRAIN DIVISION, BAY CITY, MICHIGAN

Well Location	Top of Riser Elevation (ft AMSL)	Modified Top of Riser Elevation (ft AMSL)	Depth to Water (feet) 10/31/00	Depth of Well (feet)	Screen Length (feet)	Screen Type	Riser Type	Diameter of Screen (inches)	Groundwater Elevation (feet AMSL)								
									03/08/99	03/19/99	04/20/99	05/20/99	06/22/99	07/20/99	09/07/99	09/27/99	
<b>Support Facilities Area (SFA)</b>																	
LMW23S	591.32	586.03	8.45	22.99	10	SS	PVC	2	578.14	578.32	578.32	578.32	Destroyed	Destroyed	Destroyed	Destroyed	
MSA5S	589.28	588.6	8.26	18.98			SS	2	580.54	580.33	580.83	579.71	577.24	579.38	581.84	581.74	
MW3S	590.25	589.64	12.56	13.00			SS	2	578.19	578.50	578.43	578.55	578.30	578.25	577.84	577.64	
MW403S	588.55	587.89	10.71	20.82	10	SS	SS	2	578.34	578.10	578.33	578.24	577.07	578.35	578.45	578.06	
MW404S	586.42	585.77	5.01	9.30	10	SS		2	n/a	581.52	581.85	581.63	581.68	581.62	581.29	580.99	
MW405S	589.03	588.52	10.10	14.47	10	SS	SS	2	579.04	579.83	579.30	579.18	579.09	579.13	578.94	578.81	
MW406S	590.14	589.5	10.98	17.45	10	SS	SS	2	579.54	579.59	579.83	580.14	579.84	579.80	579.27	579.29	
<b>Undeveloped Area (UA)</b>																	
MW7S	590.51	590.03	12.49	12.20				2	581.86	581.71	579.45	579.33	578.82	578.67	578.42	576.85	
MW10S	589.85	589.17	10.96	12.19			PVC	2	583.01	583.05	580.56	580.45	580.00	579.77	579.37	578.97	
MW501D	584.54	584.05	7.14	54.63	10	SS	SS	2	578.51	578.56	578.49	578.47	577.68	578.74	578.52	577.88	
MW501S	584.39	583.62	5.67	14.86	10	SS	SS	2	579.80	579.79	579.91	579.72	579.25	578.82	578.35		
MW502D	589.82	589.28	12.46	57.98	10	SS	SS	2	579.68	579.57	578.45	578.37	577.88	578.60	578.36	577.75	
MW503D	588.94	588.54	11.58	56.60	10	SS	SS	2	578.60	578.45	578.49	578.39	578.02	578.60	578.38	577.78	
MW503S	589.09	588.69	10.49	18.97	10	SS	SS	2	580.52	580.38	580.67	580.43	579.49	579.15	578.64	578.39	
MW504S	586.2	585.54	7.35	14.33	10	SS	SS	2	581.51	581.65	n/a	579.70	579.39	579.20	578.76	578.47	
MW506S	589.48	588.85	10.90	14.22	10	SS	SS	2	582.47	582.61	580.93	580.28	578.22	579.00	578.48	578.24	
MW508SR (replaced MW508S Jan/00)	591.81	591.26	13.71	15.00	7	SS	SS	2	Buried	Buried	Buried	Buried	Buried	Buried	Buried	Buried	
Gage 3	584.76	579.24	Dry	--	--	--	--	--	584.06	584.06	584.21	584.26	584.26	584.26	Dry	Dry	
<b>Crotty Street Channel</b>																	
MW1-00	588.87	588.26	10.81	12.00	7	SS	SS	2	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	
MW2-00	590.09	589.29	11.84	18.00	7	SS	SS	2	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	
MW3-00	587.92	588.4	10.95	12.50	7	SS	SS	2	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	
MW4-00	590.67	589.65	12.18	19.00	7	SS	SS	2	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	
MW5-00	589.73	588.89	11.58	13.00	7	SS	SS	2	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	
Gage 1	569.43	569.43	8.00	--	--	--	--	--	Destroyed	Destroyed	Destroyed	Destroyed	Destroyed	Destroyed	Destroyed	Destroyed	

Notes:

- (1) Approximate value
  - (2) Lock Needs Replacing
  - (3) Gage needs to be relocated.
  - (4) Could not open due to liner attachment.
  - (5) Could not take water level, riser pipe needs extension
- n/a - groundwater elevation not available

TABLE 4.1

**MONITORING WELL COMPLETION DETAILS AND GROUNDWATER ELEVATIONS  
GM POWERTRAIN DIVISION, BAY CITY, MICHIGAN**

Well Location	Top of Riser Elevation (ft AMSL)	Modified Top of Riser Elevation (ft AMSL)	Depth to Water (feet) 10/31/00	Depth of Well (feet)	Screen Length (feet)	Screen Type	Riser Type	Diameter of Screen (inches)	Groundwater Elevation (feet AMSL)							
									10/25/99	11/24/99	1/4/00	2/2/00	2/28/00	3/29/00	4/26/00	5/30/00
									<b>Inlet Slip (IS)</b>							
Gage 4	580	579.52	1.44	--	--	--	--	--	n/a	582.72	582.17	578.50	582.22	583.22	583.18	583.14
Gage 5	582.72	569.47	8.00	--	--	--	--	--	Dry	Dry	Dry	Dry	Dry	Dry	Dry	Dry
<b>Lagoon Area (LA)</b>																
LMW2S	590.16	589.48	11.28	19.25	10	SS	PVC	2	577.91	577.53	577.60	577.48	578.01	577.88	578.24	578.67
LMW6S	590.41	589.86	11.66	19.04	10	SS	PVC	2	577.33	576.92	577.22	577.23	578.23	577.90	578.67	579.43
LMW7S	592.04	591.47	13.88	18.52	10	SS	PVC	2	577.94	577.80	577.84	577.86	578.42	578.71	578.99	580.13
LMW8S	590.69	590.12	12.05	18.59	10	SS	PVC	2	577.59	577.36	577.77	577.73	578.36	578.12	578.83	579.86
LMW11S	591.49	590.61	9.97	19.54	10	SS	SS	2	582.46	582.43	582.14	581.43	582.16	582.85	582.89	582.90
LMW12S	590.43	589.59	11.24	18.99	10	SS	PVC	2	578.13	577.91	578.29	578.05	578.86	578.78	579.15	580.05
MW201D1	588.21	587.65	9.97	29.63	10	SS	SS	2	578.44	577.23	578.44	No Access	578.39	578.36	578.67	578.79
MW201D2	587.86	587.26	9.60	36.36	10	SS	SS	2	578.43	577.22	577.91	No Access	578.40	578.46	578.68	578.78
MW201D3	588.29	587.76	10.05	46.70	10	SS	SS	2	578.37	577.17	577.86	No Access	578.33	578.33	578.85	578.74
MW201D4	588.33	587.78	10.32	56.75	10	SS	SS	2	578.04	576.83	577.54	No Access	578.10	578.09	578.67	578.50
LMW5S	590.51	589.73	11.73	19.43	10	SS	PVC	2	579.21	578.86	578.98	578.68	579.60	579.54	579.96	580.86
<b>Machine Storage Area (MSA)</b>																
LMW13S	590.02	589.4	10.77	19.22	10	SS	PVC	2	581.26	580.68	580.08	579.27	581.74	581.27	581.81	581.63
LMW17S	589.77	589.31	10.38	19.83	10	SS	PVC	2	579.69	579.71	579.47	579.08	579.96	579.91	580.19	580.06
LMW18S	591.24	592.33	13.81	22.52	10	SS	PVC	2	577.62	577.32	577.37	577.09	577.80	577.66	578.09	578.10
LMW19S	589.22	588.61	9.23	19.32	10	SS	PVC	2	579.95	579.58	580.30	579.70	581.39	580.73	581.25	580.96
MW1S	591.94	591.08	12.51	12.95	2	SS	SS	2	579.11	579.15	579.07	579.05	579.18	579.28	579.29	579.26
MW100S	590.03	591.97	12.64	14.44	10	SS	SS	2	578.77	578.09	577.49	577.09	576.69	576.87	577.07	577.79
MW101S	594.17	593.34	14.43	19.22	10	SS	SS	2	579.81	579.65	579.61	579.61	579.86	579.21	580.14	580.39
MW102D1	594.13	594.86	16.99	30.99	10	SS	SS	2	577.47	576.38	576.80	576.81	577.23	577.25	577.60	577.70
MW102D2	594.08	594.93	17.08	36.21	10	SS	SS	2	577.33	576.24	576.67	576.80	577.08	577.12	577.44	577.58
MW102D3	594.14	594.91	17.11	46.74	10	SS	SS	2	577.35	576.26	576.71	576.88	577.12	577.16	577.47	577.59
MW102D4	594.06	594.9	17.17	56.85	10	SS	SS	2	577.21	576.12	576.56	575.70	576.98	577.01	577.34	577.45
MW300S	587.71	587.12	8.85	15.06	10	SS	SS	2	578.87	579.91	579.27	578.55	No Access	579.73	580.18	579.89
LMW14SR (Replaced LMW14S Jan/00)	589.65	589.01	10.88	13.00	7	SS	SS	2	578.58	Damaged	Damaged	578.58	578.55	578.99	578.91	579.22
<b>Perimeter Banks (PB)</b>																
LMW1S	590.05	589.36	10.56	18.96	10	SS	PVC	2	578.60	579.90	579.74	579.33	580.31	580.27	580.68	580.63
LMW3D	590.02	589.46	11.80	32.84	5	SS	SS	2	578.30	577.05	577.93	578.70	578.40	578.66	578.58	578.66
LMW15D	589.06	588.34	10.71	32.8	10	SS	PVC	2	578.49	577.18	577.95	578.23	578.56	578.56	578.74	578.88
MW200D	588.12	587.35	10.28	63.15	10	SS	SS	2	577.96	576.77	577.64	577.72	578.05	578.00	579.08	578.38
MW200S	588.45	587.69	9.67	16.0	10	SS	SS	2	579.33	578.92	579.09	578.79	579.73	579.65	579.73	580.94
MW301D1	590.15	589.54	(5)	27.50	10	SS	SS	2	578.63	577.42	578.05	578.28	578.56	578.59	578.85	578.80
MW301D2	589.77	589.16	(5)	37.24	10	SS	SS	2	578.57	577.35	577.99	578.22	578.51	578.54	578.77	578.89
MW301D3	589.83	589.22	(5)	44.04	10	SS	SS	2	578.54	577.32	577.96	578.18	578.48	578.49	578.74	578.85
MW301D4	589.92	589.33	(5)	55.95	10	SS	SS	2	578.47	577.27	577.90	578.14	578.43	578.45	578.69	578.76
MW302D1	589.38	588.76	10.99	29.18	10	SS	SS	2	578.60	577.39	578.05	578.26	578.52	578.58	578.82	578.93
MW302D2	589.4	588.78	11.03	35.70	10	SS	SS	2	578.56	577.37	578.03	578.22	578.52	578.54	578.78	578.90
MW302D3	589.56	588.96	11.24	45.97	10	SS	SS	2	578.51	577.32	577.99	578.19	578.47	578.50	578.73	578.84
MW302D4	589.36	588.7	11.19	55.94	10	SS	SS	2	578.33	577.14	577.82	578.01	578.30	578.32	578.58	578.68
Gage 2	Buried	569.4	8.00	--	--	--	--	--	Buried	Buried	Buried	Buried	Buried	Buried	Buried	Buried

TABLE 4.1

MONITORING WELL COMPLETION DETAILS AND GROUNDWATER ELEVATIONS  
GM POWERTRAIN DIVISION, BAY CITY, MICHIGAN

Well Location	Top of Riser Elevation (ft AMSL)	Modified Top of Riser Elevation (ft AMSL)	Depth to Water (feet) 10/31/00	Depth of Well (feet)	Screen Length (feet)	Screen Type	Riser Type	Diameter of Screen (inches)	Groundwater Elevation (feet AMSL)							
									10/25/99	11/24/99	1/4/00	2/2/00	2/28/00	3/29/00	4/26/00	5/30/00
									<b>Support Facilities Area (SFA)</b>							
LMW23S	591.32	586.03	8.45	22.99	10	SS	PVC	2	Destroyed	Destroyed	Destroyed	582.74 <sup>(2)</sup>	582.88	582.94	583.13	583.25
MSA5S	589.28	588.6	8.26	18.98			SS	2	581.77	581.70	581.42	580.96	582.13	580.62	582.37	582.22
MW3S	590.25	589.64	12.56	13.00			SS	2	n/a	577.40	Dry	Dry	Dry	577.82	577.97	578.63
MW403S	588.55	587.89	10.71	20.82	10	SS	SS	2	578.19	577.59	577.63	577.61	577.72	577.84	578.29	578.44
MW404S	586.42	585.77	5.01	9.30	10	SS		2	581.58	--	No Access	No Access	No Access	No Access	582.24	Covered
MW405S	589.03	588.52	10.10	14.47	10	SS	SS	2	578.99	579.04	579.15	579.13	579.25	579.16	579.25	579.30
MW406S	590.14	589.5	10.98	17.45	10	SS	SS	2	579.24	578.71	578.59	578.39	578.85	579.01	579.20	580.11
<b>Undeveloped Area (UA)</b>																
MW7S	590.51	590.03	12.49	12.20				2	578.29	579.00	578.16	577.87	578.63	578.63	579.08	579.92
MW10S	589.85	589.17	10.96	12.19			PVC	2	579.23	579.07	579.11	578.80	579.67	579.65	580.59	580.79
MW501D	584.54	584.05	7.14	54.63	10	SS	SS	2	577.68	576.42	577.18	577.26	577.62	577.44	577.87	577.99
MW501S	584.39	583.62	5.67	14.86	10	SS	SS	2	579.06	578.86	578.93	575.69	579.82	579.11	579.66	579.89
MW502D	589.82	589.28	12.46	57.98	10	SS	SS	2	577.59	576.43	577.09	577.14	577.58	577.43	577.87	577.97
MW503D	588.94	588.54	11.58	56.60	10	SS	SS	2	577.63	576.56	577.18	577.17	577.69	577.46	578.06	578.15
MW503S	589.09	588.69	10.49	18.97	10	SS	SS	2	578.85	578.66	579.00	578.77	580.38	579.91	580.76	581.37
MW504S	586.2	585.54	7.35	14.33	10	SS	SS	2	579.15	579.08	579.24	578.87	580.16	579.43	579.94	580.31
MW506S	589.48	588.85	10.90	14.22	10	SS	SS	2	578.85	578.59	578.79	578.59	580.07	579.73	580.55	581.12
MW508SR (replaced MW508S Jan/00)	591.81	591.26	13.71	15.00	7	SS	SS	2	Buried	Buried	Buried	578.03	578.57	578.99	579.55	580.78
Gage 3	584.76	579.24	Dry	--	--	--	--	--	Dry	Dry	Dry	Dry	584.16	584.16	584.06	583.76
<b>Crotty Street Channel</b>																
MW1-00	588.87	588.26	10.81	12.00	7	SS	SS	2	n/a	n/a	n/a	577.89	578.89	578.04	578.42	578.68
MW2-00	590.09	589.29	11.84	18.00	7	SS	SS	2	n/a	n/a	n/a	579.11	578.11	577.26	577.65	Not Accessable
MW3-00	587.92	588.4	10.95	12.50	7	SS	SS	2	n/a	n/a	n/a	578.27	579.25	578.40	578.79	579.05
MW4-00	590.67	589.65	12.18	19.00	7	SS	SS	2	n/a	n/a	n/a	577.03	578.03	577.18	577.60	Not Accessable
MW5-00	589.73	588.89	11.58	13.00	7	SS	SS	2	n/a	n/a	n/a	577.63	578.36	578.66	578.86	579.12
Gage 1	569.43	569.43	8.00	--	--	--	--	--	Destroyed	Destroyed	Destroyed	Destroyed	Destroyed	Destroyed	Destroyed	Destroyed

Notes:

- (1) Approximate value
- (2) Lock Needs Replacing
- (3) Gage needs to be relocated.
- (4) Could not open due to liner attachment.
- (5) Could not take water level, riser pipe needs extension
- n/a - groundwater elevation not available

TABLE 4.1

MONITORING WELL COMPLETION DETAILS AND GROUNDWATER ELEVATIONS  
GM POWERTRAIN DIVISION, BAY CITY, MICHIGAN

Well Location	Top of Riser Elevation (ft AMSL)	Modified Top of Riser Elevation (ft AMSL)	Depth to Water (feet) 10/31/00	Depth of Well (feet)	Screen Length (feet)	Screen Type	Riser Type	Diameter of Screen (inches)	Groundwater Elevation (feet AMSL)				
									6/30/00	07/18/00	08/29/00	09/11/00	10/31/00
<b><u>Inlet Slip (IS)</u></b>													
Gage 4	580	579.52	1.44	--	--	--	--	--	581.98	582.72	580.68	582.22	580.96
Gage 5	582.72	569.47	8.00	--	--	--	--	--	n/a (3)	n/a (3)	578.02	577.87	577.47
<b><u>Lagoon Area (LA)</u></b>													
LMW2S	590.16	589.48	11.28	19.25	10	SS	PVC	2	578.65	577.85	577.78	577.72	578.20
LMW6S	590.41	589.86	11.66	19.04	10	SS	PVC	2	579.40	578.50	578.48	578.29	578.20
LMW7S	592.04	591.47	13.88	18.52	10	SS	PVC	2	580.11	579.08	578.29	578.11	577.59
LMW8S	590.69	590.12	12.05	18.59	10	SS	PVC	2	579.52	578.63	578.53	578.48	578.07
LMW11S	591.49	590.61	9.97	19.54	10	SS	SS	2	581.94	582.28	580.63	581.39	580.64
LMW12S	590.43	589.59	11.24	18.99	10	SS	PVC	2	580.21	579.01	577.04	578.69	578.35
MW201D1	588.21	587.65	9.97	29.63	10	SS	SS	2	578.81	578.50	578.05	578.00	577.68
MW201D2	587.86	587.26	9.60	36.36	10	SS	SS	2	578.82	578.46	578.00	577.96	577.66
MW201D3	588.29	587.76	10.05	46.70	10	SS	SS	2	578.79	578.49	578.06	577.99	577.71
MW201D4	588.33	587.78	10.32	56.75	10	SS	SS	2	578.56	577.83	577.81	577.75	577.46
LMW5S	590.51	589.73	11.73	19.43	10	SS	PVC	2	580.30	578.84	578.43	578.13	578.00
<b><u>Machine Storage Area (MSA)</u></b>													
LMW13S	590.02	589.4	10.77	19.22	10	SS	PVC	2	580.62	580.11	578.90	578.90	578.63
LMW17S	589.77	589.31	10.38	19.83	10	SS	PVC	2	579.85	579.09	579.20	579.24	578.93
LMW18S	591.24	592.33	13.81	22.52	10	SS	PVC	2	577.80	578.52	579.03	578.67	578.52
LMW19S	589.22	588.61	9.23	19.32	10	SS	PVC	2	580.56	579.45	580.13	579.34	579.38
MW1S	591.94	591.08	12.51	12.95	2	SS	SS	2	579.31	578.34	578.38	578.43	578.57
MW100S	590.03	591.97	12.64	14.44	10	SS	SS	2	578.03	579.85	579.66	579.57	579.33
MW101S	594.17	593.34	14.43	19.22	10	SS	SS	2	580.22	579.02	579.04	578.99	578.91
MW102D1	594.13	594.86	16.99	30.99	10	SS	SS	2	577.62	578.71	578.15	578.16	577.87
MW102D2	594.08	594.93	17.08	36.21	10	SS	SS	2	577.48	578.67	578.13	578.13	577.85
MW102D3	594.14	594.91	17.11	46.74	10	SS	SS	2	577.52	578.63	578.09	578.08	577.80
MW102D4	594.06	594.9	17.17	56.85	10	SS	SS	2	577.38	578.55	578.02	578.00	577.73
MW300S	587.71	587.12	8.85	15.06	10	SS	SS	2	n/a (4)	n/a (2)	578.24	578.16	578.27
LMW14SR (Replaced LMW14S Jan/00)	589.65	589.01	10.88	13.00	7	SS	SS	2	579.32	579.19	578.21	578.16	578.13
<b><u>Perimeter Banks (PB)</u></b>													
LMW1S	590.05	589.36	10.56	18.96	10	SS	PVC	2	580.76	579.60	579.11	579.05	578.80
LMW3D	590.02	589.46	11.80	32.84	5	SS	SS	2	578.79	578.02	578.04	577.99	577.66
LMW15D	589.06	588.34	10.71	32.8	10	SS	PVC	2	n/a (4)	578.43	578.03	577.94	577.63
MW200D	588.12	587.35	10.28	63.15	10	SS	SS	2	578.46	577.87	578.14	577.43	577.07
MW200S	588.45	587.69	9.67	16.0	10	SS	SS	2	580.28	578.87	578.68	578.16	578.02
MW301D1	590.15	589.54	(5)	27.50	10	SS	SS	2	579.37	578.65	578.88	(5)	(5)
MW301D2	589.77	589.16	(5)	37.24	10	SS	SS	2	578.80	578.56	578.47	(5)	(5)
MW301D3	589.83	589.22	(5)	44.04	10	SS	SS	2	578.80	578.56	578.32	(5)	(5)
MW301D4	589.92	589.33	(5)	55.95	10	SS	SS	2	578.78	578.48	578.48	(5)	(5)
MW302D1	589.38	588.76	10.99	29.18	10	SS	SS	2	578.91	578.61	577.32	578.11	577.77
MW302D2	589.4	588.78	11.03	35.70	10	SS	SS	2	578.95	578.58	577.68	578.08	577.75
MW302D3	589.56	588.96	11.24	45.97	10	SS	SS	2	578.88	578.54	577.75	578.06	577.72
MW302D4	589.36	588.7	11.19	55.94	10	SS	SS	2	578.73	578.32	577.38	577.82	577.51
Gage 2	Buried	569.4	8.00	--	--	--	--	--	Buried (3)	Buried (3)	578.04	577.80	577.40

TABLE 4.1

MONITORING WELL COMPLETION DETAILS AND GROUNDWATER ELEVATIONS  
GM POWERTRAIN DIVISION, BAY CITY, MICHIGAN

Well Location	Top of Riser Elevation (ft AMSL)	Modified Top of Riser Elevation (ft AMSL)	Depth to Water (feet) 10/31/00	Depth of Well (feet)	Screen Length (feet)	Screen Type	Riser Type	Diameter of Screen (inches)	Groundwater Elevation (feet AMSL)				
									6/30/00	07/18/00	08/29/00	09/11/00	10/31/00
<b>Support Facilities Area (SFA)</b>													
LMW23S	591.32	586.03	8.45	22.99	10	SS	PVC	2	583.08	577.63	577.71	577.73	577.58
MSA5S	589.28	588.6	8.26	18.98			SS	2	581.17	581.32	580.41	580.56	580.34
MW3S	590.25	589.64	12.56	13.00			SS	2	578.46	578.02	577.58	577.46	577.08
MW403S	588.55	587.89	10.71	20.82	10	SS	SS	2	578.22	577.58	577.37	577.38	577.18
MW404S	586.42	585.77	5.01	9.30	10	SS		2	582.21	581.02	581.43	581.05	580.76
MW405S	589.03	588.52	10.10	14.47	10	SS	SS	2	579.08	578.51	578.46	576.33	578.42
MW406S	590.14	589.5	10.98	17.45	10	SS	SS	2	580.03	579.01	577.77	578.68	578.52
<b>Undeveloped Area (UA)</b>													
MW7S	590.51	590.03	12.49	12.20				2	579.36	578.24	577.86	577.68	577.54
MW10S	589.85	589.17	10.96	12.19			PVC	2	580.11	578.75	578.46	578.22	578.21
MW501D	584.54	584.05	7.14	54.63	10	SS	SS	2	577.82	577.88	577.35	577.30	576.91
MW501S	584.39	583.62	5.67	14.86	10	SS	SS	2	579.22	577.90	577.97	577.62	577.95
MW502D	589.82	589.28	12.46	57.98	10	SS	SS	2	577.96	577.49	577.24	577.11	576.82
MW503D	588.94	588.54	11.58	56.60	10	SS	SS	2	578.07	577.70	577.45	577.36	576.96
MW503S	589.09	588.69	10.49	18.97	10	SS	SS	2	580.30	579.00	578.58	578.29	578.20
MW504S	586.2	585.54	7.35	14.33	10	SS	SS	2	579.49	578.07	578.25	577.82	578.19
MW506S	589.48	588.85	10.90	14.22	10	SS	SS	2	580.04	578.58	578.19	577.95	577.95
MW508SR (replaced MW508S Jan./00)	591.81	591.26	13.71	15.00	7	SS	SS	2	580.38	579.11	578.19	577.95	577.55
Gage 3	584.76	579.24	Dry	--	--	--	--	--	583.76	580.24	Dry	Dry	Dry
<b>Crotty Street Channel</b>													
MW1-00	588.87	588.26	10.81	12.00	7	SS	SS	2	579.57	577.71	577.60	577.36	577.45
MW2-00	590.09	589.29	11.84	18.00	7	SS	SS	2	578.67	577.65	577.59	577.36	577.45
MW3-00	587.92	588.4	10.95	12.50	7	SS	SS	2	578.46	578.68	577.60	577.37	577.45
MW4-00	590.67	589.65	12.18	19.00	7	SS	SS	2	578.87	577.62	577.57	577.34	577.47
MW5-00	589.73	588.89	11.58	13.00	7	SS	SS	2	n/a (4)	n/a (4)	578.01	577.91	577.31
Gage 1	569.43	569.43	8.00	--	--	--	--	--	Destroyed (3)	Destroyed (3)	578.05	577.93	577.43

Notes:

- (1) Approximate value
- (2) Lock Needs Replacing
- (3) Gage needs to be relocated.
- (4) Could not open due to liner attachment.
- (5) Could not take water level, riser pipe needs extension
- n/a - groundwater elevation not available

TABLE 4.2

**SUMMARY OF LONG-TERM GROUNDWATER AND STORMWATER MONITORING ACTIVITIES  
GM POWERTRAIN GROUP, BAY CITY PLANT, BAY CITY, MICHIGAN**

<b>Plant Area</b>	<b>Location</b>	<b>Groundwater Quality Monitoring</b>		<b>Static Water Level Monitoring (1)</b>
		<b>Parameters</b>	<b>Frequency</b>	<b>Frequency</b>
<b><u>Inlet Slip (IS)</u></b>				
IS	Gage 4 (2)	--	--	annually
IS	Gage 5 (2)	--	--	annually
<b><u>Lagoon Area (LA)</u></b>				
LA	LMW1S	PCBs, VOCs	annually	annually
LA	LMW2S (3)	--	--	annually
LA	LMW6S (3)	--	--	annually
LA	LMW8S (3)	--	--	annually
LA	LMW12S (3)	--	--	annually
LA	MW201D1	PCBs, VOCs	annually	annually
LA	MW201D2	PCBs, VOCs	annually	annually
LA	MW201D3	PCBs, VOCs	annually	annually
LA	MW201D4	PCBs, VOCs	annually	annually
<b><u>Machine Storage Area (MSA)</u></b>				
MSA	LMW17S	--	--	annually
MSA	LMW18S (3)	--	--	annually
MSA	LMW19S	--	--	annually
MSA	MW1S (3)	--	--	annually
MSA	MW100S (3)	--	--	annually
MSA	MW101S (3)	--	--	annually
MSA	MW102D1	PCBs	annually	annually
MSA	MW102D2	PCBs	annually	annually
MSA	MW102D3	PCBs	annually	annually
MSA	MW102D4	PCBs	annually	annually
MSA	MW300S	PCBs	annually	annually
MSA	LMW14S	--	--	annually
<b><u>Perimeter Banks (PB)</u></b>				
PB	LMW3D	PCBs	annually	annually
PB	LMW5S	PCBs	annually	annually
PB	LMW13S	PCBs	annually	annually
PB	LMW15D	PCBs	annually	annually
PB	MW200D	PCBs	annually	annually
PB	MW200S	--	--	annually
PB	MW301D1	PCBs	annually	annually
PB	MW301D2	PCBs	annually	annually
PB	MW301D3	PCBs	annually	annually
PB	MW301D4	PCBs	annually	annually
PB	MW302D1	PCBs	annually	annually
PB	MW302D2	PCBs	annually	annually
PB	MW302D3	PCBs	annually	annually
PB	MW302D4	PCBs	annually	annually
PB	Gage 2	--	--	annually
<b><u>Support Facilities Area (SFA)</u></b>				
SFA	LMW7S	--	--	annually
SFA	LMW11S	--	--	annually
SFA	LMW23S	--	--	annually
SFA	MSA5S	--	--	annually
SFA	MW3S	--	--	annually
SFA	MW403S	--	--	annually
SFA	MW404S	--	--	annually
SFA	MW405S	--	--	annually
SFA	MW406S	--	--	annually

TABLE 4.2

**SUMMARY OF LONG-TERM GROUNDWATER AND STORMWATER MONITORING ACTIVITIES  
GM POWERTRAIN GROUP, BAY CITY PLANT, BAY CITY, MICHIGAN**

<b>Plant Area</b>	<b>Location</b>	<b>Groundwater Quality Monitoring</b>		<b>Static Water Level Monitoring (1)</b>
		<b>Parameters</b>	<b>Frequency</b>	<b>Frequency</b>
<b><u>Undeveloped Area (UA)</u></b>				
UA	MW7S	PCBs, metals	annually	annually
UA	MW10S	PCBs, metals	annually	annually
UA	MW501D	PCBs, metals	annually	annually
UA	MW501S	PCBs, metals	annually	annually
UA	MW502D	PCBs, metals	annually	annually
UA	MW503D	PCBs, metals	annually	annually
UA	MW503S	PCBs, metals	annually	annually
UA	MW504S	PCBs, metals	annually	annually
UA	MW506S	PCBs, metals	annually	annually
UA	MW508SR	PCBs, metals	annually	annually
UA	Gage 3 (2)	--	--	annually
<b><u>Crotty Street Channel (CSC)</u></b>				
CSC	MW1	--	--	annually
CSC	MW2	--	--	annually
CSC	MW3	--	--	annually
CSC	MW4	--	--	annually
CSC	MW5	--	--	annually
CSC	Gage 1 (2)	--	--	annually
<b><u>Stormwater System(3)</u></b>				
MSA(5)	Extraction System	PCBs	Semi-annually	--
LA(5)	Extraction System	PCBs	Semi-annually	--
CSC(5)	Extraction System	PCBs	Semi-annually	--
SWTP(4)	Influent from Lagoons	PCBs	Semi-annually	--
CSC(5)	CB2	PCBs	Semi-annually	--

## Notes:

- (1) Static water level monitoring refers to independent monitoring program to evaluate containment. Static water level measurements will also be collected at all groundwater quality monitoring wells to evaluate groundwater flow directions.
- (2) Staff gauge.
- (3) Extraction system monitoring.
- (4) To be sampled by plant personnel.
- (5) To be sampled by REALM personnel.

**TABLE 5.1**  
**REPORTING REQUIREMENTS**  
**MONITORING, OPERATION, AND MAINTENANCE ACTIVITIES**  
**GM POWERTRAIN GROUP, BAY CITY PLANT**  
**BAY CITY, MICHIGAN**

<i><b>Action</b></i>	<i><b>Requirements for Reporting</b></i>
Site inspection and maintenance activity report	Within 60 days of completion of activities. Semi-annually for 2 years and annually for an other 28 years.
Static Water Level Monitoring	Within 45 days following each static water level monitoring event. Monthly until March 2001, then in conjunction with groundwater sampling events.
Groundwater Sampling	Within 60 days of receiving validated sampling event analytical data. Semi-annually until September 2001, and annually for an other 25 years.
Contingency Plan	If needed due to contaminant migration or other significant changes, verbal notification to MDEQ within 3 business days, and written proposal of contingencies within 10 business days.
Site Modifications	Any intrusive work must be reported and approved prior to commencement.
Archimedes Screw Pump System is shut down	Verbal notification to MDEQ within 2 business days, followed by written notification within 7 days.

TABLE 8.1

**ANALYTICAL PARAMETERS  
GM POWERTRAIN GROUP, BAY CITY PLANT  
BAY CITY, MICHIGAN**

<b><i>Sample Parameters</i></b>	<b><i>Sample Method</i></b>	<b><i>Target Detection Limits (ug/l)</i></b>
<b><u>Metals</u></b>		
Antimony	SW-846 6020	2.0
Arsenic	SW-846 6020	2.0
Barium	SW-846 6020	1.0
Beryllium	SW-846 6020	1.0
Cadmium	SW-846 6020	1.0
Chromium	SW-846 6020	2.0
Cobalt	SW-846 6020	1.0
Copper	SW-846 6020	2.0
Lead	SW-846 6020	1.0
Mercury	SW-846 7470A	0.2
Nickel	SW-846 6020	2.0
Selenium	SW-846 6020	2.0
Silver	SW-846 6020	1.0
Thallium	SW-846 6020	1.0
Tin	SW-846 6020	10.0
Vanadium	SW-846 6020	10.0
Zinc	SW-846 6010B	20.0
<b><u>PCBs</u></b>		
Aroclor-1016	SW-846 8082	0.2
Aroclor-1221	SW-846 8082	0.2
Aroclor-1232	SW-846 8082	0.4
Aroclor-1242	SW-846 8082	0.2
Aroclor-1248	SW-846 8082	0.2
Aroclor-1254	SW-846 8082	0.2
Aroclor-1260	SW-846 8082	0.2
<b><u>Appendix IX Volatile Organic Carbons</u></b>		
1,1,1,2-Tetrachloroethane	SW-846 8260B	1.0
1,1,1-Trichloroethane	SW-846 8260B	1.0
1,1,2,2-Tetrachloroethane	SW-846 8260B	1.0
1,1,2-Trichloroethane	SW-846 8260B	1.0
1,1-Dichloroethane	SW-846 8260B	1.0
1,1-Dichloroethene	SW-846 8260B	1.0
1,2,3-Trichloropropane	SW-846 8260B	1.0

**ANALYTICAL PARAMETERS  
GM POWERTRAIN GROUP, BAY CITY PLANT  
BAY CITY, MICHIGAN**

<b>Sample Parameters</b>	<b>Sample Method</b>	<b>Target Detection Limits (ug/l)</b>
<b><u>Appendix IX Volatile Organic Carbons (cont'd.)</u></b>		
1,2-Dibromo-3-chloropropane (DBCP)	SW-846 8260B	1.0
1,2-Dibromoethane (EDB)	SW-846 8260B	1.0
1,2-Dichloroethane	SW-846 8260B	1.0
1,2-Dichloroethene (total)	SW-846 8260B	1.0
1,2-Dichloropropane	SW-846 8260B	1.0
1,4-Dioxane	SW-846 8260B	50.0
2-Butanone	SW-846 8260B	10.0
2-Hexanone	SW-846 8260B	10.0
4-Methyl-2-pentanone	SW-846 8260B	10.0
Acetone	SW-846 8260B	10.0
Acetonitrile	SW-846 8260B	20.0
Acrolein	SW-846 8260B	20.0
Acrylonitrile	SW-846 8260B	20.0
Allyl chloride	SW-846 8260B	2.0
Benzene	SW-846 8260B	1.0
Bromodichloromethane	SW-846 8260B	1.0
Bromoform	SW-846 8260B	1.0
Bromomethane	SW-846 8260B	1.0
Carbon disulfide	SW-846 8260B	1.0
Carbon tetrachloride	SW-846 8260B	1.0
Chlorobenzene	SW-846 8260B	1.0
Chloroethane	SW-846 8260B	1.0
Chloroform	SW-846 8260B	1.0
Chloromethane	SW-846 8260B	1.0
Chloroprene	SW-846 8260B	2.0
cis-1,3-Dichloropropene	SW-846 8260B	1.0
Dibromochloromethane	SW-846 8260B	1.0
Dibromomethane	SW-846 8260B	1.0
Dichlorodifluoromethane (CFC-12)	SW-846 8260B	1.0
Ethyl methacrylate	SW-846 8260B	1.0
Ethylbenzene	SW-846 8260B	1.0
Iodomethane	SW-846 8260B	1.0
Isobutyl alcohol	SW-846 8260B	50.0
Methyl acrylonitrile	SW-846 8260B	2.0
Methyl methacrylate	SW-846 8260B	2.0
Methylene chloride	SW-846 8260B	1.0
Propionitrile (Ethyl cyanide)	SW-846 8260B	4.0
Styrene	SW-846 8260B	1.0
Tetrachloroethene	SW-846 8260B	1.0
Toluene	SW-846 8260B	1.0
trans-1,3-Dichloropropene	SW-846 8260B	1.0
trans-1,4-Dichloro-2-butene	SW-846 8260B	1.0
Trichloroethene	SW-846 8260B	1.0
Trichlorofluoromethane (CFC-11)	SW-846 8260B	1.0
Vinyl acetate	SW-846 8260B	2.0
Vinyl chloride	SW-846 8260B	1.0
Xylene (total)	SW-846 8260B	1.0

APPENDIX A

OPERATION, MAINTENANCE, AND MONITORING FORMS

**MAINTENANCE ACTIVITY CHECKLIST  
GM POWERTRAIN GROUP, BAY CITY PLANT  
BAY CITY, MICHIGAN**

<b>Description</b>	<b>Frequency</b>	<b>Inspected By (Print)</b>	<b>Date</b>	<b>Inspection Results (1)</b>	<b>Nature of Maintenance/Repairs (1)</b>
O&M Log	Monthly	_____	_____	_____	_____
Site Log Book	Monthly	_____	_____	_____	_____
Extraction Well Water Levels	Monthly	_____	_____	_____	_____
Inspection	Monthly	_____	_____	_____	_____
Maintenance	Monthly - As Required	_____	_____	_____	_____
Level Transmitter Inspection	Monthly	_____	_____	_____	_____
Maintenance	Monthly - As Required	_____	_____	_____	_____
Calibration	Semi-Annually	_____	_____	_____	_____
Control Panel Inspection	Monthly	_____	_____	_____	_____
Maintenance	Monthly - As Required	_____	_____	_____	_____
Air Supply Manifold Inspection	Monthly	_____	_____	_____	_____

**MAINTENANCE ACTIVITY CHECKLIST  
GM POWERTRAIN GROUP, BAY CITY PLANT  
BAY CITY, MICHIGAN**

<b>Description</b>	<b>Frequency</b>	<b>Inspected By (Print)</b>	<b>Date</b>	<b>Inspection Results (1)</b>	<b>Nature of Maintenance/Repairs (1)</b>
Air Compressor Maintenance	Monthly - As Required	_____	_____	_____	_____
Heater Check	Monthly (Winter Season)	_____	_____	_____	_____
East Lagoon Sump Pump Inspection	Monthly	_____	_____	_____	_____
Maintenance	Monthly - As Required	_____	_____	_____	_____
Monitoring Well Sampling	As Required	_____	_____	_____	_____
Water Levels	As Required	_____	_____	_____	_____
General Maintenance	As required	_____	_____	_____	_____
Force Main Cleaning	As required	_____	_____	_____	_____
Flowmeter Cleaning	As required	_____	_____	_____	_____
Spare Parts Inventory	As used	_____	_____	_____	_____

**MAINTENANCE ACTIVITY CHECKLIST  
GM POWERTRAIN GROUP, BAY CITY PLANT  
BAY CITY, MICHIGAN**

<b>Description</b>	<b>Frequency</b>	<b>Inspected By (Print)</b>	<b>Date</b>	<b>Inspection Results (1)</b>	<b>Nature of Maintenance/Repairs (1)</b>
Staff Gauges Water Levels	As Required	_____	_____	_____	_____
Exposure Barriers	Monthly	_____	_____	_____	_____
SFA Pavement	Monthly	_____	_____	_____	_____
Multi-Layer Cap	Monthly	_____	_____	_____	_____
Containment System	Monthly	_____	_____	_____	_____
Stormwater Collection System	Monthly	_____	_____	_____	_____
Crotty Street Channel Abandoned 60" Sewer	Monthly	_____	_____	_____	_____

\* Note: All of the suggested frequencies are minimums and additional maintenance may be required  
(1) - Attach additional documentation.

**O&M LOG  
GM POWERTRAIN GROUP, BAY CITY PLANT  
BAY CITY, MICHIGAN**

EW#	NAME (print)	DATE	NAME (print)	DATE	NAME (print)	DATE	NOTES, DESCRIPTION OF MAINT., SPARE PARTS USED
EW-1	VISUAL						
	COUNTER						
	WATER LEVEL (ft.)						
	PUMP MAINT. (y/n)						
EW-2	VISUAL						
	COUNTER						
	WATER LEVEL (ft.)						
	PUMP MAINT. (y/n)						
EW-3	VISUAL						
	COUNTER						
	WATER LEVEL (ft.)						
	PUMP MAINT. (y/n)						
EW-4	VISUAL						
	COUNTER						
	WATER LEVEL (ft.)						
	PUMP MAINT. (y/n)						
EW-5	VISUAL						
	COUNTER						
	WATER LEVEL (ft.)						
	PUMP MAINT. (y/n)						
FQIT-02	FLOW (gpm)						
	TOTAL (gal.)						
LT-02							
CP-02							
AIR SUPPLY MANIFOLD							
LAGOON SUMP							
AIR COMPRESSOR							
HEATER							

**O&M LOG  
GM POWERTRAIN GROUP, BAY CITY PLANT  
BAY CITY, MICHIGAN**

EW#		NAME (print)	DATE	NAME (print)	DATE	NAME (print)	DATE	NOTES, DESCRIPTION OF MAINT., SPARE PARTS USED
EW-6	VISUAL							
	COUNTER							
	WATER LEVEL (ft.)							
	PUMP MAINT. (y/n)							
EW-7	VISUAL							
	COUNTER							
	WATER LEVEL (ft.)							
	PUMP MAINT. (y/n)							
EW-8	VISUAL							
	COUNTER							
	WATER LEVEL (ft.)							
	PUMP MAINT. (y/n)							
EW-9	VISUAL							
	COUNTER							
	WATER LEVEL (ft.)							
	PUMP MAINT. (y/n)							
EW-10	VISUAL							
	COUNTER							
	WATER LEVEL (ft.)							
	PUMP MAINT. (y/n)							
EW-11	VISUAL							
	COUNTER							
	WATER LEVEL (ft.)							
	PUMP MAINT. (y/n)							
EW-12	VISUAL							
	COUNTER							
	WATER LEVEL (ft.)							
	PUMP MAINT. (y/n)							
FQIT-01	FLOW (gpm)							
	TOTAL (gal.)							

**O&M LOG  
GM POWERTRAIN GROUP, BAY CITY PLANT  
BAY CITY, MICHIGAN**

EW#		NAME (print)	DATE	NAME (print)	DATE	NAME (print)	DATE	NOTES, DESCRIPTION OF MAINT., SPARE PARTS USED
LT-01								
CP-01								
AIR SUPPLY MANIFOLD								
FUEL STORAGE AREA SUMP								
HEATER								
EW-13	VISUAL							
	COUNTER							
	WATER LEVEL (ft.)							
	PUMP MAINT. (y/n)							
EW-14	VISUAL							
	COUNTER							
	WATER LEVEL (ft.)							
	PUMP MAINT. (y/n)							
EW-15	VISUAL							
	COUNTER							
	WATER LEVEL (ft.)							
	PUMP MAINT. (y/n)							
FQIT-03	FLOW (gpm)							
	TOTAL (gal.)							
HEATER								

## SAMPLE COLLECTION DATA SHEET - GROUNDWATER SAMPLING PROGRAM

PROJECT NAME GMPT Bay City  
 SAMPLING CREW MEMBERS \_\_\_\_\_  
 DATE OF SAMPLE COLLECTION \_\_\_\_\_

PROJECT NO. 12610-10/20

[Note: For 1"(0.04gal), 2"(0.16gal), 3"(0.37gal), 4"(0.65gal), 5"(1.02gal), 6"(1.47gal),8"(2.61gal), 10"(4.08gal), 12"(5.88gal) per foot of water column]

Sample I.D. Number	Well Number	Reference Elevation (ft.AMSL)	Water Depth (ft.btor)	Groundwater Elevation (ft.AMSL)	Bottom Depth (ft.btor)	Well Volume (gal.)	Volume Purged (gal.)	Field pH	Sample Parameters	Field Temp. (° C)	Field DO	Field Comments
	MW502D	589.28							PCB / Metal			Bladder Pump
	MW503D	588.54							PCB / Metal			Bladder Pump
	MW503S	588.69							PCB / Metal			Bladder Pump
	MW504S	585.54							PCB / Metal			Bladder Pump
	MW506S	588.85							PCB / Metal			Bladder Pump
	MW508SR	591.26							PCB / Metal			Bladder Pump
	MW1-00	588.26										--
	MW2-00	589.29										--
	MW3-00	588.4										--
	MW4-00	589.65										--
	MW5-00	588.89										--
	GAGE-1	569.43										Top of Gage
	GAGE-5	569.47										Top of Gage
	GAGE-2	569.4										Top of Gage
	GAGE-4	579.52										Top of Gage
	GAGE-3	579.24										Top of Gage

**Additional Comments:** \_\_\_\_\_

**Copies to:** \_\_\_\_\_

**CRA**

APPENDIX B

MONITORING AND EXTRACTION WELL LOGS

APPENDIX C

MANUFACTURER PRODUCT INFORMATION

**APPENDIX C**  
**MANUFACTURER PRODUCT INFORMATION INDEX**

1. Static Water Level Meter.
2. Extraction Well Pumps and Counters.
3. Membrane Dryer for RWPS.
4. Nexteq Scale Free Units.
5. Union Ball Check Valves.
6. Transformer, Disconnect, and Circuit Breakers.
7. Extraction System Tubing.
8. Pressure Transmitter.
9. Magnetic Flow Meters for groundwater extraction systems.
10. Remote Access Sensaphone 2000 Data Logger.
11. Quincy QT and PLT Series Compressors.
12. Heater for Extraction Well Meter.

APPENDIX D

HEALTH AND SAFETY PLAN

## TABLE OF CONTENTS

	<u>Page</u>
1.0 INTRODUCTION.....	D-1
2.0 SITE CHARACTERIZATION AND POTENTIALLY HAZARDOUS COMPOUNDS.....	D-3
3.0 BASIS FOR DESIGN .....	D-4
4.0 RESPONSIBILITIES AND ADMINISTRATION .....	D-5
5.0 WORKER TRAINING AND EDUCATION.....	D-6
6.0 PERSONAL PROTECTIVE EQUIPMENT (PPE).....	D-7
6.1 PROTECTION LEVELS .....	D-7
6.2 REASSESSMENT OF PROTECTION LEVELS .....	D-9
6.3 DURATION OF WORK TASKS .....	D-10
6.4 LIMITATIONS OF PROTECTIVE CLOTHING .....	D-10
6.5 RESPIRATORY PROTECTION PROGRAM.....	D-12
6.6 SITE CONTROL.....	D-13
7.0 ACTIVITY HAZARD/RISK ANALYSIS .....	D-15
7.1 CHEMICAL EXPOSURE .....	D-15
8.0 AIR MONITORING.....	D-18
9.0 DECONTAMINATION PROCEDURES.....	D-19
9.1 EQUIPMENT DECONTAMINATION PROCEDURES.....	D-19
9.2 PERSONNEL DECONTAMINATION PROCEDURES.....	D-19
10.0 GENERAL SAFETY AND PERSONAL HYGIENE.....	D-20
11.0 MEDICAL SURVEILLANCE.....	D-21
12..0 ENVIRONMENTAL CONTROL PROGRAM .....	D-22
12.1 WEATHER MONITORING .....	D-22
12.2 RAIN AND SNOW.....	D-22
12.3 TEMPERATURE .....	D-22
12.4 WIND .....	D-23
12.5 WORKING IN AND ON THE RIVER.....	D-23
13.0 CONFINED SPACE ENTRY PROCEDURE.....	D-24

TABLE OF CONTENTS

	<u>Page</u>
14.0 EMERGENCY RESPONSE.....	D-25
14.1 EMERGENCY CONTACTS .....	D-25
14.2 ADDITIONAL EMERGENCY NUMBERS .....	D-25
14.3 EMERGENCY EQUIPMENT AVAILABLE ON SITE .....	D-26
14.4 PROJECT PERSONNEL RESPONSIBILITIES DURING EMERGENCIES.....	D-26
14.5 MEDICAL EMERGENCIES .....	D-27
14.6 FIRE OR EXPLOSION.....	D-27
14.7 SPILLS OR CONTAINER LEAKS.....	D-28
15.0 RECORDKEEPING.....	D-29

LIST OF FIGURES  
(Following Report)

FIGURE D1.1	SITE LOCATION MAP
FIGURE D1.2	SITE PLAN
FIGURE D14.1	EMERGENCY HOSPITAL ROUTE

LIST OF TABLES  
(Following Report)

TABLE D2.1	POTENTIAL CHEMICAL COMPOUNDS OF CONCERN
TABLE D6.1	SPECIFIC PERSONAL PROTECTIVE LEVELS
TABLE D7.1	ANTICIPATED HAZARDS/RISKS AND APPROPRIATE PRECAUTIONS

## **1.0 INTRODUCTION**

The Health and Safety Plan (HASP) presented herein describes the health and safety procedures and emergency response guidelines to be implemented during the Monitoring, Operation, and Maintenance Plan (O&M Plan) at the General Motors Powertrain Group, Bay City Plant (Site) located in Bay City, Michigan. Figures D1.1 and D1.2 present the Site location and Site layout, respectively.

The scope of work to be completed during the O&M Plan includes the following work activities:

- i) mobilization and demobilization of labor, materials, and equipment to and from the Site;
- ii) Machine Storage Area:
  - a) inspection and maintenance of multi-layer cap,
  - b) groundwater monitoring,
  - c) inspection and maintenance of the groundwater extraction system and appurtenances;
- iii) Lagoon Areas:
  - a) groundwater monitoring,
  - b) inspection and maintenance of the groundwater extraction system and appurtenances;
- iv) Perimeter Banks:
  - a) groundwater monitoring,
  - b) multi-layer cap inspection and maintenance,
  - c) inspection and maintenance of sheet pile wall;
- v) Support Facilities Area:
  - a) inspection and maintenance of paved areas,
  - b) water level measurements;
- vi) Undeveloped Area:
  - a) groundwater monitoring,
  - b) inspection and maintenance of cover;
- vii) Crotty Street Channel:
  - a) inspection and maintenance of multi-layer cap,
  - b) groundwater monitoring,

- c) inspection and maintenance of the groundwater extraction system and appertenances,
- d) inspection and maintenance of sheet pile wall; and
- vii) decontamination activities.

During a portion of these activities, personnel may come in contact with soils and groundwater, which may contain hazardous substances. This HASP has been developed to minimize direct contact by Site personnel with materials potentially having chemical presence by ensuring:

- i) that Site personnel are not adversely exposed to the compounds of concern;
- ii) that public health and the environment are not adversely impacted by materials with elevated chemical presence which may potentially migrate off-Site during O&M activities at the Site;
- iii) compliance with applicable governmental and non-governmental (American Conference of Governmental Industrial Hygienists [ACGIH]) regulations and guidelines. In particular, the amended rules of the Occupational Safety and Health Administration (OSHA) for Subpart H of Part 1910 (Title 29 Code of Federal Regulations [CFR] Part 1910.120) will be implemented for all Site work; and
- iv) initiation of proper emergency response procedures to minimize the potential for any adverse impact to Site workers, the general public, or the environment.

For the purpose of this HASP, activities performed on Site involving contact with materials with potentially elevated chemical presence will be considered contaminated operations requiring Personal Protective Equipment (PPE). A detailed description of the PPE required is presented in Section 6.1.

The applicability of this HASP extends to all personnel who will be on Site, including State and Federal Agency personnel, contractors, subcontractors, and visitors to the Site. Subcontractors who will work with CRA Services at the Site will be required to prepare and implement a HASP for their Site personnel. They may contractually adopt this HASP.

All O&M activities at the Site will be conducted in accordance with the provisions of an approved Site-specific HASP. A copy of this HASP and employer-specific Standard Operating Procedures (SOPs) will be maintained on Site whenever activities are in progress.

## **2.0 SITE CHARACTERIZATION AND POTENTIALLY HAZARDOUS COMPOUNDS**

---

Previous Site investigations have detected the presence of chemicals on Site. Table D2.1 presents a list of the potential chemical compounds of concern at the Site. The exposure routes and regulatory time weighted average (TWA) exposure levels for these compounds of concern are also listed in Table D2. 1. These levels are set to protect the health of workers.

### **3.0 BASIS FOR DESIGN**

Regulations set forth by OSHA in Title 29, Code of Federal Regulations, Parts 1910 and 1926 (29 CFR 1910 and 1926) form the basis of this HASP. Emphasis is placed on Sections 1910.120 (Hazardous Waste Operations and Emergency Response), 1910 Subpart I (Personal Protective Equipment), and 1910 Subpart Z (Toxic and Hazardous Substances). In addition, current Threshold Limit Values (TLVs) formulated by the ACGIH have been considered in the development of the selection of PPE. Some of the specifications within this section are in addition to the OSHA regulations, and reflect the positions of the United States Environmental Protection Agency (USEPA), the National Institute for Occupational Safety and Health (NIOSH), and the United States Coast Guard (USCG) regarding safe operating procedures at hazardous waste sites.

The health and safety of the public and Site personnel and the protection of the environment will take precedence over cost and schedule considerations for all project work.

#### **4.0 RESPONSIBILITIES AND ADMINISTRATION**

The Construction Superintendent shall be responsible, along with the HSO, for all decisions regarding operations and work stoppage due to health and safety considerations. The HSO will have prior experience in working at hazardous waste sites.

The on-Site HSO responsibilities include:

- i) supervision and enforcement of safety equipment usage, including the required use of extra equipment if appropriate;
- ii) supervision and inspection of equipment cleaning;
- iii) supervision of decontamination;
- iv) conduct the on-Site personnel safety indoctrination session for potential hazards, personal hygiene principles, confined space entry procedures, all other SOPs, safety equipment usage, emergency procedures, and location of first aid kits and identification of personnel trained in first aid and cardiopulmonary resuscitation (CPR);
- v) maintain Exclusion Zone (EZ) and Contaminant Reduction Zone (CRZ) work areas;
- vi) review and modify the HASP as more information becomes available or conditions warrant;
- vii) issue a confined space entry permit as required;
- viii) authority to suspend work activity due to unsafe working conditions;
- ix) coordination of emergency procedures;
- x) be responsible for performing air monitoring;
- xi) ensure that all on-Site personnel have obtained the required medical examination prior to arrival at the Site, have met the OSHA training requirements, and have been fit tested for the respiratory equipment they may use;
- xii) maintain the on-Site Hazard Communication Program including copies of Material Safety Data Sheets (MSDSs); and
- xiii) conduct brief daily safety meetings.

## **5.0 WORKER TRAINING AND EDUCATION**

Prior to commencing Site activities, a Health and Safety/Site Indoctrination Session will be presented. Attendance is mandatory for all personnel who will be or who are expected to be involved with project activities.

The training program will stress the importance that each attendee understands the basic principles of personnel protection and safety, be able to perform their assigned job tasks in a safe and environmentally responsible manner, and be prepared to respond in an appropriate manner to any emergency which may arise. A brief history of the Site will be included and the various components of the project HASP will be presented followed by an opportunity to ask questions to ensure that each attendee understands the HASP. Personnel not successfully completing this training program will not be permitted to enter or work in potentially contaminated areas of the Site.

This training will be given in addition to the basic training required under OSHA and is not intended to meet the requirements of 29 CFR 1910.120. Prior to working in or entering an EZ environment (as defined in Section 6.0), all personnel will be required to provide documentation to the HSO indicating successful completion of the training requirements of 29 CFR 1910.120.

## **6.0 PERSONAL PROTECTIVE EQUIPMENT (PPE)**

This section of the HASP describes the requirements for PPE and the specific levels of protection required for each work task to be conducted at the Site during project activities. Basic PPE in all Site areas will consist of hard hats, safety glasses, and safety boots/shoes.

### **6.1 PROTECTION LEVELS**

Personnel will wear protective equipment when project activities involve potential exposure to chemicals from vapors, gases, or particulates that may be generated on Site or when direct contact with potentially hazardous substances may occur. Chemical resistant clothing protects the skin from contact with skin-destructive and absorbable chemicals. Respirators protect lungs, the gastrointestinal tract, and if a full-face respirator is worn, the eyes, against airborne toxicants. Respiratory protection levels will be based on the real-time air monitoring results and the action levels that are presented in Section 6.5.

Protection levels are selected based upon the following:

- i) measured concentrations of the Site chemicals and expected concentrations in the ambient atmosphere compared to allowable exposure levels (Table D2.1);
- ii) potential for exposure to chemicals in air, splashes of liquids, or other contact due to the nature of work tasks; and
- iii) Site chemical toxicity, route of exposure, and chemical matrix.

The specific protection levels to be employed at the Site for each work task are listed in Table D6.1. All project activities conducted at the Site will require the use of one of the following levels of PPE.

#### **Level B (Not Expected to be Worn):**

- i) supplied air respirator (Mine Safety and Health Administration [MSHA]/NIOSH approved). Respirators may be positive pressure-demand, self-contained breathing apparatus (SCBA) or positive pressure-demand airline respirator (with escape bottle for Immediately Dangerous to Life and Health [IDLH] or potential for IDLH atmosphere);
- ii) polycoated tyvek® or saranex® coveralls;

- iii) steel toe work boots and disposable boot covers or rubber boots;
- iv) disposable nitrile inner gloves;
- v) outer nitrile work gloves;
- vi) hearing protection as necessary;
- vii) personal floatation device as necessary; and
- viii) hard hat.

Level C:

- i) tyvek® coveralls [polycoated tyvek® when handling or working with liquids (e.g., decontamination)];
- ii) steel toe work boots disposable boot covers or rubber boots;
- iii) disposable cotton inner gloves as necessary;
- iv) outer nitrile work gloves;
- v) half-face or full-face air purifying respirator (APR), equipped with combination cartridges for organic vapors and particulates (P-100);
- vi) hearing protection device as necessary;
- vii) personal floatation device as necessary; and
- viii) hard hat.

Modified Level D:

- i) tyvek® coveralls (polycoated tyvek® when handling or working with liquids);
- ii) steel toe work boots;
- iii) disposable cotton inner gloves as necessary;
- iv) outer nitrile work gloves;
- v) safety glasses;
- vi) splash shields as necessary;
- vii) hearing protection as necessary;
- viii) personal floatation device as necessary; and
- ix) hard hat.

Level D:

- i) standard work uniform or coveralls;
- ii) steel toe work boots;

- iii) gloves as necessary;
- iv) safety glasses;
- v) splash shield as needed;
- vi) hearing protection as necessary;
- vii) personal floatation device as necessary; and
- viii) hard hat.

PPE will be maintained in a clean sanitary condition and ready for use. Disposable coveralls shall be discarded when torn and as an employee leaves the EZ. Hard hats shall be thoroughly cleaned after leaving the EZ. Respirators shall be cleaned after each day's use and cartridges discarded. A sufficient quantity of potable water shall be supplied for washing, cleaning PPE, and drinking. A potable water supply for washing and cleaning PPE will be maintained adjacent to the decontamination area described in Section 9.0. Fresh potable water for drinking will be supplied on a daily basis and be maintained at a location removed from the active work area.

## **6.2 REASSESSMENT OF PROTECTION LEVELS**

Protection levels provided by PPE selection shall be upgraded or downgraded based upon a change in Site conditions or the review of the results of air monitoring.

When a significant change occurs, the hazards should be reassessed. Some indicators of the need for reassessment are:

- i) commencement of a new work phase;
- ii) change in job tasks during a work phase;
- iii) change of season/weather;
- iv) when temperature extremes or individual medical considerations limit the effectiveness of PPE;
- v) chemicals other than those expected to be encountered are identified;
- vi) change in ambient levels of chemicals; and
- vii) change in work scope which effects the degree of contact with areas of potentially elevated chemical presence.

All proposed changes to protection levels and PPE requirements will be reviewed and approved prior to their implementation by the HSO.

### **6.3 DURATION OF WORK TASKS**

The duration of project activities involving the usage of PPE will be established by the HSO or his designee based upon ambient temperature and weather conditions, the capacity of personnel to work in the designated level of PPE (heat stress and cold stress, see Section 12.3 - Environmental Control), and limitations of the protective equipment (i.e., ensemble permeation rates, life expectancy of air-purifying respirator cartridges, etc.). As a minimum, rest breaks will be observed at the following intervals:

- i) 15 minutes midway between shift startup and lunch;
- ii) 1/2 to 1 hour for lunch; and
- iii) 15 minutes in the afternoon, between lunch and shift end.

All rest breaks will be taken in a clean area (e.g., support zone) after full decontamination and PPE removal. Additional rest breaks will be observed, based upon the heat stress monitoring guidelines presented in the CRA Services Health and Safety SOPs.

### **6.4 LIMITATIONS OF PROTECTIVE CLOTHING**

PPE ensembles designated for use during project activities have been selected to provide protection against chemicals at known or anticipated concentrations in the soil and groundwater. However, no protective garment, glove, or boot is chemical-proof, nor will it afford protection against all chemical types. Permeation of a given chemical through PPE is a complex process governed by the chemical concentrations, environmental conditions, physical condition of the protection garment, and the resistance of a garment to a specific chemical; chemical permeation may continue even after the source of the chemical has been removed from the garment.

In order to obtain optimum usage from PPE, the following procedures are to be followed by all Site personnel using PPE:

- i) when using disposable coveralls, don a clean, new garment after each rest break or at the beginning of each shift;
- ii) inspect all clothing, gloves, and boots both prior to and during use for:
  - a) imperfect seams,

- b) non-uniform coatings,
- c) tears,
- d) poorly functioning closures; and
- iii) inspect reusable garments, boots, and gloves both prior to and during use for:
  - a) visible signs of chemical permeation,
  - b) swelling,
  - c) discoloration,
  - d) stiffness,
  - e) brittleness,
  - f) cracks,
  - g) any sign of puncture, and
  - h) any sign of abrasion.

Reusable gloves, boots, or coveralls exhibiting any of the characteristics listed above will be discarded. PPE used in areas known or suspected to exhibit elevated concentrations of chemicals will not be reused.

Additional PPE usage guidelines are as follows:

- i) ankles/wrists will be secured tightly with the use of duct tape;
- ii) prescription eyewear used on Site shall be safety glasses equipped with side shields when full-face respirators are not required. Contact lenses shall not be used;
- iii) all EZ workers will have received training in the usage of full-face air purifying respirators and SCBA which may be required in an emergency;
- iv) steel toe leather footwear shall be covered with neoprene overboots prior to entering the EZ and immediately upon entering the CRZ; and
- v) safety footwear and hard hats are to be worn by Site personnel at all times.

EZ personnel also carry certain responsibilities for their own health and safety, and are required to observe the following safe work practices:

- i) familiarize themselves with this HASP;
- ii) use the "buddy system" when working in a contaminated operation;

- iii) use the safety equipment in accordance with training received, labeling instructions, and common sense;
- iv) maintain safety equipment in good condition and proper working order;
- v) refrain from activities that would create additional hazards (i.e., smoking, eating, etc., in restricted areas, leaning against dirty, contaminated surfaces);
- vi) smoking, eating, and drinking will be prohibited except in designated areas. These designated areas may change during the duration of the project to maintain adequate separation from the active work area(s). Designation of these areas will be the responsibility of the HSO; and
- vii) soiled disposable outerwear shall be removed and placed into a covered container prior to washing hands and face, eating, using lavatory facilities, or leaving the Site.

## **6.5 RESPIRATORY PROTECTION PROGRAM**

Prior to arriving at the Site, all on-Site personnel will have received training in the use of, and have been fit tested for a full-facepiece respirator. All on-Site personnel will be required to comply with their employer specific written respiratory protection program developed in accordance with OSHA 29 CFR 1910.134.

Respiratory protection may be required during some of the project activities. This is to ensure worker protection from potentially contaminated particulates and volatile organic compounds (VOCs).

A photoionization detector (PID) will be used to determine if organic vapors are present. A background reading will be established prior to commencing work activities at each active work area.

Action levels to determine the level of respiratory protection necessary during Project activities are based on the concentration of the Site chemicals measured within the breathing zone. The action levels and appropriate respiratory protection for these Site activities are as follows:

***Sustained Organic Vapor Reading Above  
Background Within Worker Breathing  
Zone in Parts Per Million (ppm)***

***Action Taken***

0 or Background  
1-50  
>50

Full-Face Respirator Available  
Wear Full-Face Respirator  
Must Wear Supplied Air Respiratory/Implement  
Additional Engineering Controls

All efforts will be made to implement additional engineering controls to minimize the need to wear a supplied air respirator. If the ambient concentrations of organic vapors are due to identifiable substances, the level of respiratory protection may be altered by the HSO.

The appropriate air purifying respirator cartridge to be used at the Site is a combination organic vapor and P-100 particulate cartridge. The cartridge used must be of the same manufacturer as the respiratory face piece.

**6.6 SITE CONTROL**

A temporary fence will be installed to prevent unauthorized access to the project work areas. Powertrain personnel may gain access to the other side of the fence only if they are escorted. The intention is to keep them out of the EZ. Designated work areas will be set up as appropriate inside the fence during the Site field activities, as required. The purpose of these procedures is to limit access to areas with potentially elevated chemical presence, and prevent the migration of potentially hazardous materials into adjacent clean areas. These areas are described in the following:

- i) The Exclusion Zone (EZ) is the area immediately surrounding the active work area. Sufficient area will be provided for efficient movement of personnel and equipment as well as chemical control. Boundaries are modifiable depending on operational requirements. The HSO will be responsible for maintaining the boundaries of this area. Personnel entering this area are required to wear the PPE as defined previously. A wind direction indication device (i.e., flagging, windsock, etc.) will be mounted in the area of any EZ during Site activities.

All personnel (including visitors) entering the EZ or CRZ using respiratory protection must have successfully passed a qualitative respirator fit test in accordance with OSHA 29 CFR 1910.134. Documentation of fit testing is the responsibility of each employer.

In the event that unauthorized personnel enter the EZ, work will stop. Work will not resume until the unauthorized personnel have been removed from the EZ or have been moved to an acceptable on-Site area. A log of all visitors to the Site, including those entering the EZ, will be maintained.

ii) The Contaminant Reduction Zone (CRZ) will provide a location for removal of PPE which has contacted material with elevated chemical presence and final removal and decontamination of personnel and equipment. Supplemental safety equipment, such as fire extinguishers, portable eyewash, and extra quantities of PPE may be stored in this area. The order in which safety equipment is to be donned is as follows:

- a) tyvek® suit;
- b) rubber boot;
- c) gloves;
- d) respirator (if required); and
- e) hard hat.

The following order applies when removing safety equipment:

- a) wash off boots and outer gloves prior to removal;
- b) tyvek® suit
- c) hard hat;
- d) respirator; and
- e) inner gloves.

iii) The Support Zone (SZ) is situated in clean areas where there is a minimal risk of encountering hazardous materials or conditions. PPE beyond standard construction safety equipment is therefore not required.

## **7.0 ACTIVITY HAZARD/RISK ANALYSIS**

This section identifies the general hazards associated with specific project activities and presents the documented or potential health and safety hazards that exist at the Site. Every effort will be made to reduce or eliminate these hazards. Those which cannot be eliminated must be guarded against by use of engineering controls and/or PPE. Table D7.1 presents the anticipated hazards/risks and hazard controls.

In addition to the chemical hazards presented in Section 2.0 of this HASP, physical hazards including uneven terrain, steep slopes, slippery surfaces, potential confined spaces, the use of heavy equipment, potential drowning from working in and on the River, the use of decontamination equipment and potential heat and cold stress exist at the Site. It will be the responsibility of each on-Site contractor and their personnel to identify the physical hazards posed by the various Site project activities and implement preventative and corrective action.

### **7.1 CHEMICAL EXPOSURE**

Preventing exposure to toxic chemicals is a primary concern. Chemical substances can enter the unprotected body by inhalation, skin absorption, ingestion, or through a puncture wound (injection). A contaminant can cause damage at the point of contact or can act systematically, causing a toxic effect at a part of the body distant from the point of initial contact.

Chemical exposures are generally divided into two categories: acute and chronic. Symptoms resulting from acute exposures usually occur during or shortly after exposure to a sufficiently high concentration of a chemical. The concentration required to produce such effects varies widely from chemical to chemical. The term "chronic exposure" generally refers to exposures to "low" concentrations of a contaminant over a long period of time. The "low" concentrations required to produce symptoms of chronic exposure depend upon the chemical, the duration of each exposure, and the number of exposures. For a given chemical, the symptoms of an acute exposure may be completely different from those resulting from chronic exposure.

For either chronic or acute exposure, the toxic effect may be temporary and reversible, or may be permanent (disability or death). Some chemicals may cause obvious symptoms such as burning, coughing, nausea, tearing eyes, or rashes. Other chemicals may cause health damage without any such warning signs (this is a particular concern for chronic exposures to low concentrations). Health effects such as cancer or respiratory disease

may not become manifest for several years or decades after exposure. In addition, some toxic chemicals may be colorless and/or odorless, may dull the sense of smell, or may not produce any immediate or obvious physiological sensations. Thus, a worker's senses or feelings cannot be relied upon in all cases to warn of potential toxic exposure.

The effects of exposure not only depend on the chemical, its concentration, route of entry, and duration of exposure, but may also be influenced by personal factors such as the individual's smoking habits, alcohol consumption, medication use, nutrition, age, and sex.

An important exposure route of concern at the Site is inhalation. The lungs are extremely vulnerable to chemical agents. Even substances that do not directly affect the lungs may pass through lung tissue into the bloodstream, where they are transported to other vulnerable areas of the body. Some toxic chemicals present in the atmosphere may not be detected by human senses (i.e., they may be colorless, odorless, and their toxic effects may not produce any immediate symptoms). Respiratory protection is therefore extremely important if there is a possibility that the work site atmosphere may contain such hazardous substances. Chemicals also can enter the respiratory tract through punctured eardrums. Where this is a hazard, individuals with punctured eardrums should be medically evaluated specifically to determine if such a condition would place them at an unacceptable risk and preclude their working at the task in question.

Direct contact of the skin and eyes by hazardous substances is another important route of exposure. Some chemicals directly injure the skin. Some pass through the skin into the bloodstream where they are transported to vulnerable organs. Skin absorption is enhanced by abrasions, cuts, heat, and moisture. The eye is particularly vulnerable because airborne chemicals can dissolve in its moist surface and be carried to the rest of the body through the bloodstream (capillaries are very close to the surface of the eye). Wearing protective equipment, not using contact lenses in chemical atmospheres (since they may trap chemicals against the eye surface), keeping hands away from the face, and minimizing contact with liquid and solid chemicals can help protect against skin and eye contact.

Although ingestion should be the least significant route of exposure at the Site, it is important to be aware of how this type of exposure can occur. Deliberate ingestion of chemicals is unlikely, however, personal habits such as chewing gum or tobacco, drinking, eating, smoking cigarettes, and applying cosmetics at the Site may provide a route of entry for chemicals.

The last primary route of chemical exposure is injection, whereby chemicals are introduced into the body through puncture wounds (i.e., by stepping or tripping and falling onto contaminated sharp objects). Wearing safety shoes, avoiding physical hazards, and taking common sense precautions are important protective measures against injection.

## **8.0 AIR MONITORING**

During the progress of project activities, monitoring of organic vapors will be taken by the HSO. Additionally, oxygen and combustible gas levels will need to be taken if personnel enter into any confined space.

The following air monitoring instrumentation will be used for this purpose:

- i) a PID detector; and
- ii) a combination oxygen/combustible gas instrument.

All monitoring equipment will be calibrated on a daily basis in accordance with the manufacturer's guidelines, and such calibrations will be recorded in the Site daily log book. Results of all daily air monitoring also will be recorded in the Site daily log book.

Air monitoring will be conducted hourly in the breathing zone of workers in the EZ or as deemed necessary by the HSO based on Site-specific conditions. Background measurements immediately upwind of the EZ will be taken before activities commence. Respiratory action levels for organic vapors are discussed in Section 6.5.

Immediately upon identifying sustained elevated levels of organic vapors (greater than 50 ppm within the Work Zone, the air monitoring results will be reported to the Site Superintendent and work activities will be shut down. The HSO will determine the cause of the sustained elevated levels of organic vapors and alternate work methods or engineering controls will be implemented to rectify the release of elevated concentrations of organic vapors, or upgrade levels of PPE as required.

CRA will implement a personnel air monitoring program for workers having the highest potential for exposure to chemicals present on Site. Samples would be collected during the startup of activities, at locations where personnel would face potential exposure, to verify the adequacy of personal protection and to document the actual exposure level to the selected chemicals of concern. Samples will be collected and analyzed for the presence of the compounds of concern as determined by the HSO. It is expected that samples will be collected and analyzed for PCBs, lead, arsenic, and mercury. Appropriate NIOSH procedures and methods will be followed and all samples are to be sent to an American Industrial Hygiene Association (AIHA) accredited laboratory. Results of the air sampling program will be posted for personnel to review. Monitoring for oxygen and combustible gas levels will be continuous according to the confined space entry permit if personnel have to enter into any confined space.

## **9.0 DECONTAMINATION PROCEDURES**

In general, everything that enters the EZ at the Site must either be decontaminated or properly discarded upon exit from the EZ. All personnel, including any State and local officials, must enter and exit the EZ through the decontamination area. Prior to demobilization, potentially contaminated equipment will be decontaminated and inspected by the HSO before it is moved into the clean zone.

The type of decontamination solution to be used is dependent on the type of chemical hazards. The decontamination solution for this Site is Liquinox (soap) for equipment and for any reusable PPE.

### **9.1 EQUIPMENT DECONTAMINATION PROCEDURES**

All equipment must be decontaminated within the CRZ or on the decontamination pad by a pressure washer upon exit from the EZ. Decontamination procedures should include: knocking soil/mud from machines; water rinsing using a solution of water and Liquinox; scraping and brushing to remove remaining soils and a final water rinse. Personnel shall wear Level C protection when decontaminating equipment. Runoff will be collected and stored until appropriate disposal arrangements are made. Following decontamination and prior to equipment removal from the Site, the HSO shall be responsible for ensuring that the equipment has been properly cleaned. This inspection shall be included in the Site log book.

### **9.2 PERSONNEL DECONTAMINATION PROCEDURES**

Personnel decontamination will be completed in accordance with the CRA Health and Safety SOP for personnel decontamination.

## **10.0 GENERAL SAFETY AND PERSONAL HYGIENE**

1. Eating at the Site is prohibited except in specifically designated areas. Designation of eating areas will be the responsibility of the HSO. The location of these areas may change during the duration of the project to maintain adequate separation from the active work area(s).
2. Smoking at the Site is prohibited except in specifically designated areas.
3. Individuals getting wet to the skin with effluent from the washing operation must wash the affected area immediately. If clothes in contact with skin are wet, then these must be changed.
4. Hands must be washed with soap and water before eating, drinking, smoking, and before using toilets.
5. All disposable coveralls and soiled gloves will be placed in covered containers at the end of every shift or sooner, if deemed necessary by the HSO. Wastes will be stored until proper disposal arrangements have been made.
6. Personnel working on Site will not be permitted to wear facial hair that interferes with the mask-to-face seal on air-purifying respirators.

## **11.0 MEDICAL SURVEILLANCE**

In accordance with the requirements detailed in 29 CPR 1910.120 and 29 CFR 1910.134, all Site personnel who will come in contact with materials with potentially elevated chemical presence will have received, within 1 year prior to starting field activities, medical surveillance by a licensed physician or physician's group.

Medical records for all on-Site personnel will be maintained by their respective employers. The medical records will detail the tests that were taken and will include a copy of the consulting physician's statement regarding the tests and the employee's suitability for work.

The medical records will be available to the employee or his/her designated representative upon written request, as outlined in 29 CFR 1910.1020.

Each employer will provide certifications to the HSO that its personnel involved in Site activities will have all necessary medical examinations and will have obtained medical certification prior to commencing work which requires respiratory protection or potential exposure to hazardous materials. Personnel not obtaining medical certification will not perform work within the CRZ and EZ.

Interim medical surveillance will be completed if an individual exhibits poor health or high stress responses due to any Site activity or when accidental exposure to elevated concentrations of chemicals occur.

## **12..0 ENVIRONMENTAL CONTROL PROGRAM**

This section of the HASP outlines measures to be implemented at the Site to prevent hazards associated with environmental conditions.

### **12.1 WEATHER MONITORING**

The HSO or Site Superintendent will be responsible for checking weather forecasts for the next day and week of work to provide advance notification of any severe weather conditions. Severe weather conditions (e.g., heavy rains) may cause unsafe conditions at the site and in some situations work may have to be stopped.

### **12.2 RAIN AND SNOW**

Excessive amounts of precipitation may cause potential safety hazards for all work tasks. The hazards would be most commonly associated with slipping, tripping, or falling due to slippery surfaces and further hazards are detailed by work task (Table D7.1).

Severe weather conditions will result in work stoppage and the implementation of further emergency measures, as described in CRA's Health and Safety SOP.

### **12.3 TEMPERATURE**

The construction activities are expected to be conducted year round. Low and high temperatures may be experienced which require measures to be implemented to prevent health and safety hazards from occurring. Potential hazards arising from temperature extremes are heat stress and cold exposure.

The potential hazard due to worker heat stress is particularly important if high protection levels of PPE are in use (e.g., respirators). A detailed monitoring program and prevention measures to implement to reduce heat stress are detailed in CRAs Health and Safety SOP. It is the responsibility of the HSO to determine which measures are appropriate to implement to prevent heat stress; these will depend largely on daily Site conditions.

Exposure to cold is similar to heat stress in that the HSO must determine the appropriate preventative measures to implement. Some of the measures which may be implemented include: more frequent breaks, additional clothing, and partial enclosure of work areas. Detailed cold exposure prevention measures are also included in CRAs Health and Safety SOPs.

#### **12.4      WIND**

High winds may be encountered at the Site and these can cause hazards that may affect Site personnel health and safety. Preventative measures that will be implemented if necessary are as follows:

- i)      restricted Site activity;
- ii)     battening down light equipment or building materials;
- iii)    partially enclosing work areas; and
- iv)    reduction or stoppage of work activities.

#### **12.5      WORKING IN AND ON THE RIVER**

Working close to the River or from a barge stationed in the River can be dangerous. The River has a strong current and could carry any individual quite a distance if one falls into the River. Preventative measures that will be implemented when working in and/or on the River are as follows:

- i)      all personnel working from a boat, barge, and directly along the shoreline will wear a personal flotation device;
- ii)     a small boat will be immediately available to aid in any rescue attempt if personnel were to fall into the River; and
- iii)    the HSO will be consulted prior to anchoring any boat barge, or equipment in the River.

### **13.0 CONFINED SPACE ENTRY PROCEDURE**

A confined space provides the potential for unusually high concentrations of contaminants, explosive atmospheres, oxygen deficient atmospheres, limited visibility, and restricted movement. This section establishes requirements for safe entry into, continued work in, and safe exit from confined spaces. Additional information regarding confined space entry can be found in 29 CFR 1926.21, 29 CFR 1910.146, and NIOSH-106. Entry into a confined space will only be undertaken after remote methods have been tried and found not to be successful. If confined space entry is required, such work will only be undertaken following the guidelines presented in the CRAs Health and Safety SOPs.

**14.0 EMERGENCY RESPONSE**

It is essential that Site personnel be prepared in the event of an emergency. Emergencies can take many forms; illnesses or injuries, chemical exposure, fires, explosions, spills, leaks, releases of harmful contaminants, or sudden changes in the weather. The following sections outline the general procedures for emergencies. Emergency information should be posted as appropriate. All emergencies will be reported to the GMPT Emergency Response Team. They will give CRA Services further direction as to the responsibilities during any emergency situation. It is possible they may wish to take the lead or they may ask us to take the lead.

**14.1 EMERGENCY CONTACTS**

Fire: 911 or Bay City Fire Department @ 517-892-8601  
Police: 911 or Bay City Police Department @ 517-892-8571  
Ambulance: 911 or 517-894-3122  
Hospital: Bay Medical Center  
1900 Columbus Avenue  
Bay City, Michigan  
Telephone: 517-894-3000

Directions to the Hospital: Travel east out of the Site along Woodside Avenue to the Truman Parkway. Turn right (south) onto Truman Parkway. Travel along the parkway which changes to Trumbell Street. Proceed along Trumbell Street for three quarters of a mile. The Hospital is on the corner of Trumbell Street and Columbus Avenue. Figure D14.1 provides the emergency route from the Site.

**14.2 ADDITIONAL EMERGENCY NUMBERS**

National Response Center (NRC) .....800-424-8802  
Agency for Toxic Substances and Disease Registry .....404-488-4100(24 Hours)  
GM Emergency Response .....517-894-7288  
USEPA Emergency Response.....800-424-8802  
Project Manager (Ian Richardson) .....519-884-0510  
State of Michigan Emergency Response Commission .....517-373-8481  
CRA Services Manager of Safety and Health (Craig Gebhardt).....716-297-2160

**14.3      EMERGENCY EQUIPMENT AVAILABLE ON SITE**

***Communication Equipment***

Emergency Alarms/Horns

***Location***

CRZ

***Medical Equipment***

OSHA Approved First Aid Kit

Portable Emergency Eyewash

CRZ or Support Zone

Fire Fighting Equipment

One 20-Pound ABC Type Dry Chemical Fire Extinguishers

CRZ

**14.4      PROJECT PERSONNEL RESPONSIBILITIES  
DURING EMERGENCIES**

**HEALTH AND SAFETY OFFICER (HSO)**

As the administrator of the HASP, the HSO has primary responsibility for responding to and correcting emergency situations. The HSO will:

- i) take appropriate measures to protect personnel including: withdrawal from the EZ, total evacuation and securing of the Site or upgrading or downgrading the level of protective clothing and respiratory protection;
- ii) take appropriate measures to protect the public and the environment including isolating and securing the Site, preventing runoff to surface waters and ending or controlling the emergency to the extent possible;
- iii) ensure that appropriate Federal, State, and local agencies are informed, and emergency response plans are coordinated. In the event of fire or explosion, the local fire department should be summoned immediately. In the event of an air release of toxic materials, the local authorities should be informed in order to assess the need for evacuation. In the event of a spill, sanitary districts and drinking water systems may need to be alerted;
- iv) ensure that appropriate decontamination treatment or testing for exposed or injured personnel is obtained;
- v) determine the cause of the incident and make recommendations to prevent the recurrence; and
- vi) ensure that all required reports have been prepared.

#### **14.5      MEDICAL EMERGENCIES**

Any person who becomes ill or injured in the EZ must be decontaminated to the maximum extent possible. If the injury or illness is minor, full decontamination should be completed and first aid administered prior to transport. If the patient's condition is serious, at least partial decontamination should be completed as much as possible without causing further harm to the patient, and first aid should be administered while awaiting an ambulance or paramedics. All injuries and illnesses must immediately be reported to the HSO and Site Superintendent.

Any person transporting an injured/exposed person to a clinic or hospital for treatment should take with them directions to the hospital and a listing of the contaminants of concern to which they may have been exposed.

Any vehicle used to transport contaminated personnel will be cleaned or decontaminated as necessary.

#### **14.6      FIRE OR EXPLOSION**

In the event of a fire or explosion, the local fire department should be summoned immediately. Upon their arrival, the HSO or designated alternate will advise the fire commander of the location, nature, and identification of the hazardous materials on Site.

If it is safe to do so, Site personnel may:

- i) if hazardous, report to the Agency On-Scene Coordinator and/or Project Manager;
- ii) use fire fighting equipment available on Site; or
- iii) remove or isolate flammable or other hazardous materials which may contribute to the fire.

## **14.7      SPILLS OR CONTAINER LEAKS**

In the event of a spill or leak, Site personnel will:

- i)      report spills and releases to the Agency On-Scene Coordinator, Project Manager, the NRC, and State Emergency Response Commission (SERC);
- ii)     locate the source of the spillage and stop the flow if it can be done safely; and
- iii)    begin containment and recovery of the spilled materials.

## **15.0 RECORDKEEPING**

The HSO shall establish and maintain records of all necessary and prudent monitoring activities as described below:

- i) name and job classification of the employees involved on specific tasks;
- ii) records of qualitative fit testing and physical examination, results for Site personnel;
- iii) records of all OSHA training certification for Site personnel;
- iv) records of training acknowledgment forms; and
- v) emergency reports describing any incidents or accidents.

TABLE D2.1

**POTENTIAL CHEMICAL COMPOUNDS OF CONCERN  
GENERAL MOTORS POWERTRAIN GROUP  
BAY CITY PLANT  
BAY CITY, MICHIGAN**

<i>Substance</i>	<i>IDLH (ppm)</i>	<i>TLV* (ppm)</i>	<i>I.P. (eV)</i>	<i>Acute Effects</i>
<b><i>Volatile Organic Compounds</i></b>				
Acetone	2500	500	9.7	Irritation of eyes, nose, and throat. Headache, dizziness, and dermatitis. Inhalation, ingestion, and skin contact hazard.
Benzene	500	0.5 (Carc, S)	9.2	Irritation of eyes, skin, nose, and respiratory system. Headache, dizziness, giddiness, nausea, and dermatitis. Inhalation, ingestion, skin absorption, and skin contact hazard.
Chlorobenzene	1000	10	9.1	Irritation of eyes, skin, and nose. Drowsiness and in coordination. Inhalation, ingestion, and skin contact hazard.
Chloroethane	3800 (LEL)	100 (S)	11.0	In coordination and abdominal cramps. Inhalation, ingestion, skin absorption, and skin contact hazard.
Chloroform	500	10	11.4	Irritation of eyes and skin. Dizziness, mental dullness, nausea, confusion, headache, and fatigue. Inhalation, ingestion, skin absorption, and skin contact hazard.
1,1-Dichloroethane	3000	100	11.1	Skin irritation. Inhalation, ingestion, and skin contact hazard.
1,2-Dichloroethene	1000	200	9.6	Irritation to eyes and respiratory system. Inhalation, ingestion, and skin contact hazard.

TABLE D2.1

**POTENTIAL CHEMICAL COMPOUNDS OF CONCERN  
GENERAL MOTORS POWERTRAIN GROUP  
BAY CITY PLANT  
BAY CITY, MICHIGAN**

<i>Substance</i>	<i>IDLH (ppm)</i>	<i>TLV* (ppm)</i>	<i>I.P. (eV)</i>	<i>Acute Effects</i>
Ethylbenzene	800 (LEL)	100	8.8	Irritation to eyes, skin, and mucous membranes. Headache and dermatitis. Inhalation, ingestion, and skin contact hazard.
Methylene chloride	2300	25	11.3	Irritation to eyes and skin. Fatigue, weakness, light-headedness, numbness, and nausea. Inhalation, ingestion, skin absorption, and skin contact hazard.
4-Methyl-2-pentanone (synonym-Hexone)	500	50	9.3	Irritation to eyes, skin, and mucous membranes. Headache and dermatitis. Inhalation, ingestion, and skin contact hazard.
Toluene	500	50 (S)	8.8	Irritation to eyes and nose. Fatigue, weakness, confusion, euphoria, dizziness, headache, nervousness, and dermatitis. Inhalation, ingestion, skin absorption, and skin contact hazard.
1,1,1-Trichloroethane	700	350	11.0	Irritation to eyes and skin. Headache, weakness, exhaustion, and dermatitis. Inhalation, ingestion, and skin contact hazard.
Trichloroethene	1000	50	9.4	Irritation to eyes and skin. Headache, vertigo, fatigue, giddiness, tremor, nausea, vomiting, and dermatitis. Inhalation, ingestion, skin absorption, and skin contact hazard.

TABLE D2.1

**POTENTIAL CHEMICAL COMPOUNDS OF CONCERN  
GENERAL MOTORS POWERTRAIN GROUP  
BAY CITY PLANT  
BAY CITY, MICHIGAN**

<i>Substance</i>	<i>IDLH (ppm)</i>	<i>TLV* (ppm)</i>	<i>I.P. (eV)</i>	<i>Acute Effects</i>
Vinyl chloride	-	1 (Carc)	10.0	Weakness and abdominal pain. Contact with liquid may cause frostbite. Inhalation and skin contact hazard.
Xylene (o, m, p isomers)	900	100	8.5	Irritation to eyes, skin, nose, and throat. Dizziness, excitement, drowsiness, in coordination, nausea, vomiting, abdominal pain, and dermatitis. Inhalation, ingestion, skin absorption, and skin contact hazard.
<b><i>Semi-Volatile Organic Compounds</i></b>				
Benzo(b)fluoranthrene	80 mg/m <sup>3</sup>	0.2 mg/m <sup>3</sup> (Carc)	NA	NA
bis(2-Ethylhexyl)phthalate	NA	5 mg/m <sup>3</sup>	NA	NA
Fluoranthrene	80 mg/m <sup>3</sup>	0.2 mg/m <sup>3</sup>	NA	NA
Methylnaphthalene	NA	NA	NA	NA
Naphthalene	250	10	8.1	Irritation to eyes. Headache, confusion, excitement, malaise, nausea, vomiting, abdominal pain, and dermatitis. Inhalation, ingestion, skin absorption, and skin contact hazard.
Phenanthrene	80 mg/m <sup>3</sup>	0.2 mg/m <sup>3</sup>	NA	NA

TABLE D2.1

**POTENTIAL CHEMICAL COMPOUNDS OF CONCERN  
GENERAL MOTORS POWERTRAIN GROUP  
BAY CITY PLANT  
BAY CITY, MICHIGAN**

<i>Substance</i>	<i>IDLH (ppm)</i>	<i>TLV* (ppm)</i>	<i>I.P. (eV)</i>	<i>Acute Effects</i>
Pyrene	80 mg/m <sup>3</sup>	0.2 mg/m <sup>3</sup>	NA	NA
<b><i>Polychlorinated Biphenyls</i></b>				
Aroclor 1248	5 mg/m <sup>3</sup>	0.5 mg/m <sup>3</sup> (S)	NA	Eye irritation. Chloracne. Inhalation, ingestion, skin absorption, and skin contact hazard.
Aroclor 1254	5 mg/m <sup>3</sup>	0.5 mg/m <sup>3</sup> (S)	NA	Eye irritation. Chloracne. Inhalation, ingestion, skin absorption, and skin contact hazard.
<b><i>Metals</i></b>				
Aluminum	NA	10 mg/m <sup>3</sup>	NA	Irritation to eyes, skin, and respiratory system. Inhalation and skin contact hazard.
Antimony	50 mg/m <sup>3</sup>	0.5 mg/m <sup>3</sup>	NA	Irritation to eyes, skin, nose, throat, and mouth. Cough, dizziness, headache, nausea, vomiting, diarrhea, stomach cramps. Inhalation, ingestion, and skin contact
Arsenic	5 mg/m <sup>3</sup>	0.01 mg/m <sup>3</sup> (Carc)	NA	Irritation of respiratory system. Dermatitis. Inhalation, ingestion, skin absorption, and skin contact hazard.
Barium	50 mg/m <sup>3</sup>	0.5 mg/m <sup>3</sup>	NA	Irritation to eyes, skin, and upper respiratory system. Inhalation, ingestion, and skin contact hazard.

TABLE D2.1

**POTENTIAL CHEMICAL COMPOUNDS OF CONCERN  
GENERAL MOTORS POWERTRAIN GROUP  
BAY CITY PLANT  
BAY CITY, MICHIGAN**

<b>Substance</b>	<b>IDLH (ppm)</b>	<b>TLV* (ppm)</b>	<b>I.P. (eV)</b>	<b>Acute Effects</b>
Beryllium	4 mg/m <sup>3</sup>	0.002 mg/m <sup>3</sup> (Carc)	NA	Irritation to eyes. Weakness, chest pains, and cough. Inhalation and skin contact hazard.
Cadmium	9 mg/m <sup>3</sup>	0.002 mg/m <sup>3</sup> (Carc)	NA	Cough, tightness in chest, headache, chills, muscle aches, nausea, vomiting, and diarrhea. Inhalation and ingestion hazard.
Chromium	250 mg/m <sup>3</sup>	0.5 mg/m <sup>3</sup>	NA	Irritation to eyes, skin, and lungs. Inhalation, ingestion, and skin contact hazard.
Cobalt	20 mg/m <sup>3</sup>	0.02 mg/m <sup>3</sup>	NA	Cough, wheezing, and dermatitis. Inhalation, ingestion, and skin contact hazard.
Copper	100 mg/m <sup>3</sup>	1 mg/m <sup>3</sup>	NA	Irritation to eyes, nose, and pharynx. Metallic taste and dermatitis. Inhalation, ingestion, and skin contact
Cyanides	25 mg/m <sup>3</sup>	5 mg/m <sup>3</sup>	NA	Irritation to eyes and skin. Headache, confusion, nausea, and vomiting. Inhalation, ingestion, skin absorption, and skin contact hazard.
Iron	2500 mg/m <sup>3</sup>	5 mg/m <sup>3</sup>	NA	Inhalation hazard.
Lead	100 mg/m <sup>3</sup>	0.05 mg/m <sup>3</sup>	NA	Irritation to eyes. Weakness, exhaustion, and abdominal pain. Inhalation, ingestion, and skin contact hazard.

TABLE D2.1

**POTENTIAL CHEMICAL COMPOUNDS OF CONCERN  
GENERAL MOTORS POWERTRAIN GROUP  
BAY CITY PLANT  
BAY CITY, MICHIGAN**

<b>Substance</b>	<b>IDLH (ppm)</b>	<b>TLV* (ppm)</b>	<b>I.P. (eV)</b>	<b>Acute Effects</b>
Manganese	500 mg/m <sup>3</sup>	0.2 mg/m <sup>3</sup>	NA	Dry throat, cough, chest tightness, vomiting, malaise, and fatigue. Inhalation and ingestion hazard.
Mercury	10 mg/m <sup>3</sup>	0.025 mg/m <sup>3</sup>	NA	Irritation to eyes and skin. Coughing, chest pain, headache, fatigue, and weakness. Inhalation, ingestion, skin absorption, and skin contact hazard.
Nickel	10 mg/m <sup>3</sup>	1 mg/m <sup>3</sup>	NA	hazard.
Vanadium	35 mg/m <sup>3</sup>	0.05 mg/m <sup>3</sup>	NA	Irritation to eyes, skin, and throat. Metallic taste in mouth. Inhalation, ingestion, and skin contact hazard.
Zinc	500 mg/m <sup>3</sup>	10 mg/m <sup>3</sup>	NA	Chills, muscle ache, nausea, fever, dry throat, cough, weakness, exhaustion, vomiting, fatigue, tight chest, and metallic taste in mouth. Inhalation hazard.

## Notes:

(Carc) The chemical substance is classified by ACGIH as a confined or suspected human carcinogen.

\* The TLV is determined by the lowest documented level between OSHA and ACGIH.

(S) There is potential significant contribution to the overall exposure by direct skin contact with vapors and/or liquid.

(LEL) The IDLH is designated since 10 percent of the LEL will be reached at that substance concentration.

**TABLE D6.1**

**SPECIFIC PERSONAL PROTECTION LEVELS  
POTENTIAL CHEMICAL COMPOUNDS OF CONCERN  
GENERAL MOTORS POWERTRAIN GROUP  
BAY CITY PLANT**

<b>Work Tasks</b>	<b>Maximum Protection Level <sup>(1)</sup></b>	<b>Alternate Protection Level <sup>(2)</sup></b>
Mobilization and Demobilization of Labor, Materials, and Equipment to and From the Site	Modified D	D
Surveying Activities	Modified D	D
Machine Storage Area:		
• Groundwater monitoring	Modified D	Modified D
• Multi-layer cap and groundwater extraction system maintenance	Modified D	D
Lagoon Area:		
• Groundwater monitoring	Modified D	Modified D
• Groundwater extraction system maintenance	Level C	Modified D
Outer Perimeter Banks:		
• Groundwater monitoring	Modified D	Modified D
• Multi-layer cap maintenance	Modified D	Level D
• Sheet pile wall maintenance	Modified D	Level D
Inlet Slip:		
• Soil erosion protection measures maintenance	Modified D	Level D
Support Facilities Area:		
• Water level measurements	Modified D	Modified D
Undeveloped Area		
• Groundwater monitoring	Modified D	Modified D
Decontamination activities	Level C	Modified D

Notes:

Specific requirements for protection levels are detailed in Section 6.1.

- (1) Level C: To be worn when the criterion for using air-purifying respirators (APRs) are met and a lesser level of skin protection is needed.  
Modified D: To be worn when dermal protection is required, however, no respiratory hazards are present. It provides minimal protection against chemical hazards.
- (2) Alternate protection levels will be used if monitoring indicates that conditions are appropriate or the HSO and Site Superintendent agree that there is a reduced potential of exposure.

**TABLE D7.1**

**ANTICIPATED HAZARDS/RISKS AND APPROPRIATE PRECAUTIONS  
POTENTIAL CHEMICAL COMPOUNDS OF CONCERN  
GENERAL MOTORS POWERTRAIN GROUP  
BAY CITY PLANT**

<i>Activity</i>	<i>Anticipated Hazards/Risks</i>	<i>Appropriate Precautions</i>
1. Mobilization and Demobilization Activities	<ul style="list-style-type: none"> <li>• slip/trip/fall hazards</li> <li>• potential back injuries from lifting heavy objects</li> <li>• potential heat or cold stress</li> <li>• severe weather</li> <li>• electrical hazards from power sources</li> <li>• moving or backing vehicles</li> <li>• cuts to hands from working with sharp objects or fencing material</li> <li>• potential drowning from working in and/or on the River</li> </ul>	<ul style="list-style-type: none"> <li>• Modified D or Level D personal protection</li> <li>• practice safe lifting techniques</li> <li>• participate in on-Site training programs</li> <li>• practice good personal hygiene principles</li> <li>• use a spotter around moving or backing equipment</li> <li>• work activities will be reduced or suspended during severe weather conditions</li> <li>• ground fault circuit interrupters (GFCIs) should be used to reduce the hazard of electrical shock. Do not stand in water when handling equipment. Electrical equipment will be approved.</li> <li>• keep first aid supplies readily available</li> <li>• wear leather gloves when working with sharp objects</li> <li>• wear personal floatation devices when working in or on the River</li> </ul>
2. Machine Storage Area: - Groundwater monitoring - Multi-layer cap and groundwater extraction system maintenance	<ul style="list-style-type: none"> <li>• slip/trip/fall hazards</li> <li>• potential back injuries from lifting heavy objects</li> <li>• potential heat or cold stress</li> <li>• severe weather</li> <li>• electrical hazards from power sources</li> <li>• moving or backing vehicles and equipment</li> <li>• personnel injuries from sharp objects, falling debris, or pinch points</li> <li>• direct contact with potentially contaminated soils and groundwater</li> <li>• hazards presented by the use of heavy equipment</li> <li>• overhead and underground hazards (i.e., electrical lines, gas, or water lines)</li> <li>• potential burns from hot equipment</li> <li>• hazards presented by the use of specialized equipment (e.g., decontamination equipment)</li> </ul>	<ul style="list-style-type: none"> <li>• Level C and Modified D based on real-time air monitoring or established protection levels (see Table 6.1)</li> <li>• practice safe lifting techniques</li> <li>• participate in all on-Site training programs</li> <li>• be trained with all appropriate equipment SOPs</li> <li>• wear leather gloves when working with sharp objects</li> <li>• practice good personal hygiene principles</li> <li>• take proper precautions in unsafe areas</li> <li>• use the "Buddy System"</li> <li>• perform an underground utilities location</li> <li>• only essential personnel allowed in work areas</li> <li>• if performing confined space entry work, make sure perr system is in place and workers have participated in a training program</li> <li>• use a spotter around moving or backing equipment</li> <li>• identify all high temperature objects or equipment</li> </ul>
Lagoon Area: - Groundwater monitoring - Groundwater extraction system maintenance		

**TABLE D7.1**

**ANTICIPATED HAZARDS/RISKS AND APPROPRIATE PRECAUTIONS  
POTENTIAL CHEMICAL COMPOUNDS OF CONCERN  
GENERAL MOTORS POWERTRAIN GROUP  
BAY CITY PLANT**

<i><b>Activity</b></i>	<i><b>Anticipated Hazards/Risks</b></i>	<i><b>Appropriate Precautions</b></i>
<p>Outer Perimeter Banks:</p> <ul style="list-style-type: none"> <li>- Groundwater monitoring</li> <li>- Multi-layer cap maintenance</li> <li>- Sheet pile wall maintenance</li> </ul>	<ul style="list-style-type: none"> <li>• hazards presented by entry into a confined space (i.e., oxygen deficient, working in small tight areas, and falling overhead objects)</li> <li>• reduced field of vision from wearing full-face respirators</li> <li>• potential drowning from working in and/or on the River</li> </ul>	<ul style="list-style-type: none"> <li>• work activities will be reduced or suspended during severe weather conditions</li> <li>• GFCIs should be used to reduce the hazard of electrical shock. Do not stand in water when handling equipment. Electrical equipment will be approved.</li> <li>• keep first aid supplies readily available</li> <li>• wear personal floatation devices when working in or on</li> </ul>
<p>Inlet Slip:</p> <ul style="list-style-type: none"> <li>- Soil erosion protection maintenance</li> </ul>		
<p>Support Facilities Area:</p> <ul style="list-style-type: none"> <li>- Water level measurements</li> </ul>		
<p>Undeveloped Area:</p> <ul style="list-style-type: none"> <li>- Groundwater monitoring</li> </ul>		
<p>Decontamination activities</p>		

APPENDIX E

HISTORICAL GROUNDWATER DATA


APPENDIX F

AS-RECORDED DRAWINGS

# REMEDIAL ACTION PLAN

## AS RECORDED DRAWINGS - SEPTEMBER 2000

### GM POWERTRAIN DIVISION AND CROTTY STREET CHANNEL SITE BAY CITY, MICHIGAN



KEY PLAN

DWG.No.	DRAWING TITLE	
<b>GENERAL</b>		
GN-WA001	G-01AR	SH01 COVER SHEET/DRAWING INDEX
GN-WA005	G-02AR	SH02 ABBREVIATIONS AND DETAIL DESIGNATIONS
GN-WA004	G-03AR	SH03 CIVIL, STRUCTURAL, AND ARCHITECTURAL LEGEND
GN-WA007	G-04AR	SH04 MECHANICAL LEGEND
GN-WA009	G-05AR	SH05 INSTRUMENTATION AND CONTROL LEGEND
GN-WA006	G-06AR	SH06 ELECTRICAL LEGEND
GN-WA010	G-07AR	SH07 CIVIL STANDARD DETAILS
GN-WA002	G-08AR	SH08 FENCING
GN-WA008	G-09AR	SH09 DISTRIBUTION PIPING
GN-WA011	G-10AR	SH10 GENERAL SITE PRE-CONSTRUCTION PLAN
GN-WA012	G-11AR	SH11 WEST SIDE PRE-CONSTRUCTION PLAN
GN-WA013	G-12AR	SH12 EAST SIDE PRE-CONSTRUCTION PLAN
<b>CIVIL</b>		
CI-WA017	C-01AR	SH13 MONITORING WELLS ABANDONED
CI-WA013	C-02AR	SH14 EXISTING MONITORING WELLS
CI-WA004	C-03AR	SH15 WELL EXTENSION DETAILS
CI-WA001	C-04AR	SH16 SOIL EXCAVATION LOCATIONS AND RESULTS
CI-WA012	C-05AR	SH17 GROUNDWATER EXTRACTION SYSTEM
CI-WA005	C-06AR	SH18 GROUNDWATER EXTRACTION SYSTEM DETAILS
CI-WA006	C-07AR	SH19 GROUNDWATER EXTRACTION WELL 13, 14, AND 15 DETAILS
CI-WA003	C-08AR	SH20 SITE CAPPING
CI-WA007	C-09AR	SH21 CAP DETAILS
CI-WA008	C-10AR	SH22 EAST LAGOON LINER PLAN
CI-WA009	C-11AR	SH23 EAST LAGOON LINER DETAILS - 1 OF 2
CI-WA010	C-12AR	SH24 EAST LAGOON LINER DETAILS - 2 OF 2
CI-WA021	C-13AR	SH25 INLET SLIP LINER PLAN AND DETAILS
CI-WA019	C-14AR	SH26 WEST SUPPORT FACILITIES AREA PAVEMENT PLAN
CI-WA018	C-15AR	SH27 EAST SUPPORT FACILITIES AREA PAVEMENT PLAN
CI-WA011	C-16AR	SH28 SUPPORT FACILITIES AREA DETAILS
CI-WA020	C-17AR	SH29 EAST AREA PLAN DRAINAGE
CI-WA022	C-18AR	SH30 MANHOLE AND CATCHBASIN DETAILS

DWG.No.	DRAWING TITLE	
<b>STRUCTURAL</b>		
ST-WA002	S-01AR	SH31 SHEET PILING 1+0 TO 12+78.87
ST-WA003	S-02AR	SH32 SHEET PILING 10+50 TO 25+46
ST-WA001	S-03AR	SH33 SHEET PILING DETAILS SHEET 1 OF 2
ST-WA004	S-04AR	SH34 SHEET PILING DETAILS SHEET 2 OF 2
<b>ELECTRICAL</b> (BY MURDOCK ENGINEERING)		
EL-ME001	E-01AR	SH35 ELECTRICAL SITE PLAN
EL-ME002	E-02AR	SH36 EQUIPMENT STORAGE AREA POWER DISTRIBUTION 1 OF 3
EL-ME003	E-03AR	SH37 EQUIPMENT STORAGE AREA POWER DISTRIBUTION 2 OF 3
EL-ME004	E-04AR	SH38 EQUIPMENT STORAGE AREA POWER DISTRIBUTION 3 OF 3
EL-ME005	E-05AR	SH39 CONTROL SCHEMATIC CP1
EL-ME006	E-06AR	SH40 EQUIPMENT STORAGE AREA CONTROL PANEL LAYOUT (CP1)
EL-ME007	E-07AR	SH41 LAGOON AREA POWER DISTRIBUTION 1 OF 2
EL-ME008	E-08AR	SH42 LAGOON AREA POWER DISTRIBUTION 2 OF 2
EL-ME009	E-09AR	SH43 CONTROL SCHEMATIC CP2
EL-ME010	E-10AR	SH44 EQUIPMENT STORAGE AREA CONTROL PANEL LAYOUT (CP2)
EL-ME011	E-11AR	SH45 POWER DISTRIBUTION SINGLE LINE
EL-ME012	E-12AR	SH46 BUILDING ELECTRICAL LAYOUT AND DETAILS

DRAWING INDEX

<b>GM POWERTRAIN</b>	
GENERAL MOTORS POWERTRAIN DIVISION BAY CITY OPERATION BAY CITY, MICHIGAN 48708-5460	
PLANT ENGINEERING BUILDING No.	SHEET No.
PE-H-96	SH01
AS RECORDED SEPTEMBER 2000	

REF. PE-E-81



**Remediation and Liability  
Management Company, Inc.**



**CONESTOGA-ROVERS & ASSOCIATES**

## ABBREVIATIONS

<p>3/C CONDUCTORS, NUMBER OF (3)</p> <p>AAP ALARM ANNUNCIATOR PANEL AAV AUTOMATIC AIR VENT AB ANCHOR BOLT ABAN ABSORBED ABS ABSOLUTE ABV ABOVE AC ALTERNATING CURRENT ACCU ACCUMULATOR ACNV AUTOMATIC CONTROL VALVE ACOUS ACOUSTICAL ACP ASPHALTIC CONCRETE PAVING ACTR ACTUATOR ADDL ADDITIONAL ADDM ADDENDUM ADH ADHESIVE ADJ ADJUSTABLE ADJC ADJACENT ADPTR ADAPTER AF AFTER FILTER AGGR AGGREGATE AHR ANCHOR AHJ AIR HANDLING UNIT AL ALUMINUM ALM ALARM ALT ALTERNATE AMB AMBIENT AMSL ABOVE MEAN SEA LEVEL ANLG ANALOG AP ACID PROOF APPROX. APPROXIMATELY APPX APPENDIX APT APARTMENT ARCH ARCHITECTURAL ASL ABOVE SEA LEVEL ASPH ASPHALTIC ASTM AMERICAN SOCIETY FOR TESTING AND AND MATERIALS ASU AIR SUPPLY UNIT ASW AUXILIARY SWITCH ASYM ASYMMETRICAL AT AIR TIGHT ATS AUTOMATIC TRANSFER SWITCH AVE AVENUE AWG AMERICAN WIRE GAGE AZ AZIMUTH</p>	<p>ONTRFLG CENTRIFUGAL CO CLEANOUT COAX COAXIAL CABLE COL COLUMN COMM COMMUNICATION CONC CONCRETE CONN CONNECTION CONSTR CONSTRUCTION CONT CONTINUOUS (CONTINUATION) COORD COORDINATE COVER COVER CP CANDLE POWER CP CONCRETE PIPE CP CONTROL PANEL CPLG COUPLING CR CENTRIFUGAL REDUCER CRCMF CIRCUMFERENCE CRN CROWN CRS COLD ROLLED STEEL CSP CONCRETE SEWER PIPE CT COOLING TOWER CTV CABLE TELEVISION CU COPPER CV CONTROL VALVE CWF COMPLETE WITH CW COLD WATER CWP CIRCULATING WATER PIPE CYL CYLINDER</p>	<p>FXTX FIXTURE</p> <p>G GAS GA GAGE GAL GALLON GALV GALVANIZED GEN GENERATOR GFCI GROUND FAULT CIRCUIT INTERRUPTOR GLV GLOBE VALVE GLZ GLAZING GND GROUND GOVT GOVERNMENT GPD GALLONS PER DAY GPH GALLONS PER HOUR GPM GALLONS PER MINUTE GPS GALLONS PER SECOND GR GRADE GR LN GRADE LINE GRL GRILLE GRTG GRATING GSKT GASKET GSZK GOOSENECK GT GREASE TRAP GT GROUT GTV GATE VALVE GUT GUTTER GWL GRAVEL GWH GAS WATER HEATER</p>	<p>LT LIGHT LTG LIGHTING LTG PNL LIGHTING PANEL LV LOW VOLTAGE LVL LEVEL(ER) LOUVER LOUVER LWC LIGHTWEIGHT CONCRETE</p> <p>M METER MA MILLIAMPERE MACH MACHINE MAINT MAINTENANCE MAN MANUAL MAS MASONRY MAU MAKE-UP AIR UNIT MAX MAXIMUM MBTU THOUSAND BRITISH THERMAL UNITS MC MOMENTARY CONTACT MCC MOTOR CONTROL CENTER MD MANUAL DAMPER MECH MECHANICAL MET METAL MEZZ MEZZANINE MFG MANUFACTURING MGD MILLION GALLONS PER DAY MH MANHOLE MHT MEAN HIGH TIDE MIL MALLEABLE IRON MI MILE MID MIDDLE MIN MINIMUM MINUTE MINUTE MISC MISCELLANEOUS MJ MECHANICAL JOINT MK MARK MKR MARKER MLT MEAN LOW TIDE MLWK MILLWORK MDDO MODIFIED MAXIMUM DRY DENSITY MOBIL MOBILIZATION MOD MOTOR OPERATED DAMPER MONITOR MONITOR MON MONUMENT MOT MOTOR OPERATED VALVE MOV MILES PER HOUR MPT MALE PIPE THREAD MS MOTOR STARTER MTD MOUNTED MV MEGAVOLT MW MEGAWATT</p> <p>N NORTH NA NOT APPLICABLE NATURAL NATURAL NC NATIONAL COARSE THREAD NC NORMALLY CLOSED NEG NEGATIVE NHD HOT WATER NEUT NEUTRAL NF NATIONAL FINE THREAD NIC NOT IN CONTRACT NIP NIPPLE NKCL NICKEL NO NORMALLY OPEN NO NUMBER NOM NOMINAL NOZ NOZZLE NPF NATIONAL PIPE THREAD NPL NAMEPLATE NPT NATIONAL TAPER PIPE THREAD NRCP NON-REINFORCED CONCRETE PIPE NRS NON-RISING STEM NTS NOT TO SCALE</p> <p>O/O OUT TO OUT OVERALL OVERALL OC ON CENTER OD OUTSIDE DIAMETER OHGW OVERHEAD GUY WIRE OIL OVER LOAD OPENING OPENING OPP OPPOSITE ORD OVERFLOW ROOF DRAIN ORF ORIFICE ORIG ORIGINAL OVLV OVERFLOW OXY OXYGEN OZ OUNCE</p> <p>P PUMP PA PIPE ANCHOR PAR PARALLEL PARG PARGING PAT PATTERN PB PULL BOX PB PUSH BUTTON PC PIECE PC POINT OF CURVE PC PORTLAND CEMENT PCC POINT OF COMPOUND CURVE PCF POUNDS PER CUBIC FOOT PEDESTAL PEDESTAL PERF PERFORATED PERIM PERIMETER PERM PERMANENT PERP PERPENDICULAR PFA POWER FACTOR PH PHASE PHOTO PHOTOGRAPH PI POINT OF INTERSECTION PIV POST INDICATOR VALVE PIVC POINT OF INTERSECTION FOR VERTICAL CURVE PKG PACKAGE PKWY PARKWAY PL LUMBER PL PROPERTY LINE PLAT PLATFORM PLBG PLUMBING PLYWD PLYWOOD PNEU PNEUMATIC PNL PANEL PNT PAINT POLY POLYETHYLENE PORT PORTABLE POS POSITIVE PPM PARTS PER MILLION PR PAIR PRC POINT OF REVERSE CURVE PRECAST PRECAST PRVC POINT OF REVERSE CURVE VERTICAL CURVE</p>	<p>PREFAB PREFABRICATED PRELIM PRELIMINARY PRI PRIMARY PRKG PARKING PROJ PROJECT PROP PROPERTY PRV PRESSURE REDUCING VALVE PRV PRESSURE RELIEF VALVE PS CONC PRESTRESSED CONCRETE PSF POUNDS PER SQUARE FOOT PSI POUNDS PER SQUARE INCH PSIA POUNDS PER SQUARE INCH ABSOLUTE PSIG POUNDS PER SQUARE INCH GAGE PST POINT OF SPIRAL TANGENT PT PIPE TANGENT PT POINT OF TANGENCY PTD PAINTED PV PAVED PVC POINT OF VERTICAL CURVE PVC POLYVINYL CHLORIDE PVG PAVING PVI POINT OF VERTICAL INTERSECTION PVMT PAVEMENT PVT POINT OF VERTICAL TANGENCY PWR POWER</p> <p>QCV QUICK COUPLER VALVE QTR QUARTER QTY QUANTITY</p> <p>R RISER RAD RADIUS RBR RUBBER RC REINFORCED CONCRETE RD ROAD RD ROOF DRAIN RDC REDUCER REC RECESS RECIRC RECIRCULATE RECT RECTANGULAR REF REFERENCE REFC REINFORCED(ING)(MENT) REM REMOVABLE REQD REQUIRED RESIL RESILIENT RETURN RETURN RF RAISED FACE RFG ROOFING RGLTR REGULATOR RH RELATIVE HUMIDITY RH RIGHT HAND RLF RELIEF RLM RAILING RM ROOM RND ROUND ROU ROUGH OPENING ROW RIGHT-OF-WAY RPM REVOLUTIONS PER MINUTE RPS REVOLUTIONS PER SECOND RR RAILROAD RV RELIEF VALVE RV ROOF VENT</p> <p>S SOUTH SA SUPPLY AIR SALV SALVAGE SAN SANITARY SAT SATURATION SCHED SCHEDULE SCRN SCREEN SD STORM DRAIN SDL SADDLE SDMH STORM DRAIN MANHOLE SEC SECOND SECT SECTION SEG SEGMENT SF SAFETY FACTOR SFL SUPPLY FAN SGL SINGLE SHLDR SHOULDER SHR SHOWER SHT SHEET(ING) SHTG SHEATHING SIG SIGNAL SIM SIMILAR SK SINK SLP SLOPE SLV SLEEVE SM SHEET METAL SM SMOOTH SMDD STANDARD MAXIMUM DRY DENSITY SMLS SEAMLESS SOLV SOLENOID VALVE SP SINGLE POLE SP SOIL PIPE SP SPACE(ING) SP GR SPECIFIC GRAVITY SP VOL SPECIFIC VOLUME SPT SINGLE POLE DOUBLE THROW SPEC SPECIFICATION SPKLR SPRINKLER SPKR SPEAKER SPLY SUPPLY SPT SUPPORT SPST SINGLE POLE SINGLE THROW SQUARE SQ FT SQUARE FEET SQ IN SQUARE INCH SQ KM SQUARE KILOMETER SQ M SQUARE METER SQ MM SQUARE MILLIMETER SQ YD SQUARE YARD SS SANITARY SEWER SS SERVICE SINK SST STAINLESS STEEL ST STREET STA STATION STAG STAGGERED STD STANDARD STIF STIFFENER STIR STIRRUP STK STAKE STL STEEL STOR STORAGE STR STRAIGHT STRUCT STRUCTURAL SUUCT SUCT SURF SURFACE</p> <p>UTIL UTILITY UV ULTRAVIOLET</p> <p>T TEE T THERMOSTAT T TREAD TAB TOP AND BOTTOM T&amp;G TONGUE AND GROOVE TAN TANGENT TB TOP OF BEAM TBM TEMPORARY BENCH MARK TC TOP OF CONCRETE TC TOP OF CURB TDH TOTAL DYNAMIC HEAD TE TOP ELEVATION TE TOTALLY ENCLOSED TECH TECHNICAL TEL TELEPHONE TEMP TEMPERATURE TEMP TEMPORARY TERM TERMINAL TF TOP OF FOOTING TFF TOP OF FINISHED FLOOR THD THREADED THERM THERMAL THK THICKNESS THRU THROUGH TNL TUNNEL TOT TOTAL TP TOP OF PAVEMENT TP TOTAL PRESSURE TRANS TRANSPARENT TSF TONS PER SQUARE FOOT TSB TOP OF SLAB TST TOP OF STEEL TTB TELEPHONE TERMINAL BOARD TV WEIGHT TW TOP OF WALL TYP TYPICAL</p> <p>U UNDERGROUND UH UNIT HEATER ULT ULTIMATE UN UNION UNEX UNEXCAVATED UNFIN UNFINISHED UNIF UNIFORM UNIV UNIVERSAL UON UNLESS OTHERWISE NOTED UPS UNINTERRUPTIBLE POWER SUPPLY</p> <p>V WASTE W WATT W WEST W/O WITHOUT WW WALL TO WALL WB WET BULB WC WATER CLOSET WD WIDTH WD WOOD WDO WINDOW WF WIDE FLANGE WG WATER GAGE WHA WATER HAMMER ARRESTOR WHR WATER HEATER WI WROUGHT IRON WL WATER LINE WL WATER LEVEL WLD WELDED WP WORKING POINT WPR WORKING PRESSURE WR WATER RESISTANT WT WEIGHT WTR WATER WTRPRF WATERPROOF(ING) WW WASTE WATER WWF WELDED WIRE FABRIC</p>
---	---	--	--	---

№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	MRT

NOTES:

- THIS IS A STANDARD LEGEND LIST, THEREFORE SOME SYMBOLS OR ABBREVIATIONS MAY APPEAR ON THIS LIST AND NOT ON THE DRAWINGS.
- CONTACT ENGINEER FOR ABBREVIATIONS NOT LISTED.

**Remediation and Liability Management Company, Inc.**

GENERAL MOTORS POWERTRAIN DIVISION  
BAY CITY OPERATION  
BAY CITY, MICHIGAN 48708-5460

PLANT ENGINEERING BUILDING No.	SHEET No.
<b>PE-H-96</b>	<b>SH02</b>
AS RECORDED MAY 2000	

SCALE VERIFICATION

THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved			
Status	Date	Initial	Initial

**DRAWING STATUS**


**GM POWERTRAIN DIVISION**  
BAY CITY, MICHIGAN

AS RECORDED

**ABBREVIATIONS AND**  
**DETAIL DESIGNATIONS**

ORA CONESTOGA-ROVERS & ASSOCIATES

Source Reference:

Project Manager: MRT	Reviewed By: RLA	Date: MAY 2000	
Scale: NO SCALE	Project N. #: 12610-10	Report N. #: 016	Drawing N. #: G-02AR

### STANDARD DETAIL DESIGNATION

SECTION DESIGNATION (LETTER)

STANDARD DETAIL DESIGNATION (ALPHANUMERIC)

C - CIVIL STANDARD DETAIL DRAWINGS  
L - LANDSCAPING STANDARD DETAIL DRAWINGS  
S - STRUCTURAL STANDARD DETAIL DRAWINGS  
A - ARCHITECTURAL STANDARD DETAIL DRAWINGS  
M - MECHANICAL STANDARD DETAIL DRAWINGS  
E - ELECTRICAL STANDARD DETAIL DRAWINGS  
IC - INSTRUMENTATION AND CONTROL STANDARD DETAIL DRAWINGS

SHOWN ON STANDARD DETAIL DRAWINGS

### SECTION DESIGNATION

SECTION DESIGNATION (LETTER)

ON DRAWING WHERE SECTION IS TAKEN:

DRAWING NUMBER WHERE SHOWN

ON DRAWING WHERE SECTION IS SHOWN:

DRAWING NUMBER(S) WHERE TAKEN

### DETAIL DESIGNATION

DETAIL DESIGNATION (NUMBER)

ON DRAWING WHERE DETAIL IS TAKEN:

DRAWING NUMBER WHERE SHOWN

ON DRAWING WHERE DETAIL IS SHOWN:

DRAWING NUMBER(S) WHERE TAKEN

**TOPOGRAPHICAL**

**MUNICIPAL SYMBOLS**

	PROPERTY BOUNDARY		STANDARD IRON BAR		ROAD SIGN
	SITE BOUNDARY		IRON BAR		UTILITY POLE
	FENCE		ROUND IRON BAR		GUY ANCHOR
	DITCH, SWALE		MONUMENT/BENCHMARK		GAS VALVE
	GROUND CONTOUR		CUT CROSS		TELEPHONE PEDESTAL
	GROUNDWATER ELEVATION CONTOUR (PIEZOMETRIC OR POTENTIOMETRIC SURFACE)		TELEPHONE CHAMBER		IRON PIPE
	SOIL EXCAVATION CONTOUR		NAIL/CONTROL		HAND HOLE
	FINAL CONTOUR		SANITARY MANHOLE		ELECTRICAL MANHOLE
	LIMIT OF REFUSE DISPOSAL		STORM MANHOLE		LIGHT STANDARD
	SLOPED SURFACE (TOP OF BANK)		PROCESS MANHOLE		DECIDUOUS TREE AND DIAMETER
	BUILDING		CATCHBASIN		CONIFEROUS TREE AND DIAMETER
	RAILWAY		DOUBLE CATCHBASIN		SHRUB AND DIAMETER
	SHORELINE		WATER VALVE		TREE STUMP AND DIAMETER
	ACCESS ROAD		VALVE CHAMBER		DECIDUOUS CLUMP TREES AND DIAMETER
	WATERMAIN		CURB STOP		CONIFEROUS CLUMP TREES NUMBER AND DIAMETER
	SANITARY SEWER		HYDRANT		
	STORM SEWER		DITCH INLET CATCHBASIN		
	PROCESS SEWER				
	AIR, HIGH PRESSURE				
	GAS MAIN				
	TELEPHONE LINE				
	ELECTRIC CABLE				
	UNDERGROUND CONDUIT				
	OVERHEAD CABLE, WIRE				
	GUARDRAIL				
	SHALLOW GROUNDWATER EXTRACTION SYSTEM				
	DEEP GROUNDWATER EXTRACTION SYSTEM				
	DEEP SOIL MIXING WALL				
	EXCAVATE AND DISPOSE IN MSA				
	SPOT ELEVATION				

**PROPOSED MUNICIPAL SYMBOLS**

	PROPOSED SANITARY MANHOLE		PROPOSED VALVE CHAMBER
	PROPOSED STORM MANHOLE		PROPOSED HYDRANT
	PROPOSED CATCHBASIN		PROPOSED DOUBLE CATCHBASIN
	PROPOSED WATER VALVE		PROPOSED UTILITY POLE

**MONITORING**

	BOREHOLE		TEST PIT
	SURFACE SOIL SAMPLE		INJECTION WELL
	STANDPIPE		GAS PROBE
	OBSERVATION/MONITORING WELL		GAS VENT
	SURFACE WATER MONITORING LOCATION		HAND AUGER BORING LOCATION
	WATER SUPPLY WELL		MULTI-PHASE EXTRACTION WELL
	PIEZOMETER		VAPOR EXTRACTION WELL
	BUNDLE PIEZOMETER		AIR SPARGING WELL
	EXTRACTION WELL		OUTFALL LOCATION
	WELL POINT		

**PROPOSED MONITORING**

	PROPOSED BOREHOLE		PROPOSED TEST PIT
	PROPOSED SURFACE SOIL SAMPLE		PROPOSED INJECTION WELL
	PROPOSED STANDPIPE		PROPOSED GAS PROBE
	PROPOSED OBSERVATION/MONITORING WELL		PROPOSED GAS VENT
	PROPOSED SURFACE WATER MONITORING LOCATION		PROPOSED HAND AUGER BORING LOCATION
	PROPOSED WATER SUPPLY WELL		PROPOSED MULTI-PHASE EXTRACTION WELL
	PROPOSED PIEZOMETER		PROPOSED VAPOR EXTRACTION WELL
	PROPOSED BUNDLE PIEZOMETER		PROPOSED AIR SPARGING WELL
	PROPOSED EXTRACTION WELL		PROPOSED OUTFALL LOCATION


**PROPOSED MONITORING**

	PROPOSED STORM SEWER
	PROPOSED GROUNDWATER EXTRACTION SYSTEM


**PROPOSED RELIEF DRAIN**

	PROPOSED RELIEF DRAIN
--	-----------------------

**GEOLOGIC & HYDROGEOLOGIC SECTIONS**




**TYPICAL WELL INSTALLATION**




**MEASURED WATER LEVEL**



**MONITORING OR SAMPLING LOCATION**



**MEASURED CHEMICAL CONCENTRATION**




**SOIL CLASSIFICATIONS**


**MATERIAL**

	CAP
	CONTAINMENT CAP
	SAND
	SEDIMENT
	SAND AND GRAVEL
	RUBBLE AND DEBRIS
	FILL
	WASTE, REFUSE
	RIPRAP
	P-STONE
	BEDROCK
	SWAMP
	TOPSOIL
	ASPHALT
	CONCRETE
	EAST LAGOON LINER
	BRICK MASONRY
	RIGID INSULATION
	WOOD, ROUGH NON-BATT INSULATION
	CONTINUOUS
	ROCK SURFACE
	EARTH SURFACE
	GRATING

**ARCHITECTURAL**



**MISCELLANEOUS**



№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	MRT

**NOTES:**

- THIS IS A STANDARD LEGEND LIST, THEREFORE SOME SYMBOLS OR ABBREVIATIONS MAY APPEAR ON THIS LIST AND NOT ON THE DRAWINGS.
- CONTACT ENGINEER FOR ABBREVIATIONS AND SYMBOLS NOT LISTED.



GENERAL MOTORS POWERTRAIN DIVISION  
BAY CITY OPERATION  
BAY CITY, MICHIGAN 48708-5460

PLANT ENGINEERING BUILDING No.	SHEET No.
PE-H-96	SH03
AS RECORDED MAY 2000	

**SCALE VERIFICATION**

THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved	

**DRAWING STATUS**

Status	Date	Initial

GM POWERTRAIN DIVISION  
BAY CITY, MICHIGAN

AS RECORDED

CIVIL, STRUCTURAL AND  
ARCHITECTURAL LEGEND




Source Reference:			
Project Manager:	Reviewed By:	Date:	
MRT	RLA	MAY 2000	
Scale:	Project N.:	Report N.:	Drawing N.:
NO SCALE	12610-10	016	G-03AR









NO	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	MRT




**CORNER BRACE**



**POST DETAILS**



**DOUBLE GATE**



**BARBED WIRE CORNER**

USE	FABRIC HEIGHT	O.D.*	LBS/FT	BOTTOM PLATE
INTERMEDIATE POSTS	BELOW 9'	2-1/2"	3.65	5"x5"x5/16"
CORNER, END, GATE AND BRACE POSTS	BELOW 9'	3"	5.79	7"x7"x3/8"
RAILS	ALL	1-3/4"	2.27	

\* CARBON STEEL PIPE - ASTM A-20, SCH 40

USE	LEAF WIDTH		FABRIC HGT	O.D.*		LBS/FT
	DOUBLE	MANGATE		DOUBLE	MANGATE	
GATE FRAME, STILES AND RAILS	2x8	2x4	6'	2"	2"	2.27
GATE POST:	16'	4'	6'	6"	4"	18.97/9.11

\* CARBON STEEL PIPE - SCHED. 40

**SITE FENCING AND GATES**

**REALM** Remediation and Liability Management Company, Inc.

**GM POWERTRAIN**  
GENERAL MOTORS POWERTRAIN DIVISION  
BAY CITY OPERATION  
BAY CITY, MICHIGAN 48708-5460

PLANT ENGINEERING BUILDING No. SHEET No.  
**PE-H-96 SH07**

**AS RECORDED JUNE 2000**

**SCALE VERIFICATION**

THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved

**DRAWING STATUS**

Status	Date	Initial

**GM POWERTRAIN DIVISION  
BAY CITY, MICHIGAN**


**AS RECORDED**

**CIVIL  
STANDARD DETAILS**


**ORA CONESTOGA-ROVERS & ASSOCIATES**

Source Reference:


Project Manager: MRT	Reviewed By: RLA	Date: JUNE 2000
Scale: AS SHOWN	Project N°: 12610-10	Report N°: 016 Drawing N°: G-07AR




**HANDRAIL DETAIL**



**HANDRAIL POST ANCHORAGE TO STEEL**




**FENCE POST ANCHORAGE TO STEEL**



**TYPICAL HAND RAIL JOINT  
TYPICAL FOR TOP AND MIDDLE RAILS**





№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	SEPTEMBER 2000	MRT

**LEGEND**

- HANDRAIL
- - - - - NEW FENCE
- - - - - ALL OTHER FENCES PREVIOUSLY SHOWN

**REALM** Remediation and Liability Management Company, Inc.

**GM POWERTRAIN**  
 GENERAL MOTORS POWERTRAIN DIVISION  
 BAY CITY OPERATION  
 BAY CITY, MICHIGAN 48708-5460

PLANT ENGINEERING BUILDING No. **PE-H-96** SHEET No. **SH08**  
**AS RECORDED SEPTEMBER 2000**

**SCALE VERIFICATION**  
 THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved

**DRAWING STATUS**








Status	Date	Initial

**GM POWERTRAIN DIVISION**  
**BAY CITY MICHIGAN**  
 AS RECORDED  
**FENCING**

**CRA CONESTOGA-ROVERS & ASSOCIATES**

Source Reference:  
 SPICER GROUP, SAGINAW, MICHIGAN, DRAWING D-352414, SEPTEMBER 2000

Project Manager: MRT	Reviewed By: AW	Date: JUNE 2000
Scale: 1"=100'	Project N°: 12610-10	Report N°: 016
		Drawing N°: G-08AR



№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	SEPTEMBER 2000	MRT



**GM POWERTRAIN**  
 GENERAL MOTORS POWERTRAIN DIVISION  
 BAY CITY OPERATION  
 BAY CITY, MICHIGAN 48708-5460

PLANT ENGINEERING BUILDING No.	SHEET No.
<b>PE-H-96</b>	<b>SH09</b>
<b>AS RECORDED SEPTEMBER 2000</b>	


SCALE VERIFICATION  
 THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved		
DRAWING STATUS		
Status	Date	Initial

<b>GM POWERTRAIN DIVISION</b>		
<b>BAY CITY MICHIGAN</b>		
<b>AS RECORDED</b>		
<b>DISTRIBUTION PIPING</b>		


**CRA CONESTOGA-ROVERS & ASSOCIATES**

Source Reference: SPICER GROUP, SAGINAW, MICHIGAN, DRAWING D352413 AND D352410, MAY 2000			
Project Manager: MRT	Reviewed By: MRT	Date: MAY 2000	
Scale: 1"=50'	Project N. #: 12610-10	Report N. #: 016	Drawing N. #: G-09AR



№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	MRT

NOTES:  
 1. FOR LEGEND SYMBOLS SEE DWG. G-03 AND G-04.  
 2. BENCHMARKS:  
 - CUT CROSS ON RIM OF STORM MANHOLE 292 - ELEV. 586.97 FT. AMSL  
 - SW CORNER WATER TOWER BASE - ELEV. 587.67 FT. AMSL  
 - SW CORNER ARCHIMEDES SCREW PUMP STATION - ELEV. 587.97 FT. AMSL



**REALM** Remediation and Liability Management Company, Inc.

**GM POWERTRAIN**  
 GENERAL MOTORS POWERTRAIN DIVISION  
 BAY CITY OPERATION  
 BAY CITY, MICHIGAN 48708-5460

PLANT ENGINEERING BUILDING No.	SHEET No.
<b>PE-H-96</b>	<b>SH10</b>
<b>AS RECORDED JUNE 2000</b>	

SCALE VERIFICATION  
 THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved

--	--

DRAWING STATUS


Status	Date	Initial

**GM POWERTRAIN DIVISION**  
**BAY CITY, MICHIGAN**  
 AS RECORDED  
 PRE-CONSTRUCTION  
 CONDITIONS

**CRA CONESTOGA-ROVERS & ASSOCIATES**


Source Reference:  
 CRA AP001, 12610R RAW OCTOBER 1999

Project Manager: MRT	Reviewed By: RLA	Date: JUNE 2000
Scale: 1"=100'	Project N. #: 12610-10	Report N. #: 016
		Drawing N. #: G-10AR



1. EXISTING CONDITIONS (SUBJECT TO FIELD VERIFICATION.)


STEP 1




1. CUT EXISTING CASING PIPE BELOW WELL CAP AND CUT EXISTING WELL PIPE APPROX. 6\"/>

2. REMOVE BOLLARDS

STEP 2




HDPE LINER PENETRATION DETAIL



1. ATTACH (WELD, USE STEEL OR PVC COUPLING), WELL PIPE EXTENSION PIECE AND TERMINATE WELL PIPE APPROX. 2\"/>

2. PROVIDE NEW WELL CAP.

STEP 3



1. ATTACH (WELD) CASING PIPE EXTENSION PIECE AND TERMINATE CASING PIPE APPROX. 4\"/>

2. PROVIDE NEW LOCKING CAP.

3. PROVIDE NEW CONCRETE APRON

4. INSTALL NEW CONCRETE FILLED BOLLARDS

STEP 4

NO	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	MRT



GENERAL MOTORS POWERTRAIN DIVISION  
BAY CITY OPERATION  
BAY CITY, MICHIGAN 48708-5460

PLANT ENGINEERING BUILDING No. SHEET No.  
**PE-H-96 SH15**

**AS RECORDED JUNE 2000**

SCALE VERIFICATION  
THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved

DRAWING STATUS		
Status	Date	Initial

**GM POWERTRAIN DIVISION  
BAY CITY MICHIGAN**

**REMEDIAL ACTION PLAN**



**WELL EXTENSION DETAILS**



Source Reference:

Project Manager: MRT	Reviewed By: MRT	Date: JUNE 2000
Scale: NTS	Project N°: 12610-10	Report N°: 016 Drawing N°: C-03AR





№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	MRT

NOTES:  
 1. FOR LEGEND SYMBOLS SEE DWG. G-03 AND G-04.  
 2. BENCHMARKS:  
 - CUT CROSS ON RIM OF STORM MANHOLE 292 - ELEV. 586.97 FT. AMSL  
 - SW CORNER WATER TOWER BASE - ELEV. 587.67 FT. AMSL  
 - SW CORNER ARCHIMEDES SCREW PUMP STATION - ELEV. 587.97 FT. AMSL

- LEGEND**
- MW501D ABANDONED MONITORING WELL
  - WP 3 ABANDONED EXTRACTION WELL
  - ✕ MSA2S DESTROYED OR LOST MONITORING WELL
  - ⊕ MW14S CUT OFF AND BURIED MONITORING WELL



PLANT ENGINEERING BUILDING No. PE-H-96	SHEET No. SH13
AS RECORDED JUNE 2000	

SCALE VERIFICATION  
 THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved

DRAWING STATUS

Status	Date	Initial


GM POWERTRAIN DIVISION  
 BAY CITY, MICHIGAN  
 AS RECORDED  
 MONITORING WELLS  
 ABANDONED



Source Reference: SPICER GROUP


Project Manager: MRT	Reviewed By: RLA	Date: JUNE 2000
Scale: 1"=150'	Project N : 12610-10	Report N : 016
		Drawing N : C-01AR





1. EXISTING CONDITIONS (SUBJECT TO FIELD VERIFICATION.)


STEP 1



1. CUT EXISTING CASING PIPE BELOW WELL CAP AND CUT EXISTING WELL PIPE APPROX. 6\"/>

2. REMOVE BOLLARDS


STEP 2



1. ATTACH (WELD, USE STEEL OR PVC COUPLING), WELL PIPE EXTENSION PIECE AND TERMINATE WELL PIPE APPROX. 2\"/>

2. PROVIDE NEW WELL CAP.

STEP 3




1. ATTACH (WELD) CASING PIPE EXTENSION PIECE AND TERMINATE CASING PIPE APPROX. 4\"/>

2. PROVIDE NEW LOCKING CAP.

3. PROVIDE NEW CONCRETE APRON

4. INSTALL NEW CONCRETE FILLED BOLLARDS

STEP 4



HDPE LINER PENETRATION DETAIL

№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	MRT



GENERAL MOTORS POWERTRAIN DIVISION  
BAY CITY OPERATION  
BAY CITY, MICHIGAN 48708-5460

PLANT ENGINEERING BUILDING No. SHEET No.  
**PE-H-96 SH15**

**AS RECORDED JUNE 2000**

SCALE VERIFICATION  
THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved

DRAWING STATUS		
Status	Date	Initial

**GM POWERTRAIN DIVISION  
BAY CITY MICHIGAN**

**REMEDIAL ACTION PLAN**


**WELL EXTENSION DETAILS**



Source Reference:

Project Manager: MRT	Reviewed By: MRT	Date: JUNE 2000
Scale: NTS	Project N: 12610-10	Report N: 016
		Drawing N: C-03AR





№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	SEPTEMBER 2000	MRT

NOTES:  
1. SEE DRAWING C-09 FOR EXTRACTION WELL DETAILS

LEGEND

	AIR EXTRACTION LINE
	GROUNDWATER EXTRACTION LINE



**GM POWERTRAIN**  
GENERAL MOTORS POWERTRAIN DIVISION  
BAY CITY OPERATION  
BAY CITY, MICHIGAN 48708-5460

PLANT ENGINEERING BUILDING No.	SHEET No.
PE-H-96	SH17
AS RECORDED SEPTEMBER 2000	

SCALE VERIFICATION

THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved

--	--

DRAWING STATUS

Status	Date	Initial

GM POWERTRAIN DIVISION  
BAY CITY MICHIGAN  
AS RECORDED  
GROUNDWATER EXTRACTION SYSTEM



Source Reference:  
SPICER GROUP, SAGINAW, MICHIGAN, DRAWING D352042, MAY 1999

Project Manager: MRT	Reviewed By: RLA	Date: JUNE 2000
Scale: 1"=60'	Project N. #: 12610-10	Report N. #: 016
		Drawing N. #: C-05AR

№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	SEPTEMBER 2000	MRT

SEE DRAWING E-10 FOR ELECTRICAL



PLANT ENGINEERING BUILDING No. SHEET No.  
**PE-H-96 SH18**  
 AS RECORDED SEPTEMBER 2000

SCALE VERIFICATION  
 THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved


DRAWING STATUS		
Status	Date	Initial

GM POWERTRAIN DIVISION  
 BAY CITY, MICHIGAN  
 AS RECORDED  
 GROUNDWATER EXTRACTION SYSTEM  
 DETAILS




Source Reference:

Project Manager: MRT	Reviewed By: RLA	Date: JUNE 2000
Scale: NTS	Project N °: 12610-10	Report N °: 016 Drawing N °: C-06AR




EXTRACTION WELL DETAIL  
 EW-1 TO EW-12


SECTION A  
 C-06




PRESSURE FILTER/REGULATOR MOUNTING DETAIL




AIR SUPPLY SCHEMATIC AT EAST LAGOON




PLAN EW-1 TO EW-12



SECTION A  
 C-05




SECTION B  
 TYPICAL  
 C-05




PIPE LAYOUT C  
 C-05


EXTRACTION WELL No.	EXTRACTION WELL ELEVATION SUMMARY						
	BOTTOM SCREEN ELEV. (AMSL)	TOP SCREEN ELEV. (AMSL)	PROPOSED FINISHED GRADE (AMSL)	TOTAL WELL DEPTH (FT)	NORTHING	EASTING	TOP I.C.U. (BASED ON MCH SURVEY) (AMSL)
EW-1	572.00	582.00	587.0e	15.00	11082.90	11169.05	573.3
EW-2	572.00	582.00	587.0e	15.00	11412.85	11164.37	574.0
EW-3	572.00	582.00	587.0e	15.00	11716.82	11166.09	572.0
EW-4	572.00	582.00	587.0e	15.00	11712.89	10991.27	573.0
EW-5	572.00	582.00	587.0e	15.00	11716.82	11302.96	574.4
EW-6	572.0	582.0	591.5	19.5	10882.30	10202.46	574.0
EW-7	572.0	582.0	589.3	17.3	11110.53	10315.92	573.0
EW-8	572.0	582.0	589.6	17.6	11295.32	10444.85	573.7
EW-9	572.0	582.0	589.3	17.3	11493.36	10521.46	574.0
EW-10	572.0	582.0	589.0	17.0	11598.64	10673.23	575.0
EW-11	575.0	585.0	592.0	17.0	11104.64	10464.00	577.5
EW-12	572.0	582.0	591.5	19.5	11098.01	10626.08	572.5




PLAN EXTRACTION WELL BASE SLAB




PLAN EW-13, EW-14 AND EW-15




PLAN OF CHAMBER AT BASE




PLAN OF CHAMBER




EW-3 & EW-11 WELL DETAIL




AIR SUPPLY SCHEMATIC AT MSA




EXTRACTION WELL PENETRATION DETAIL FOR EW-13, EW-14 AND EW-15




EXTRACTION WELL DETAIL EW-13, EW-14 AND EW-15 SECTION A



MSA AREA WELL VAULT DETAIL (TYPICAL)



TYPICAL WELL VAULT WITH FLOW METER (2)



TYPICAL ELECTRICAL VAULT (2)

EXTRACTION WELL No.	EXTRACTION WELL ELEVATION SUMMARY					
	TOP MANHOLE CASING (FT AMSL)	BOTTOM MANHOLE ELEV (FT AMSL)	TOTAL WELL DEPTH (FT)	DEPTH TO PUMP INLET (FT BTOC)	PUMP INLET ELEV (FT AMSL)	NORTHING EASTING
EW-13	587.80	571.1284	16.67	15.50	572.30	11666.81 10478.35
EW-14	586.00	569.502	16.50	15.08	570.92	11276.70 10293.17
EW-15	587.43	570.7615	16.67	15.67	571.76	10893.08 10082.45

No	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	SEPTEMBER 2000	MRT

SEE DRAWING E-1 to E-04 FOR ELECTRICAL



PLANT ENGINEERING BUILDING No. PE-H-96 SHEET No. SH19  
AS RECORDED SEPTEMBER 2000

SCALE VERIFICATION  
THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved


DRAWING STATUS		
Status	Date	Initial

GM POWERTRAIN DIVISION  
BAY CITY, MICHIGAN  
AS RECORDED  
GROUND EXTRACTION WELL  
13, 14 AND 15 DETAILS



Source Reference:

Project Manager: MRT	Reviewed By: RLA	Date: JUNE 2000
Scale: NTS	Project N°: 12610-10	Report N°: 016 Drawing N°: C-07AR



№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	SEPTEMBER 2000	MRT

**NOTES:**  
 1. FOR HDPE LINER ATTACHMENT TO THE TANK CONCRETE PAD FUEL STORAGE AREA SEE TYPICAL DETAILS DWG. C-17.  
 2. EXACT LOCATION AND INVERT EL. FOR 6"Ø HDPE RELIEF DRAIN WILL BE FINALIZED IN THE FIELD.



PLANT ENGINEERING BUILDING No.	SHEET No.
<b>PE-H-96</b>	<b>SH20</b>
<b>AS RECORDED SEPTEMBER 2000</b>	

SCALE VERIFICATION
THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.


Approved	
DRAWING STATUS	

Status	Date	Initial


**GM POWERTRAIN DIVISION**  
**BAY CITY MICHIGAN**  
 AS RECORDED  
 SITE CAPPING




Source Reference: NOVA CONSULTANTS, INC. SEPTEMBER 2000			
Project Manager: MRT	Reviewed By: AW	Date: JUNE 2000	
Scale: 1"=60'	Project N. #: 12610-10	Report N. #: 016	Drawing N. #: C-08AR




**DETAIL 1**  
N.T.S. C-12



**SECTION D**  
N.T.S. C-08



**SECTION A**  
N.T.S. C-08



**SECTION E**  
N.T.S. C-08

NO	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	SEPTEMBER 2000	MRT

**REALM** Remediation and Liability Management Company, Inc.

**GM POWERTRAIN**  
GENERAL MOTORS POWERTRAIN DIVISION  
BAY CITY OPERATION  
BAY CITY, MICHIGAN 48708-5460

PLANT ENGINEERING BUILDING No. SHEET No.  
**PE-H-96 SH21**  
AS RECORDED SEPTEMBER 2000

SCALE VERIFICATION  
THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved

DRAWING STATUS




Status	Date	Initial

**GM POWERTRAIN DIVISION**  
BAY CITY, MICHIGAN  
AS RECORDED  
CAP DETAILS

**CRA CONESTOGA-ROVERS & ASSOCIATES**

Source Reference:

Project Manager: MRT	Reviewed By: AW	Date: JUNE 2000
Scale: NO SCALE	Project N°: 12610-10	Report N°: 016
		Drawing N°: C-09AR



№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	MRT

**LEGEND**

	EXISTING ROADWAY
	EXISTING GUARDRAIL
	EXISTING ELECTRICAL CONDUIT
	NEW LIMIT OF HDPE LINER
	NEW GAS VENT SYSTEM
	NEW GAS VENT

**REALM** Remediation and Liability Management Company, Inc.

**GM POWERTRAIN**  
 GENERAL MOTORS POWERTRAIN DIVISION  
 BAY CITY OPERATION  
 BAY CITY, MICHIGAN 48708-5460

PLANT ENGINEERING BUILDING No. PE-H-96 SHEET No. SH22

AS RECORDED JUNE 2000

**SCALE VERIFICATION**  
 THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved

**DRAWING STATUS**

Status	Date	Initial


**GM POWERTRAIN DIVISION**  
 BAY CITY MICHIGAN  
 AS RECORDED  
 EAST LAGOON LINER PLAN

**ORA CONESTOGA-ROVERS & ASSOCIATES**


Source Reference: SPICER GROUP

Project Manager:	Reviewed By:	Date:
MRT	AW	JUNE 2000
Scale:	Project N.:	Report N.:
AS SHOWN	12610-10	016
		Drawing N.:
		C-10AR







DETAIL 6  
C-11  
HDPE LINER ATTACHMENT TO CONCRETE DETAIL  
N.T.S.



DETAIL 7  
C-12  
LINER ATTACHMENT TO EXISTING STRUCTURES TYPICAL DETAIL PLAN VIEW  
N.T.S.

DETAIL 8  
C-12  
HDPE LINER ATTACHMENT TO CONCRETE DETAIL  
N.T.S.



SECTION D  
C-12  
N.T.S.

NO	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	MRT

**REALM** Remediation and Liability Management Company, Inc.

**GM POWERTRAIN**  
GENERAL MOTORS POWERTRAIN DIVISION  
BAY CITY OPERATION  
BAY CITY, MICHIGAN 48708-5460

PLANT ENGINEERING BUILDING No. SHEET No.  
**PE-H-96 SH24**  
AS RECORDED JUNE 2000

SCALE VERIFICATION  
THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved

DRAWING STATUS

Status	Date	Initial


GM POWERTRAIN DIVISION  
BAY CITY, MICHIGAN  
AS RECORDED  
EAST LAGOON LINER DETAILS -  
2 OF 2

**CRA CONESTOGA-ROVERS & ASSOCIATES**

Source Reference:

Project Manager: MRT	Reviewed By: AW	Date: JUNE 2000
Scale: NOT TO SCALE	Project N°: 12610-10	Report N°: 016
		Drawing N°: C-12AR





No	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	MRT

**NOTES:**

- PAVEMENT FINAL ELEVATIONS AND GRADES WILL BE DETERMINED IN FIELD.
- ADJUST PAVEMENT TO MATCH EXISTING GRADES, MANHOLES AND STRUCTURES.
- FINAL LOCATION AND SPACING FOR SAWCUT AND CONSTRUCTION JOINTS WILL BE DETERMINED IN FIELD.



PLANT ENGINEERING BUILDING No. SHEET No.  
**PE-H-96 SH26**  
 AS RECORDED JUNE 2000

**SCALE VERIFICATION**  
 THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved

**DRAWING STATUS**


Status	Date	Initial

**GM POWERTRAIN DIVISION**  
 BAY CITY, MICHIGAN  
 AS RECORDED  
 WEST SUPPORT FACILITIES AREA  
 PAVEMENT PLAN



Source Reference:  
 SPICER GROUP, SAGINAW, MICHIGAN, DRAWING D352409, OCTOBER 1999

Project Manager: MRT	Reviewed By: RLA	Date: JUNE 2000
Scale: 1"=40'	Project N°: 12610-10	Report N°: 016
		Drawing N°: C-14AR



№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	MRT

NOTES:  
 1. PAVEMENT FINAL ELEVATIONS AND GRADES WILL BE DETERMINED IN FIELD.  
 2. ADJUST EXISTING MANHOLES AND STRUCTURES AS REQUIRED  
 3. FINAL LOCATION AND SPACING FOR SAWCUT AND CONSTRUCTION JOINTS TO BE DETERMINED IN FIELD



PLANT ENGINEERING BUILDING No. PE-H-96 SHEET No. SH27  
 AS RECORDED JUNE 2000

SCALE VERIFICATION  
 THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved

DRAWING STATUS


Status	Date	Initial

GM POWERTRAIN DIVISION  
 BAY CITY, MICHIGAN  
 AS RECORDED  
 EAST SUPPORT FACILITIES AREA  
 PAVEMENT PLAN




Source Reference:  
 SPICER GROUP, SAGINAW, MICHIGAN, DRAWING D352409 AND D352406, OCTOBER 1999


Project Manager: MRT	Reviewed By: RLA	Date: JUNE 2000
Scale: 1"=50'	Project N. #: 12610-10	Report N. #: 016
		Drawing N. #: C-15AR




DETAIL 10  
C-15  
**FLEXIBLE PAVEMENT DETAIL**  
N.T.S.



DETAIL 11  
S-03  
**RIGID PAVEMENT ISOLATION JOINT DETAIL**  
N.T.S.



DETAIL 12  
C-15  
**SAWCUT DETAIL**  
N.T.S.



DETAIL 13  
C-15  
**RIGID PAVEMENT CONSTRUCTION JOINT DETAIL**  
N.T.S.

NO	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	REVISED CONSTRUCTION JOINT DETAILS	APR 15/99	RLA
3	AS RECORDED	MAY 2000	MRT



PLANT ENGINEERING BUILDING No. SHEET No.  
**PE-H-96 SH28**  
AS RECORDED JUNE 2000

SCALE VERIFICATION  
THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved

DRAWING STATUS		
Status	Date	Initial

**GM POWERTRAIN DIVISION**  
BAY CITY, MICHIGAN  
AS RECORDED  
SUPPORT FACILITIES AREA DETAILS




Source Reference:

Project Manager: MRT	Reviewed By: RLA	Date: JUNE 2000
Scale: AS SHOWN	Project N°: 12610-10	Report N°: 016
		Drawing N°: C-16AR









DETAIL **D-3**  
S-01  
NTS

TYPICAL SECTION NOT ADJACENT DSM WALL




DETAIL **D-2**  
S-01  
NTS


TYPICAL SECTION ADJACENT TO DSM WALL




DETAIL **1**  
S-4  
NTS



DETAIL **2**  
S-4  
NTS



DETAIL **2**  
S-4  
NTS



DETAIL **1**  
S-4  
NTS

№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	MRT



GENERAL MOTORS POWERTRAIN DIVISION  
BAY CITY OPERATION  
BAY CITY, MICHIGAN 48708-5460

PLANT ENGINEERING BUILDING No. SHEET No.  
**PE-H-96 SH34**

AS RECORDED JUNE 2000

SCALE VERIFICATION  
THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved



DRAWING STATUS		
Status	Date	Initial

GM POWERTRAIN DIVISION  
BAY CITY, MICHIGAN

AS RECORDED  
SHEET PILING DETAILS  
SHEET 2 OF 2



Source Reference:			
Project Manager:	Reviewed By:	Date:	
MRT	RLA	JUNE 2000	
Scale:	Project N °:	Report N °:	Drawing N °:
AS SHOWN	12610-10	016	S-04AR



NO	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	MRT



PLANT ENGINEERING BUILDING No. PE-H-96 SHEET No. SH32  
 AS RECORDED JUNE 2000

SCALE VERIFICATION  
 THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.



Approved

DRAWING STATUS		
Status	Date	Initial

CROTTY STREET CHANNEL SITE  
 BAY CITY, MICHIGAN  
 AS RECORDED  
 SHEET PILING  
 PLAN AND PROFILE 10+50 - 25+46



Source Reference: SPICER GROUP, SAGINAW, MICHIGAN, DRAWING E23201, FEBRUARY 2000			
Project Manager: MRT	Reviewed By: RLA	Date: JUNE 2000	
Scale: 1"=50' 1"=10'	Project N°: 12610-10	Report N°: 016	Drawing N°: S-02AR



№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	MRT

**REALM** Remediation and Liability Management Company, Inc.

**GM POWERTRAIN**  
 GENERAL MOTORS POWERTRAIN DIVISION  
 BAY CITY OPERATION  
 BAY CITY, MICHIGAN 48708-5460

PLANT ENGINEERING BUILDING No. SHEET No.  
**PE-H-96 SH31**  
 AS RECORDED JUNE 2000

SCALE VERIFICATION  
 THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved

DRAWING STATUS


Status	Date	Initial

GM POWERTRAIN DIVISION  
 BAY CITY, MICHIGAN  
 AS RECORDED  
 SHEET PILING  
 PLAN AND PROFILE 1+00 - 12+78.87

**CRA CONESTOGA-ROVERS & ASSOCIATES**


Source Reference:  
 SPICER GROUP, SAGINAW, MICHIGAN, DRAWING D352408, JULY 1999

Project Manager: MRT	Reviewed By: RLA	Date: JUNE 2000
Scale: 1"=50' 1"=10'	Project N. #: 12610-10	Report N. #: 016 Drawing N. #: S-01AR




**DETAIL** D-1  
NTS S-1,S-2

**SECTION THROUGH DUAL WALL**



**DETAIL** 3  
NTS S-03



**DETAIL** 1  
NTS S-03

№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	MRT



PLANT ENGINEERING BUILDING No.	SHEET No.
<b>PE-H-96</b>	<b>SH33</b>
<b>AS RECORDED JUNE 2000</b>	

SCALE VERIFICATION  
THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved	

DRAWING STATUS		
Status	Date	Initial

**GM POWERTRAIN DIVISION**  
**BAY CITY, MICHIGAN**


AS RECORDED

**SHEET PILING DETAILS**  
**SHEET 1 OF 2**


<b>CRA CONESTOGA-ROVERS &amp; ASSOCIATES</b>			
Source Reference:			
Project Manager:	Reviewed By:	Date:	
MRT	RLA	JUNE 2000	
Scale:	Project N °:	Report N °:	Drawing N °:
AS SHOWN	12610-10	016	S-03AR



2000  
2001  
2002  
2003  
2004  
2005  
2006  
2007  
2008  
2009  
2010  
2011  
2012  
2013  
2014  
2015  
2016  
2017  
2018  
2019  
2020  
2021  
2022  
2023  
2024  
2025  
2026  
2027  
2028  
2029  
2030  
2031  
2032  
2033  
2034  
2035  
2036  
2037



2038  
2039  
2040  
2041  
2042  
2043  
2044  
2045  
2046  
2047  
2048  
2049  
2050  
2051  
2052  
2053  
2054  
2055  
2056  
2057  
2058  
2059  
2060  
2061  
2062  
2063  
2064  
2065  
2066  
2067  
2068  
2069  
2070  
2071  
2072  
2073  
2074  
2075



№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	JL

NOTES:  
1. POWER FEED FROM EXISTING PUMPING STATION CONTROL PANEL



PLANT ENGINEERING BUILDING NO. SHEET No.  
**PE-E-81 SH36**  
**AS RECORDED JUNE 2000**

SCALE VERIFICATION  
THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved





DRAWING STATUS		
Status	Date	Initial

**GM POWERTRAIN DIVISION**  
**BAY CITY, MICHIGAN**  
**AS RECORDED**  
**EQUIPMENT STORAGE AREA**  
**POWER DISTRIBUTION SH. 1 OF 3**



Source Reference:

Project Manager: MRT	Reviewed By: RLA	Date: JUNE 2000
Scale: NO SCALE	Project N°: 12610-10	Report N°: 016
		Drawing N°: E-02AR



MAJOR EQUIPMENT LIST				
FOR EW-6,7,8,9,10,11,12				
SYM	QTY	MANUFACTURER	PART NUMBER	DESCRIPTION
DP1	1	C-H	YS2024/LT2024S	100A, 18CCT 480V 3Ø 3W PANELBOARD
DS 2005	1	SQUARE-D	HUJ361	30A NON-FUSED DISCONNECT
FD2038, FD2051, FD2064, FD3000, FD3013, FD3026, FD3038	7	SQUARE-D	H362	60A DISCONNECT
LP2042, LP2056, LP2069	1	SQUARE-D	--	100A, 20cct, 120/240V, 3W
LP2042, LP2056, LP2069, LP3005, LP3018, LP3031, LP3043	7	SQUARE-D	NG0012L100CV/MH20/MHC20/S	100A, 12cct, 120/240V, 3W PANELBOARD, NEMA1
T2007	1	SQUARE-D	--	480:120/240 10 KVA LIGHTING TRANSFORMER

SEE DWG.12610-20(004)EL-ME003AME FOR MAJOR EQUIPMENT LIST OF EW-13, 14, 15

№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	REVISED AS REQUIRED	NOV 15/99	BFM
3	AS RECORDED	MAY 2000	BFM



PLANT ENGINEERING BUILDING No.	SHEET No.
<b>PE-E-81</b>	<b>SH37</b>
<b>AS RECORDED JUNE 2000</b>	

SCALE VERIFICATION  
THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved

DRAWING STATUS		
Status	Date	Initial

**GM POWERTRAIN DIVISION**  
**BAY CITY, MICHIGAN**

**AS RECORDED**

**EQUIPMENT STORAGE AREA**  
**POWER DISTRIBUTION SHEET 2 OF 3**






Source Reference:			
Project Manager:	Reviewed By:	Date:	
MRT	RLA	JUNE 2000	
Scale:	Project N.:	Report N.:	Drawing N.:
NO SCALE	12610-10	016	E-03AR

№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	FOR NEW EXTRACTION WELLS	NOV 15/99	BFM
3	REVISED FOR NEW EXTRACTION WELLS	NOV 30/99	BFM
4	AS RECORDED	MAY 2000	BFM

3100  
3101  
3102  
3103  
3104  
3105  
3106  
3107  
3108  
3109  
3110  
3111  
3112  
3113  
3114  
3115  
3116  
3117  
3118  
3119  
3120  
3121  
3122  
3123  
3124  
3125  
3126  
3127  
3128  
3129  
3130  
3131  
3132  
3133  
3134  
3135  
3136  
3137

3138  
3139  
3140  
3141  
3142  
3143  
3144  
3145  
3146  
3147  
3148  
3149  
3150  
3151  
3152  
3153  
3154  
3155  
3156  
3157  
3158  
3159  
3160  
3161  
3162  
3163  
3164  
3165  
3166  
3167  
3168  
3169  
3170  
3171  
3172  
3173  
3174  
3175



MAJOR EQUIPMENT LIST				
FOR EW-13, 14, 15				
SYM	QTY	MANUFACTURER	PART NUMBER	DESCRIPTION
FD3107,FD3122,FD3145	3	SQUARE-D	H361DS	30A DISC. WITH NEMA 4X ENCLOSURE
T3107,T3122,T3145	3	SQUARE-D	3S1F	480:120/240, 3kVA OUTDOOR LIGHTING TRANSFORMER
LP3112,LP3127,LP3150	3	SQUARE-D	NQ0012L100CV/MH20WP	100A, 12cct, 120/240V, 3W PANELBOARD, NEMA3R

EW-13, 14, 15 POWER DISTRIBUTION DIAGRAM



PLANT ENGINEERING BUILDING No. PE-E-81 SHEET No. SH38  
AS RECORDED JUNE 2000

SCALE VERIFICATION  
THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.



Approved

DRAWING STATUS		
Status	Date	Initial

GM POWERTRAIN DIVISION  
BAY CITY, MICHIGAN  
AS RECORDED  
EQUIPMENT STORAGE AREA  
POWER DISTRIBUTION SHEET 3 OF 3



Source Reference:			
Project Manager:	Reviewed By:	Date:	
MRT	RLA	JUNE 2000	
Scale:	Project N.:	Report N.:	Drawing N.:
NO SCALE	12610-10	016	E-04AR



№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	ADDITIONAL FOR NEW EXTRACTION WELLS	NOV 15/99	BFM
3	REVISED AS REQUIRED	DEC 06/99	BFM
4	AS RECORDED	MAY 2000	BFM



PLANT ENGINEERING BUILDING No. SHEET No.  
**PE-E-81** **SH39**  
 AS RECORDED JUNE 2000

SCALE VERIFICATION  
 THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

DRAWING STATUS		
Status	Date	Initial

GM POWERTRAIN DIVISION  
 BAY CITY, MICHIGAN  
 AS RECORDED  
 CONTROL SCHEMATIC  
 CP1



Source Reference:			
Project Manager:	Reviewed By:	Date:	
MRT	RLA	JUNE 2000	
Scale:	Project N.:	Report N.:	Drawing N.:
NO SCALE	12610-10	016	E-05AR


№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	ADDITIONAL FOR NEW EXTRACTION WELLS	NOV 15/99	BFM
3	REVISED AS REQUIRED	DEC 06/99	BFM
4	AS RECORDED	MAY 2000	BFM

**BILL OF MATERIAL** FOR EW-6, 7, 8, 9, 10, 11, 12


SYM	QTY	MANUFACTURER	PART NUMBER	DESCRIPTION
1	1	HOFFMAN	A-30HS2508LP	30x25x8 NEMA 4 ENCLOSURE
2	1	HOFFMAN	A-30P24	BACK PANEL
3	1	ALLEN-BRADLEY	1494V-DS30 #94V-RA1/1494V-W1	30A NON-FUSED DISCONNECT W/OPERATING HANDLE
4	8	ALLEN-BRADLEY	1492-FB1	1 POLE FUSE BLOCKS
5	1	INNOV. TECH. Inc.	HS-120-10A	TVSS-10A
6	1	SOLA	SLS-24-012	24VDC POWER SUPPLY
7	1	OMRON	H3CR-A-AC100-240	TIMER DELAY RELAY
8	1	OMRON	P2CF-11	RELAY BASE
9	1	PHONE TICS	SENSOPHONE2000	AUTODIALER/DATA LOGGER
10	1	SQUARE D	MTL375	SURGE SUPPRESSOR
11	1			GROUND BUSS
12	1	HUBBELL	SPECIF. GRADE	RECEPTACLE
13	1	ALLEN-BRADLEY	1492-H6	FUSED TERMINAL BLOCK
14	1	HUBBELL		TELEPHONE JACK
15	1	ALLEN-BRADLEY	100-A18ND3	IEC CONTACTOR 18A
16	1	ALLEN-BRADLEY	700HA32A1	DPDT 120V RELAY
17	1	ALLEN-BRADLEY	700HN125	RELAY BASE
18	1	ALLEN-BRADLEY	800T-J2A	3 POSITION SELECTOR SWITCH
19	1	ALLEN-BRADLEY	800T-P16G	PILOT LIGHT GREEN
20	1	ALLEN-BRADLEY	800T-P16R	PILOT LIGHT RED

**BILL OF MATERIAL** FOR EW-13, 14, 15

SYM	QTY	MANUFACTURER	PART NUMBER	DESCRIPTION
4	1	ALLEN-BRADLEY	1492-FB1	1 POLE FUSE BLOCK
7	1	OMRON	H3CR-A-AC100-240	TIMER DELAY RELAY
8	1	OMRON	P2CF-11	RELAY BASE
10	2	SQUARE D	MTL375	SURGE SUPPRESSOR
13	2	ALLEN-BRADLEY	1492-H6	FUSED TERMINAL BLOCK



**BACK PANEL  
LAYOUT**



**DOOR LAYOUT**

**GM POWERTRAIN**  
 GENERAL MOTORS POWERTRAIN DIVISION  
 BAY CITY OPERATION  
 BAY CITY, MICHIGAN 48708-5460

PLANT ENGINEERING BUILDING No. SHEET No.  
**PE-E-81 SH40**

**AS RECORDED JUNE 2000**

SCALE VERIFICATION  
 THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved \_\_\_\_\_

DRAWING STATUS

Status	Date	Initial

**GM POWERTRAIN DIVISION  
 BAY CITY, MICHIGAN**

AS RECORDED

EQUIPMENT STORAGE AREA  
 CONTROL PANEL LAYOUT (CP1)

**CRA CONESTOGA-ROVERS & ASSOCIATES**

Source Reference:

Project Manager: MRT	Reviewed By: RLA	Date: JUNE 2000
Scale: NO SCALE	Project N°: 12610-10	Report N°: 016 Drawing N°: E-06AR

No	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	JL

NOTES:  
 1. CONNECT TO EXISTING DISTRIBUTION PANEL BOARD IN RAW WATER FEED STATION.



PLANT ENGINEERING BUILDING No. SHEET No.  
**PE-E-81 SH41**  
 AS RECORDED JUNE 2000

SCALE VERIFICATION  
 THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.




Approved

DRAWING STATUS		
Status	Date	Initial


GM POWERTRAIN DIVISION  
 BAY CITY, MICHIGAN  
 AS RECORDED  
 LAGOON AREA  
 POWER DISTRIBUTION, SH. 1 OF 2



Source Reference:			
Project Manager: MRT	Reviewed By: RLA	Date: JUNE 2000	
Scale: NO SCALE	Project N°: 12610-10	Report N°: 016	Drawing N°: E-07AR









PULSE TO DATA LOGGER

\* FOR FUTURE USE

LOSS OF FLOW ALARM DELAY (FUTURE USE) \*



DATA LOGGER INPUT JUMPERS CONFIGURATION



№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	JL



PLANT ENGINEERING BUILDING NO.	SHEET No.
PE-E-81	SH43
AS RECORDED JUNE 2000	

SCALE VERIFICATION

THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

Approved

DRAWING STATUS		
Status	Date	Initial

GM POWERTRAIN DIVISION  
BAY CITY, MICHIGAN

AS RECORDED

CONTROL SCHEMATIC  
CP2




Source Reference:


Project Manager:	Reviewed By:	Date:	
MRT	RLA	JUNE 2000	
Scale:	Project N °:	Report N °:	Drawing N °:
NO SCALE	12610-10	016	E-09AR

№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	AS RECORDED	MAY 2000	JL

BILL OF MATERIAL				
SYM	QTY	MANUFACTURER	PART NUMBER	DESCRIPTION
1	1	HOFFMAN	A-30HS2508LP	30x25x8 NEMA 4 ENCLOSURE
2	1	HOFFMAN	A-30P24	BACK PANEL
3	1	ALLEN-BRADLEY	1494V-DS30 494V-RA1/1494V-W	30A NON-FUSED DISCONNECT W/OPERATING HANDLE
4	6	ALLEN-BRADLEY	1492-FB1	1 POLE FUSE BLOCKS
5	1	INOV. TECH. Inc.	HS-120-10A	TVSS-10A
6	1	SOLA	SLS-24-012	24VDC POWER SUPPLY
7	1	OMRON	H3CR-A-AC100-240	TIMER DELAY RELAY
8	1	OMRON	P2CF-11	RELAY BASE
9	1	PHONETICS	SENSOPHONE2000	AUTODIALER/DATA LOGGER
10	1	SQUARE D	MTL375	SURGE SUPPRESSOR
11	1			GROUND BUSS
12	1	HUBBELL	SPECIF. GRADE	RECEPTACLE
13	1	ALLEN-BRADLEY	1492-H6	FUSED TERMINAL BLOCK
14	1	HUBBELL		TELEPHONE JACK



**BACK PANEL  
LAYOUT**



**DOOR LAYOUT**



GENERAL MOTORS POWERTRAIN DIVISION  
BAY CITY OPERATION  
BAY CITY, MICHIGAN 48708-5460

PLANT ENGINEERING BUILDING No. PE-E-81 SHEET No. SH44

AS RECORDED JUNE 2000

SCALE VERIFICATION

THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.



Approved

DRAWING STATUS

Status	Date	Initial

GM POWERTRAIN DIVISION  
BAY CITY, MICHIGAN

AS RECORDED

EQUIPMENT STORAGE AREA  
CONTROL PANEL LAYOUT (CP2)




Source Reference:


Project Manager: MRT	Reviewed By: RLA	Date: JUNE 2000
Scale: NO SCALE	Project N. : 12610-10	Report N. : 016
		Drawing N. : E-10AR



№	Revision	Date	Initial
1	ISSUED FOR CONSTRUCTION	MAR 01/99	MRT
2	ADDITIONAL FOR NEW EXTRACTION WELLS	NOV 17/99	BFM
3	REVISED FOR NEW EXTRACTION WELLS	NOV 30/99	BFM
4	REVISED AS REQUIRED	DEC 06/99	BFM
5	AS RECORDED	MAY 2000	BFM




EXTRACTION WELL EW-11 BUILDING LAYOUT




- ① CONNECTOR: BURNDY CAT. No. YGLR29C34
- ② GROUND ROD: 3/4" DIA. x 10' LG.

GROUNDING DETAILS




SECTION B TYPICAL E-01

LIGHTING SCHEDULE				
SYM	QTY	MANUFACTURER	MODEL NUMBER	DESCRIPTION
A	1	HUBBELL	VG-15	150W INCANDESCENT



TYPICAL BUILDING LAYOUT (EW-13, 14, 15)


N.T.S



TYPICAL EQUIPMENT LAYOUT (EW-13, 14, 15)

N.T.S

NOTE: THE PVC JUNCTION BOX IS ONLY FOR EW-14.



SECTION C TYPICAL E-01



PLANT ENGINEERING BUILDING No. PE-E-81 SHEET No. SH46  
AS RECORDED JUNE 2000

SCALE VERIFICATION  
THIS BAR MEASURES 1" ON ORIGINAL. ADJUST SCALE ACCORDINGLY.

DRAWING STATUS		
Status	Date	Initial

GM POWERTRAIN DIVISION  
BAY CITY, MICHIGAN  
AS RECORDED  
BUILDING ELECTRICAL LAYOUT  
AND DETAILS



Source Reference:			
Project Manager:	Reviewed By:	Date:	
MRT	RLA	JUNE 2000	
Scale:	Project N.:	Report N.:	Drawing N.:
NTS	12610-10	016	E-12AR